VARSITY SUPPLY
COLLEGE SUPPLIES
1602 N. High St., Columbus, O.

GEORGE W HOLMAN
65-13 19 AVE
COLUMBUS
OHIO

TRIANGLE HOUSE

USE 7/8" RIVETS THRUOUT
wt. of floor = 450 plf.
clear width = 14' Stringers 6'-6" ℄ to ℄
Span 206
Stringer web = 44" deep 2(6x6 L's) + no coverplat
8 x 8 x 10" ties
8" centers
Assume wt. per sq. ft. stringer to be
8 x panel length

24	
48	
51	
66	
97	
98	
101	
102	
180	
58	
116	apply to bottle
117	stringer ft. beam
125	
128	

read over for stringer

DESIGNING AND DETAILING
OF
SIMPLE STEEL STRUCTURES

McGraw-Hill Book Co. Inc.

PUBLISHERS OF BOOKS FOR

Coal Age ▽ Electric Railway Journal
Electrical World ▽ Engineering News-Record
American Machinist ▽ The Contractor
Engineering & Mining Journal ▽ Power
Metallurgical & Chemical Engineering
Electrical Merchandising

DESIGNING AND DETAILING OF SIMPLE STEEL STRUCTURES

BY

CLYDE T. MORRIS, C.E.

PROFESSOR OF STRUCTURAL ENGINEERING, OHIO STATE UNIVERSITY, MEMBER OF THE AMERICAN SOCIETY OF CIVIL ENGINEERS, MEMBER AMERICAN SOCIETY FOR TESTING MATERIALS, MEMBER SOCIETY FOR THE PROMOTION OF ENGINEERING EDUCATION

THIRD EDITION
REVISED AND RESET

SECOND IMPRESSION

McGRAW-HILL BOOK COMPANY, INC.
239 WEST 39TH STREET. NEW YORK

LONDON: HILL PUBLISHING CO., LTD.
6 & 8 BOUVERIE ST., E. C.

1914

Copyright, 1914, by the
McGraw-Hill Book Company, Inc.

Copyright, 1909, by
CLYDE T. MORRIS

PREFACE TO THIRD EDITION

After four years use in the class room, the author has decided that the arrangement of the chapters could be improved and as he wished to include some additional material in the book, he has taken this opportunity to change the order of presentation of the different topics. The whole book has received careful revision and several of the chapters have been partially rewritten. A new chapter on highway bridges has been added together with a reprint of the Specifications for Steel Highway Bridges of the State Highway Department of Ohio. About half of the figures in the book have been redrawn and a number of new figures added and such errors as have been discovered in the text have been corrected.

CLYDE T. MORRIS.

COLUMBUS, Ohio,
March, 1914.

PREFACE TO FIRST EDITION

THE object sought in this book is to collect from the many larger and more exhaustive works on structural steel design, those parts which are applicable to simple structures, and which can be taken up in technical schools in the limited time usually allotted to the subject; and at the same time, to show by general cases and specific examples how the simple laws of statics may be applied to the details of steel structures with the object of producing details which are in accord with the stresses they have to transmit.

It is presumed that the student has already finished a course in stresses, and little time is given here to the methods of calculating the primary stresses in structures.

An effort has been made to make the nomenclature, throughout, conform to that used in "*Stresses in Structures*," by Prof. A. H. Heller, and a table is given so that the meaning of any letter or character in any formula can be at once determined by reference to it. In some cases where reference is made to another book, and a formula is taken bodily from it, the nomenclature of the original author is retained and the meaning of the letters given in connection.

Cross references to other articles in this book are indicated by figures in parentheses giving the article number, thus (14). References to other works on the subject are given in foot notes.

The author wishes to acknowledge his indebtedness to Mr. C. C. Heller for the privilege of using various manuscript notes and sketches, left at his death by Prof. A. H. Heller, which have formed the basis of many of the articles in this book.

It is hoped that by the illustrations given and the methods employed, the reasons will be made apparent for many of the details commonly employed in structural work, and which are many times put in by "rule of thumb" and too often without due consideration of the stresses they have to carry.

CLYDE T. MORRIS.

COLUMBUS, Ohio.
April 6, 1909.

NOTATION

A = total area of cross-section (square inches).
A_F = net area of one flange.
A_w = gross area of cross-section of web = th.
a = distance shown in the figure.
b = distance shown in the figure.
C = centrifugal force per pound.
C C_1 C_2 C' etc = Constants of integration.
c = distance shown in figure.
D = direct stress.
$D.L.$ = dead load or dead load stress.
d = distance from neutral axis to a parallel axis.
= depth between centers of gravity of the flanges of a girder.
= depth between centers of chords of a truss.
E = modulus of elasticity.
e = distance shown in the figure.
= eccentricity of application of load.
H = horizontal reaction.
h = depth of the web of a girder (inches).
I = moment of inertia.
k = distance shown in the figure.
k_1 = distance between centers of bearings at the top of post.
k_2 = distance between centers of bearings at the bottom of post.
L = total length.
$L.L.$ = live load or live load stress.
l_1 l_2 etc. = partial lengths.
M = moment about any point or bending moment.
N = number of panels.
P = concentrated load or force.
p = panel length.
R = reaction.
= resultant of two or more forces.

r = radius of gyration.
S = shear.
s = unit stress.
s_1 = maximum unit stress in extreme fiber.
s_c = unit stress in compression = $\frac{P}{A}$.
s_p = dead load unit stress.
s_L = live load unit stress.
s_t = unit stress in tension.
s_w = working unit stress.
t = thickness of web of plate girder.
V = vertical reaction due to horizontal forces.
v = distance perpendicular to the neutral axis.
W = total uniform load.
w = load per foot.
θ = angle shown in figure.
= angle with the vertical made by a diagonal truss member.

CONTENTS

CHAPTER I

PAGE

DESIGNING AND ESTIMATING 1

ART.

1. Classes of Structural Steel Work 1
2. Kinds of Shops 2
3. Proposals and Contracts 2
4. Designs and Estimates 3
5. Time Savers 8
6. Order of Estimating 9
7. Specifications 13
8. Stress Sheets and General Plans 14

CHAPTER II

RIVETING 16

9. Dimensions of Rivets 16
10. Rivet Holes 17
11. Driving Rivets 18
12. Proper Sizes of Rivets 20
13. Spacing of Rivets 20
14. Kinds of Joints 22
15. Theory of Riveting 23
16. Requirements for a Good Riveted Joint 27
17. Design of Riveted Connections 28
18. Examples of Riveted Joints 30
19. Net Sections of Tension Members 35
20. Eccentric Stresses in Riveted Connections 40
21. Showing Rivets on Drawings 43

CHAPTER III

MILL BUILDINGS 45

22. Roofs 45
23. Construction 45
24. Roof Coverings 45
25. Types of Trusses 46
26. Building Construction 48
27. Loads 50
28. Stresses 52
29. The Design of a Building 53

ART. PAGE
30. Purlins 53
31. The Trusses 57
32. Buildings with Columns 61
33. The Detail Drawings 65

CHAPTER IV

PLATE GIRDER BRIDGES 72
34. Construction and Uses 72
35. Stresses in Girders 73
36. The Web 73
37. The Flanges 75
38. Economic Depth 76
39. Stiffeners 78
40. Web Splices 79
41. Flange Riveting 80
42. Flange Splices 83
43. Design of a Stringer 84
44. Design of a Deck Plate Girder Bridge 90
45. Through Plate Girders 113

CHAPTER V

PIN CONNECTED BRIDGES 115
46. Construction 115
47. Types of Trusses 115
48. Loads 116
49. Tension Members 117
50. Compression Members 119
51. Lateral Systems 124
52. Design of a Pin Connected Railway Bridge 125
53. Dead Load 125
54. The Depth 125
55. Stresses 127
56. Design of Tension Members 129
57. Design of Compression Members 133
58. Design of the End Posts 140
59. The Portal Bracing 144
60. Design of Floor Beams 146
61. Top Lateral Bracing 151
62. Bottom Lateral Bracing 152
63. Shoes and Rollers 153
64. Estimate and Stress Sheet 154

CHAPTER VI

DETAILS OF PIN CONNECTED BRIDGES 159
65. Detail Drawings 159
66. Pins 159

ART. PAGE
67. Calculation of Pins ... 160
68. Camber ... 167
69. Details of a Riveted Tension Member ... 168
70. Location of Pins in Top Chord and End Posts ... 171
71. Lacing of Compression Members ... 173
72. Details of the Floor Beams ... 177

CHAPTER VII

HIGHWAY BRIDGES ... 182
73. Kinds of Bridges ... 182
74. Flooring Materials ... 183
75. Loads ... 184
76. Impact ... 185
77. Distribution of the Load ... 186
78. Calculation of Joists ... 186
79. Types of Steel Highway Bridges ... 191

CHAPTER VIII

MANUFACTURE AND ERECTION ... 193
80. Shop Operations ... 193
81. Erection ... 194
82. The Drafting Department ... 195
83. A Draftsman's Equipment ... 196
84. Ordering Material ... 200
85. Shop Drawings ... 203
86. Order of Procedure for a Pin Connected Bridge ... 211
87. Order of Procedure for a Plate Girder Bridge ... 213
88. Shop Bills ... 216
89. Shipment ... 218
90. Materials ... 219
91. Inspection ... 224

APPENDIX ... 225
General Specifications for Steel Highway Bridges, 1911, State Highway Department of Ohio ... 225

DESIGNING AND DETAILING OF SIMPLE STEEL STRUCTURES

CHAPTER I

DESIGNING AND ESTIMATING

1. Classes of Structural Steel Work. Ordinarily the term "structural steel" covers only the rolled steel used in structures, and does not include any castings or machinery; but in many classes of work, machinery is so intimately connected with the structure as to render the separate design of the two impossible.

The field of usefulness of steel in structural work is being constantly extended, and the problems of its design becoming more complex, especially for work in the more populous districts of the country.

The following is a list of the more important kinds of structural steel work:

Bridges for steam and electric railways and highways,
- I-Beam spans,
- Longitudinal trough floor spans,
- Through and deck plate girder spans,
- Combination bridges (wood and steel),
- Simple truss spans,
- Draw-bridges (swing, lift, rolling, bascule, etc.),
- Viaducts or trestles,
- Elevated railways,
- Arch bridges,
- Suspension bridges,

Turntables for locomotives,
Trainsheds,
Steel mill and factory buildings,

Steel roof trusses,
Grandstands,
Steel work for tall office buildings,
Stand pipes and elevated tanks and towers,
Steel canal lock gates,
Traveling crane girders,
Ore conveyor bridges,
Car unloaders,
Bins for ore, coal, coke, grain, etc.

2. Kinds of Shops. It may be said that no single plant in this country is well equipped for turning out all of the different kinds of structures enumerated in the preceding article. Some are confined to the manufacture of railway bridges, heavy highway bridges, and heavy building work, some to highway bridges and light building work, some to steel work for buildings, some shops are not equipped to make pin connected work and others cannot do girder work economically. Some shops are not fitted to handle reamed work. (10).

These facts are sometimes emphasized by the manufacturer in order that he may be allowed to make his own designs, but this should not be given too much weight by the purchaser, as all the usual forms of details can be executed in any shop fitted for the particular kind of work under consideration and there will seldom be any difference in price to the purchaser, unless the form of detail is an unusual one.

3. Proposals and Contracts. The requirements of various purchasers in regard to proposals and contracts are not at all uniform. The law requires that public officials advertise for proposals on public work, and any manufacturer who meets the requirements must be allowed to bid. The laws differ in the various states. Private corporations, companies, and individuals do not usually advertise for bids, but invite proposals from such manufacturers as they desire to compete for the work. They very seldom require the deposit of a certified check with the proposal to insure the signing of a contract by the successful bidder, or the furnishing of a bond to insure the fulfillment of the contract. The certified check and bond are usually required on public work.

If the purchaser does not furnish a design or plans of the

work, each manufacturer submits his own design with his proposal. This may be in accordance with specifications of his own or with some standard specifications. The letting of the contract then becomes a question not only of the lowest bid but also of the most desirable design. Usually the manufacturer submits only a stress and section sheet, commonly called a strain sheet, but sometimes " show " plans, showing the general appearance of the structure and some details of construction are also submitted with the strain sheet. Show plans are frequently nothing more than ornamental drawings on which the lettering and shade lines play an important part.

Railroads and the more populous counties and large cities have bridge engineering departments which prepare plans for their bridges. These, together with standard specifications, are submitted to the contractors who then all bid on the same plan. As a rule this method is more satisfactory than the other because the purchaser's engineer has the purchaser's interests uppermost in his mind and also he can usually devote more time to the study of peculiar conditions surrounding a particular job than can the contractor's engineer, who must limit the time spent on the design because there is no assurance that the contractor will secure the work.

4. Designs and Estimates. When an improvement is contemplated the purchaser should employ someone who is competent to prepare plans and specifications and estimates of cost of the proposed work. Also, before making a proposal, the manufacturer must make an estimate of cost, and if no plans are submitted by the purchaser on which to base the proposal, he must also prepare a design and plans to accompany his bid. In either case the method of procedure in making the designs and estimates will be essentially the same. In the case of the manufacturer this work is done by the estimating department.

Designs and estimates must frequently be prepared upon the shortest notice by the contractor's estimating department, and in any case they must be completed before the time set for receiving bids. Certain methods of doing the work of the estimating department are of the highest importance, as they save time and reduce the liability of errors.

Proposals for bridge work are asked for either " lump sum " or per pound. In case a lump sum price is required a very care-

ful estimate is necessary. Usually when a pound price is given, only an approximate estimate is made to give a general idea of the various quantities of materials involved.

The estimate of cost includes such items as the following:

Material,
  Steel from the mill (various shapes take different prices),
  Eye-bars,
  Castings,
  Buckle plates,
  Hand railing, etc.
  } In case these are not manufactured by the contractor in question.
Labor of manufacture,
  Shop labor,
  Drafting,
  General expense,
Freight, Haul,
Erection (staging and false work) Painting,
Lumber,
Sub-contract work as paving, masonry work, etc.

Before the cost estimate can be made, of course the various quantities of material required must be determined.

The data furnished for making the design, are frequently very meager but usually include specifications, profiles and maps of the location.

Before starting on a design and estimate, the first thing the designer has to do is to familiarize himself with the requirements and conditions to be met. Of these requirements the specification is often the only one of importance, although in some cases other matters may demand more study. *The specification* is a guide giving the kind of material to use, the loads to be assumed as acting on the structure, the unit stresses allowed, the kinds of details desired, the quality of the workmanship, etc. These will be discussed more fully in Art. 7.

If the *design* is to go in competition with others it is important that it be an *economical* one, that is, the weight must generally be as small as possible and still meet the requirements of the specifications. This is of course important to the purchaser in any case. Designing of structures is not such an exact science that it may be said that all material in excess of what is required

to take the calculated stresses is wasted, but the lightest structure is generally the cheapest and usually the *price* is the most important determining factor in selecting a design. Each case must, however, be treated according to the peculiar conditions surrounding it. *Only engineers of experience can design really economic structures.* This question is an important one because it is a matter of producing a structure to perform a certain function safely and at a minimum cost.

No two estimating departments use exactly the same methods. The following will give the essential points.

In order that the important requirements of the specification may be easily found they may be underscored on the first


FORM No. 3

THE OHIO STATE BRIDGE COMPANY

Sheet No._____ Made by_____ Date_____

Estimate for_____

MEM.	No.	SIZE	Length	Wt. P Ft.	WEIGHTS					TOTAL

FIG. 1.

reading, or an *abstract* made omitting such parts as are common to all specifications and such parts as do not affect the design. If a blank form is used for this abstract it will be better for reference. Calculations should be kept in some permanent form for future reference, the name of the structure and the date being prominently indicated.

The information used in making estimates of weight and cost, and stress and section sheets, is set down on blank forms called estimate sheets. If the estimate is from plans giving more or less detail, a form like Fig. 1 may be used. If a design is made in connection with the estimate, blanks like Figs. 2 and 3 are used. The usual size of these is $8\frac{1}{2} \times 14$ inches.

On the form shown in Fig. 2, in the space at the top, should

be shown a single line diagram of the structure, properly lettered.



FORM No. 1

THE OHIO STATE BRIDGE COMPANY

Sheet No. ____ Made by _____ Date _____

Estimate for _____

Span Extreme	Span C. to C.	Estimated DL per ft. Steel	Total Steel
Roadway	Panels at	Floor & Track	Steel per ft.
Sidewalk	Depth C. to C.	Total	Total Lumber
Capacity Trusses	Length of Diag.	Panel Load per Truss DL	
Capacity Floor		" " " " LL	
Specifications	Sec. Tg.		

MEM	DL Stress	LL Stress	Impact	Total Stress	Unit Stress	Req. Area	MATERIAL	Actual Area	No. Pcs.	Wt. P. Ft.	Length	WEIGHT

The form shown in Fig. 3 is to be used in connection with this one.

FIG. 2.



FORM No. 2

THE OHIO STATE BRIDGE COMPANY

Sheet No. _____ Made by _____ Date _____

Estimate for _____

MEM	DL Stress	LL Stress	Impact	Total Stress	Unit Stress	Req. Area	MATERIAL	Actual Area	No. Pcs.	Wt. P. Ft.	Length	WEIGHT

This form is used in connection with the one shown in Fig. 2.

FIG. 3.

(For example see page 154.) This form also has places for the principal data upon which the design is based, stresses, make

up and areas of members and their estimated weights. This form is used for sheet No. 1 of the estimate. For the following sheets the form of Fig. 3 is used, which is similar to the lower part of Fig. 2.

An estimate should give within a few percent, the actual quantities of the various materials which will be required to make the structure. An estimator must, therefore, not only know how to obtain the weights of main members, but he must be thoroughly familiar with detailing.

Unless the estimate is made from plans giving details, or is for a plate girder bridge, or some such simple structure, the details are not all set down, but are lumped as a percentage of the main parts. A convenient way of doing this, for pin connected trusses, is to make the details of each member, a percentage of the rest of the member, and for riveted trusses, a percentage of the balance of the whole truss. Of course these percentages will vary with the specifications and form of truss, and must be determined by making an estimate of the details, or by taking them from previous estimates in which the details have been estimated.

An estimating department accumulates, in time, many valuable tables, such as tables of standard connections, joists, rivet and pin values, portal stresses, properties of columns, moment tables, etc., which save much time. Much valuable information is given in the handbooks published by mills rolling structural steel shapes. Those gotten out by the Carnegie Steel Co. and the Cambria Steel Co. are the most complete. Since they give the properties of all rolled shapes, one of them is indispensable in making designs and estimates. Combinations of shapes are frequently used for compression members and girders. Since it is necessary to know the radius of gyration or moment of inertia of these and the location of the neutral axes, and since calculating these involves considerable labor, there should be some systematic method of making the calculations and of preserving the results for future reference. There are several sets of tables published, giving the properties of builtup sections, and one of these will be a great help in designing.[1]

[1] "Osborn's Tables," by Frank C. Osborn.
"Properties of Steel Sections," by John C. Sample.
"Godfrey's Tables," by Edward Godfrey.

5. Time Savers. Besides the books and tables above referred to there are several instruments, the use of which will save much time and mental effort and reduce mistakes to a minimum.

The most important of these is the *slide rule*. It is, in fact, indispensable in this sort of work. *Thacher's cylindrical slide rule* or the *Fuller rule* are more accurate than is necessary for the ordinary work of the estimating department. A rule which will give results with a maximum error of one in two hundred is sufficiently accurate for all ordinary purposes. The Thacher rule is, of course, very convenient when more refined work is desired. It will give results with a maximum error of about one in ten thousand.

The ordinary ten-inch *Manheim rule* will answer very well, but one which will give the product of three numbers at one setting is very convenient. In getting weights, the number of pieces, the weight per foot and the length are multiplied together. There are several rules on which this operation can be performed at one setting. The "*Duplex*" rule is one. This rule is ten inches long and the setting is made on one face and the result read on the other by means of a runner. On the "*Engineer's Slide Rule*" the entire operation is performed on one face at one setting. This rule is twenty-four inches long and has no runner. The great advantage of this rule, aside from its three multiple feature, is the ease with which it may be read. There are only a few more divisions in the twenty-four inches than are given on the other rules in ten inches, and consequently the continued use of the rule is not nearly so trying on the eyes. The degree of accuracy is not much greater than that of the ten-inch rules. The maximum error of operations on the three multiple face is about one in two hundred. On the other face of the rule is an ordinary slide rule with scales twenty-four inches long, which gives results within one in five hundred with the same ease on the eyes.

Care should be taken to select a rule which works easily but not loosely, and one in which the graduations on the slide correspond with those on the rule. The trial of a few simple numbers will be a sufficient test of its accuracy. For instance, when the 1 and 2 are set opposite the following multiples should also read *exactly* opposite: 2 to 4, 2.5 to 5, 3 to 6, etc. A rule with a white celluloid face is preferable.

The scales on the slide rule being logarithmic, problems involving multiplication, division, powers and roots can be solved by its use. The books of instruction, which accompany the rules, explain their use fully, but the method of operation can easily be discovered by trial with simple problems. Some definite method of operation should be adopted and always followed, to save time, so that it will be unnecessary to reason out the process each time a multiplication is performed. Most problems may be resolved into the simple form of $\frac{ax}{b}=Ans.$, and for these the following simple rule is convenient: "*Keep the DIVISOR on the SLIDE and read the ANSWER on the OUTSIDE.*" Of course, any one of the three factors may be unity, which provides for simple multiplication and division.

The decimal point is best located by inspection after the result has been set down.

If many estimates are made in one office, it should be provided with some kind of an *adding machine*. There are several such machines manufactured in this and other countries. An elaborate machine, such as is used in banks and clearing houses, is not necessary. The "Computometer" is an excellent machine but is somewhat expensive. A small instrument like the "Rapid Computer" is not so expensive and will answer very well.

6. Order of Estimating. It is, of course, very important that all multiplications and additions be correct within certain limits, and every check possible should be employed. *It is also very important that no omissions are made.* The best way to insure reliable results and at the same time secure speed in estimating, is to follow some fixed order of performing the work and some definite form of setting it down.

The following forms have been used by the author and will serve as illustrations:

ORDER OF ESTIMATING RAILWAY BRIDGES

Truss Memb.-Web Diag.
Web Vert.
Bot. Chord
Top Chord

Total Truss Memb.
Pins, Pin Nuts.
Shoes & Mas. Pls.
Rollers & Frames.
Int. Floor Bms.
End Floor Bms.
Int. Stringers.
End Stringers.
Stringer Pedestals.
Stringer Cross Frames.
Stringer Laterals.
Bottom Laterals.
Top Laterals.
Portals—Rods—Knees.
Top Struts.
Sub Struts.
Sway Rods—Knees.
Top & Bot. Struts-Deck Br.
Bot. End Struts.
Longitudinal Struts.
Castings; Lead.
Bolts & Spikes.

Total Iron & Steel.

Timber ft. B. M.
Furnished by.
Placed by.
Tie Plates.
Specifications.
Paint—Shop, Field.
Material.
Reaming.
Inspection by
Transportation.
Haul.
Removal.
Erection.
Bid f. o. b. or Erected.
Certified Check.
Bond.
Penalty.
Time of Completion.
Bid Due.
Substructure.

ORDER OF ESTIMATING HIGHWAY BRIDGES.

Truss Memb.-Web. Diag.
Web Vert.
Bot. Chord
Top Chord

Total Truss Memb.
Pins, Pin Nuts,
Shoes & Mas. Pls.
Rollers & Frames.
End Fl. Bms. } Hanger Pls.
Int. Fl. Bms. } Lat. Con. &c.
Sidewalk Brackets.
Fl. Bm. Hangers.
Bot. Laterals } Connections,
Top Laterals } Pins, &c.
Portals—Rods—Knees.
Top Struts.
Sub Struts.
Sway Rods—Knees.
Fl. Bm. Knees—Low Trusses.
Top & Bot. Struts-Deck Br.
Bot. End Struts.
Longitudinal Struts.
Steel Joist—I Bms.
Facia, Curbs.
St. Ry., Exp. Joints.
Castings.
Bolts & Spikes.

Total Iron & Steel.

Lumber ft. B.M.
Buckle Pls.
St. Ry. Rails-furnished by.
Laid by.
Hand Railing.
C. I. Newel Posts.
Cresting, Ornaments.
Latticed Hub Guard.
Wood Fence.
Paving-Roadways & S. W.
Specifications.
Paint—Shop, Field.
Material.
Reaming.
Inspection by.
Freight.
Haul.
Removal.
Erection.
Bid. f. o. b. or Erected.
Certified Check.
Bond.
Penalty.
Payment.
Time of Completion.
Bid Due.
Substructure.

ORDER OF ESTIMATING STEEL BUILDINGS.

Trusses—Main, Vent., Knees.
Lean-to.
Special.
Hip & Valley Rafters, etc.
Columns—Main.
Clearstory.
Crane.
Lean-to.
End.
Floor.
Struts—Latticed Eave.
Side, End, Vent.
Special.
Ties—Bottom Chord.
Special.
Ventilator Knees.
Roof Purlins—Main, Vent.
Lean-to, Special.
Purlins—Side.
End, Gable.
Finish Angles—Main Roof.
Vent. Roof.
Lean-to Roof.
Rods—Rafter, Main, Vent.,
Lean-to.
Bottom Chord.
Side Sways.
End Sways.
Sag Ties.
Anchor Bolts—Bolts, &c.
Crane Girders—Brackets.
Floor Girders—Joist.
Floor Plate.
Stairs—Tracks for Doors, &c.

Total Steel in Bldg.

Crane Rail-Clips & Fastenings.
Corrugated Iron—Roof.
Sides.
Ridge Cap—Flashing.
Gutters—Down spouts.
Slate, Felt, Tin, Cornice, &c.
Louvers.
Wood Purlins, Nailing Strips.
Sheeting ft. B. M.
Skylights—No. & size—Glazing.
Windows—No. & size—Glazing.
Doors.
Door Frames—Window Frames.
Skylight Frames.
Railings.
Circular Ventilators.
Brick Walls & Foundations.
Specifications.
Materials.
Paint—Shop, Field.
Freight.
Haul.
Removal.
Erection.
Bid f. o. b. or Erected.
Certified Check.
Bond.
Penalty.
Time of Completion.
Bid Due.

7. Specifications. A specification is a set of rules for the guidance of the designer, the draftsman, the rolling mill, the shop, the erector and the inspector. It is a part of the contract [1] and all work is gotten out in accordance with some specification, and for bridges, generally in accordance with some standard specification. There are a number of bridge specifications which are published in pamphlet form for general use.

The following are some of the most used specifications for steel railway bridges:

"General Specifications for Steel Railroad Bridges" of the American Railway Engineering Association.

"General Specifications for Steel Railroad Bridges and Viaducts," by Theo. Cooper.

"General Specifications for Railway Bridges," by Edwin Thacher.

"General Specifications for Railway Bridge Superstructures," by The Osborn Engineering Company.

"General Specifications governing the Designing of Steel Railroad Bridges and Viaducts," by J. A. L. Waddell.

The general specifications for highway bridges usually include specifications for electric railway bridges because bridges frequently serve both purposes. The following are some of the more important of these:

"General Specifications for Steel Highway and Electric Railway Bridges and Viaducts," by Theo. Cooper.

"General Specifications for Highway Bridges," by Edwin Thacher.

"General Specifications for Highway Bridge Superstructures," by The Osborn Engineering Company.

"General Specifications governing the Designing of Highway Bridges and Viaducts," by J. A. L. Waddell.

Most railroads have standard specifications of their own. Manufacturers also have specifications which they use when no other is designated. The "Manufacturers' Standard Specifications," given in the various rolling mill hand books, cover only the material as rolled.

Specifications for bridges carrying electric railways, adopted

[1] See "Engineering Contracts and Specifications," by J. B. Johnson, for a complete discussion of the subject.

by the Massachusetts Railroad Commission, have been written by Prof. Geo. F. Swain.

The building codes of the various large cities are supposed to govern the design and erection of all buildings within their limits, but many of these are antiquated and cannot be applied to modern types of construction.

" General Specifications for Structural Work of Buildings " by C. C. Schneider, covers all types of modern building construction.

" General Specifications for Steel Roofs and Buildings," by Chas. Evan Fowler, refers only to mill building construction.

There are many points of similarity in all specifications, especially with regard to certain details. The tendency in the future will, no doubt, be towards more uniformity in all requirements for structures of the same kind. There is no more profitable study for the beginner, than the study of a number of standard specifications.[1] They give, among other things, the types of bridges to be used for different spans, clearances required, construction of the floor, loads to be used in calculating stresses of all kinds, unit stresses which must not be exceeded, details of construction such as lacing for compression members and rollers for expansion bearings, kind of workmanship required, quality of steel and timber to be used, requirements as to painting, inspection, testing, etc.

8. Stress Sheets and General Plans. These are made on tracing cloth and of some standard size. Each company usually has at least two standard sizes of drawings. The common sizes are $8\frac{1}{2}$ in.$\times$14 in., $11\frac{1}{2}$ in.$\times$18 in., and 24 in.$\times$36 in.

The *stress sheet* should show, on a single line diagram, stresses, make up of each member and its area, principal dimensions such as span length, panel lengths, depth and width, and complete general data. Live and dead load stresses should be given separately if the unit stresses are different. The maximum shear and maximum moment should be given for plate girders. It is also well to specify the pitch of rivets in the flanges of girders, and the number of rivets required in the end connections of floor beams and stringers. (See stress sheets Figs. 32, 55, and 69, pages 62, 112 and 158.

[1] For a comparison of the main features of a number of railway bridge specifications, see an article by Prof. A. H. Heller in Engineering News, Vol. 50, page 444.

Full general data should be given for reference. Under this head are included the specifications governing the design, the kind of steel, the location of the structure, the live and dead loads assumed, the grade, the alignment, the skew (if any), the construction of the floor, the distance from masonry to bridge seat, etc.

For bridges, the diagrams usually include an elevation, a half or full view of the upper and lower lateral systems, and end elevation and a cross section.

General plans may be simply "show" plans or plans giving more or less detail. The latter sometimes show practically everything except the rivet spacing and lengths of details.

CHAPTER II

RIVETING

RIVETS are used not only to connect members of riveted structures together, but also in all sorts of steel structures, to join parts of members built up of plates, angles, channels, etc., and for connecting details, such as pin plates, lacing bars and batten plates.

9. Dimensions of Rivets. Rivets are made in a machine, which upsets one end of a hot bar of steel or iron, forming the head, and cuts off enough of the bar to make a rivet of the desired length.

The size of a rivet is designated by the diameter of the shank, and its length under head, thus $\frac{3}{4}$ in. $\times 3\frac{1}{4}$ in.

"*Button heads,*" which are hemispherical are used where there is room for them. Their size depends upon the diameter of the rivet. Fig. 4 shows about the proportions which are used in structural work for "button heads" and countersunk rivets.



FIG. 4.

Fig. 5 gives the standard heads used by The American Bridge Company. It will be noted that the heads do not have spherical surfaces before driving. The cups on the riveting machine are supposed to have hollow spherical surfaces, so that the pressure will at first be concentrated on the center of the head when the rivet is being driven. This aids in upsetting the body of the rivet so that it will fill the hole.

The grip of a rivet is equal to the sum of the thicknesses of the pieces joined. The distance between the heads of a rivet will usually exceed the grip, on account of the roughness of the surfaces of the parts joined. Allowance is made for this in the length of the rivet used, which must be long enough so that

there will be sufficient metal to fill the hole and form the head. A table of lengths required for different grips is given in the



FIG. 5.

hand-books published by the various steel companies. (See "Cambria," page 294.)[1]

10. Rivet Holes. Holes for rivets are either *punched, sub-punched and reamed* or *drilled.* When reaming is required, the amount varies with different specifications from $\frac{1}{8}$ in. to $\frac{1}{4}$ in. That is, the diameter of the hole punched is from $\frac{1}{8}$ in. to $\frac{1}{4}$ in. smaller than the finished hole. The object of reaming is to remove the material surrounding the hole which is more or less injured in punching, and to insure a better *fit* and *matching of holes.* The injury done in punching is greater in thick material than in thin, and in medium steel than in soft steel. Hard steel is seldom used in structural work.



FIG. 6.

Where metal is used of greater thickness than the diameter of the rivets, it is usually drilled. Also some specifications require that all holes shall be drilled in certain cases.

The common practice is to use "*punched work*" for buildings and ordinary highway bridge work, with both soft and medium

[1] All references are made to the 1912 edition.

steel. For railway bridges the practice differs very much on different roads. Usually soft steel over $\frac{5}{8}$ in. thick, and all medium steel is required to be reamed. It is probable that the development of manufacture will be toward drilling all holes, which would assure a *fit* and *matching of parts* which cannot be attained with punched work. Even if it were possible to do punching accurately, the matching of holes would be difficult to attain because punching causes a piece to stretch, and the amount of stretch depends upon the thickness of the metal and the number of holes. For this reason, as shown in Fig. 7, it is necessary to ream all holes after the pieces are assembled, so that the rivets may be entered. This is usually done with a hand pneumatic reamer. *This reaming does not produce "reamed" work,* as only part of the injured metal around the hole is removed. Forcing round tapered pins, called "*drift pins,*" into the holes with sledges, instead of this reaming, *is not allowable* because it injures the metal. The use of drift pins however in assembling is not only permissible but is absolutely necessary.



FIG. 7.

11. Driving Rivets. Rivets are driven hot, and may be driven in three ways; by power riveting machines, by pneumatic hand hammers, or by hand. Wherever it is practical, rivets are driven by power riveters, because these produce *better results* at a *less cost.*

Power riveting machines are of two kinds, direct and indirect acting. The direct acting are the most satisfactory, as the full pressure may be held on the rivet as long as desired. In these machines the ram moves in the line of the final pressure throughout the stroke. In the indirect acting machines, the cups are held in jaws which are pivoted in the middle, the power being applied at one end of the arm and the rivet driven at the other. This causes the cup to rotate in the arc of a circle. Consequently the cups must be changed every time the grip of the rivet changes or else a lop-sided rivet head would result.

Machines using compressed air are the commonest, and are called *air riveters.* They are used as portable machines, being hung from cranes running on overhead tracks in the shop, and do very good work if of proper capacity and if the air pressure

is sufficient. A shop doing girder work should have a machine which will exert a pressure of from 50 to 60 tons. Hydraulic machines are the simplest and most reliable, but they must be used as stationary machines. Steam machines are also stationary, and these machines are therefore better adapted to riveting light pieces than large and heavy ones.

Rivets which must be driven in the field are usually driven by hand, but on large jobs power is sometimes used. There are generally a few shop rivets in every structure which cannot be driven by machine without taking the piece back, after an intermediate operation, like planing, has been performed. Such rivets are also usually driven by hand or with pneumatic hand hammers.

The use of the *pneumatic hammer reduces* hand riveting to very small proportions. This hammer strikes very rapidly. The blows are comparatively light ones, but very good rivets can be driven with it. Pneumatic hammers are often used for field riveting.

Rivets driven by power riveters or pneumatic hammers, through several thicknesses of plates, which are then planed off to the center of the rivet, will show so tight that it is difficult to see the line of demarcation between the rivet and the plates.

In hand riveting the end of the shank is hammered with hand hammers until it is upset roughly into the form of a head. A "*snap*," which is a hammer with a cup shaped face, is then held over it and struck with a sledge until the head is properly formed and the rivet is tight. The rivet is held in place while being driven by a "*dolly*," which is a steel bar with a cup shaped face which fits over the head of the rivet.

The heating of rivets is important, because overheating, or "burning" is injurious, as well as doing work on them at a "blue heat." The range of temperature at which wrought iron may be worked without injury, is greater than for steel, and therefore some specifications require that field rivets shall be of wrought iron. If a rivet is not properly heated it is almost certain to be a bad one. There are also times in a shop, when there is an unusual demand for power, and the pressure used for driving the rivets runs too low.

A loose rivet may be discovered by striking the rivet head a sharp blow with a light hammer specially made for the pur-

pose. An experienced inspector can detect loose rivets by the jar on the hand and the sound produced, even when no movement can be seen. Sometimes attempts are made to deceive inspectors by caulking the heads of loose rivets or by giving them several sharp blows with the riveting machine.

12. Proper Sizes of Rivets. The usual sizes of rivets, which are seldom departed from in structural work are $\frac{1}{2}$ in., $\frac{5}{8}$ in., $\frac{3}{4}$ in. and $\frac{7}{8}$ in. Rivets larger than $\frac{7}{8}$ in. in diameter *can not be driven tight by hand*, and in shops, it is not always possible to obtain sufficient power to drive them satisfactorily.

It is a common rule not to use a rivet diameter smaller than the thickness of the thickest plate through which it passes, because, although somewhat thicker plates can be punched, it is often expensive work on account of the breakage of punches. If thicker metal is used it must be drilled, and the result is that metal of greater thickness than about $\frac{7}{8}$ in. is avoided.

Tables giving the maximum size of rivet which can be driven in various sizes of structural shapes, and the location of the most desirable rivet center lines or " gages," are found in the handbooks published by the various steel companies.[1]

Generally it is best to use the largest size of rivet allowable in each piece, unless this would result in a number of sizes in one member, which would cause extra handling in the shop. Usually but one or two different diameters of rivets are used in an entire structure. When two different diameters of rivets are used in one member, the change should be made in such a manner that the two sizes of holes do not both come in any large pieces, as this would necessitate extra handling in punching. Although a $\frac{7}{8}$ inch rivet may be driven in a 3 inch leg of an angle, a $3\frac{1}{2}$ inch angle should be used to make an important connection with $\frac{7}{8}$ inch rivets.

13. Spacing of Rivets. Rivets are spaced according to practical rules which are almost universal. It is evident that rivet holes might be punched so closely together that the metal between them would be injured to such an extent that it would be of very little value. On the other hand the rivets might be so far apart that the parts joined would not be in close contact between rivets, leaving a space for water and dirt to lodge, causing rust which would buckle the parts and might develop

[1] See " Cambria," pages 44, 45, 46 and 298.

high local stresses. Rivets might also be placed so near the edge of a piece that the metal would tear out.

By "*pitch*" *of rivets* is usually meant the distance center to center, *parallel* to the line of stress, whether the rivets be in the same or in different rows. *End distances* are parallel to the line of stress and *side* distances are perpendicular to it. In Fig 8,

p = pitch. e = end distance. s = side distance. d = diameter of rivet. t = thickness of outside plate.



FIG. 8.

The following table gives the usual specified limits for rivet spacing, and Fig. 8 explains the terms used.

Diameter of Rivet in Inches. d	Min. Dist. Cen. to Cen. Specified in Inches. $3d$	Usual Min. Pitch for Single Line in Inches.	Maximum Pitch Specified.	Usual Maximum Pitch Used.	End Distance Specified in Inches. $2d$	End Distance Usually Used in Inches.	Side Distance Specified in Inches. $2d$	Side Distance Usually Used in Inches.
$\frac{1}{2}$	$1\frac{1}{2}$	$2\frac{1}{4}$	$16t$ or 6 in.	$16t$ or 6 in.	1	$1\frac{1}{4}$	1	1 or $1\frac{1}{4}$
$\frac{5}{8}$	$1\frac{7}{8}$	$2\frac{1}{2}$			$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{4}$
$\frac{3}{4}$	$2\frac{1}{4}$	$2\frac{1}{2}$			$1\frac{1}{2}$	$1\frac{1}{2}$	$1\frac{1}{2}$	$1\frac{1}{2}$
$\frac{7}{8}$	$2\frac{5}{8}$	3			$1\frac{3}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	$1\frac{1}{2}$

The minimum pitch in a double line may be less than in a single line, so long as the distance center to center of holes in any direction is not less than the minimum distance specified. It is not the usual practice to use the *least* allowable pitch unless there is a good reason for not avoiding it. For the maximum pitch $16t$ requires 4 in. for $\frac{1}{4}$ in. plates and 5 in. for $\frac{5}{16}$ in. plates. It is not good practice to exceed these pitches, but in some classes of work 6 in. is used as the maximum pitch for all thicknesses of plates. In the best classes of work, no metal is used in important parts, less than $\frac{3}{8}$ in. thick, in which case $16t = 6$ in.

The maximum pitch allowed perpendicular to the line of stress is usually about twice that allowed parallel to it, but this

is rarely used except in cover plates of compression members, in which case $40t$ is sometimes allowed.

At the ends of compression members, the pitch is usually 3 in. and should not exceed four times the diameter of the rivet for a distance equal to about twice the depth of the member. This is to insure a uniform distribution of the stress to the several component parts of the member.

The end distance should never be less than $1\frac{1}{2}$ times the diameter of the rivet, and it is usually specified 2 diameters. It should never exceed 8 times the diameter of the rivet.

In the location of rivets it is important to provide clearance for the riveting tool. This has a diameter about $\frac{3}{4}$ in. greater than the diameter of the head of the rivet, so that from the center of the rivet to the clearance line, the distance should be



FIG. 9.



FIG. 10.

at least one-half the diameter of the rivet head plus $\frac{3}{8}$ in. *In special cases* a riveting tool with one side cut off, requiring a clearance but little greater than half the diameter of the rivet head, may be used.

Some shops have multiple punches, which punch a number of holes at one operation, and are usually used in connection with a spacing table. Certain parts are punched on these punches and are not laid out by templet. There are limitations to the spacing which the table can make, and these must be kept in view in making the shop drawings.

14. Kinds of Joints. Figs. 9 to 14 show different kinds of riveted joints in plates, and different arrangements of rivets. It is evident that a lap joint is much weaker than a butt joint with two splice plates. In a lap joint there is a moment, having a lever arm equal to the sum of half the thicknesses of the plates. *If there were no deformation*, the resulting unit bending stress

in the plate would be three times the unit stress due to direct stress, but as the joint deforms the center lines of the plates approach each other, as shown in Figs. 9 and 10, and the moment is reduced. The bending of the plates will increase the tensile stress in the rivets, and successive changes of stress, if great enough would loosen them.

Butt joints with two splice plates should be used whenever possible.

15. Theory of Riveting. In spite of their importance, there is no rational working theory for designing riveted joints and



FIG. 11.



FIG. 12.



FIG. 13.



FIG. 14.

connections under stress. Therefore certain assumptions are usually made, which ordinarily render the design of riveted connections a very simple matter.

In a steam boiler or standpipe [1] the important point is to get a maximum efficiency of the joint, which requires that we have the same factor of safety in the net sections as in the rivets. This subject will not be considered here. In steel buildings and bridges it is simply a question of having, at any point, a sufficient number of rivets and a sufficient net area to take care of the stress at the point.

[1] For the design of standpipes, see Johnson's "Modern Framed Structures," Chapter XXVII, 8th edition.

The following assumptions are made in designing riveted joints:

1. That all rivets completely fill the holes into which they are driven.

2. That the rivets in a compression member take the place of the metal punched out, but that in a tension member the section is weakened because the net section through the rivet holes is less than the gross section.

3. That a rivet cannot safely carry a tensile stress, that is a stress pulling against its head.

4. That the friction between the parts joined should be neglected.

5. That the bending stress in the rivets may be neglected.

6. That the net section of a piece of steel will offer the same resistance *per square inch* as the gross section.

7. That the stress is equally distributed over the net section of the pieces joined in tension.

8. That the stress is equally distributed over all the rivets of a joint.

As stated above, these assumptions are not rational, but nevertheless they are universally used in designing riveted connections because they give results which are consistent with the results of tests.

These assumptions are largely interdependent and will be considered in detail.

If a rivet were perfectly driven, and the hole completely filled when the rivet was hot, it would contract in diameter in cooling. This contraction *precludes an intimate contact between the rivet and the walls of the hole*.[1]

Regardless of this fact *it is the universal practice* to proportion compression members for gross section, and tension members for net section. An allowance should, however, be made in compression members, for *open holes*, or holes for loose fitting bolts or pins. The allowance to be made in tension members will be treated in Art. 19.

Coincident with the contraction in diameter while cooling, the length between heads tends to decrease, and a tensile stress

[1] According to experiments by M. Considere in 1886, the space between the rivet and the side of the hole, varies from 0.002 to 0.02 inch. See Bulletin No. 62 American Railway Engineering Association, page 149.

is set up in the rivet. In addition to this stress, the metal which is being riveted together is compressed by the enormous pressure exerted by the riveting machine, and when this pressure is relieved, the metal tends to resume its unstrained form, and exerts a tensile stress on the rivet. This initial tension tends further to reduce the diameter of the cold rivet and cause a greater clearance between the rivet and the walls of the hole. The amount of the initial tensile stress on the rivet is a very uncertain quantity. *It sometimes requires a very little pull on the head of a rivet to break it off.* This is probably in part due to the heat treatment which it has received, making it nonhomogeneous. Nearly all specifications prohibit the use of rivets in direct tension, but they are nevertheless so used in certain connections, because the construction is usual and simple. In these connections there are usually stresses acting at right angles to each other, such as a shearing and a tensile stress. Bolts might be used to take the tension and rivets to take the shear, but rivets are generally used throughout.

Experiments indicate that the clearance between the rivet and the walls of the hole, allows a slip to take place when the friction between the parts is overcome.[1] Therefore *friction is the resisting force in a riveted joint*, so long as the stress is not great enough to produce slip. With good riveting and ordinary working stresses there is probably no slip,[2] nevertheless rivets are calculated to resist shearing off. If a proper working stress is used, the shearing strength of a rivet is a proper measure of the friction produced, because the friction depends upon the tension in the rivet, and that, as well as the shearing strength, depends upon the area of the cross section. In good work the slip is so small that a joint may safely be strained beyond the slipping point, if the stresses *do not alternate in direction.*[3]

Practically, it is considered of great importance, that the rivets should completely fill the holes into which they are driven. Since this is impossible it is not of so much importance so long as *sufficient friction* is produced between the parts joined. As

[1] See Johnson's "Materials of Construction," Article 375, also pages 3 and 4 of Bulletin No. 62 American Railway Engineering Association.

[2] Experiments indicate that slip occurs at a stress of from 11500 lbs. to 21900 lbs. per sq. in. of rivet cross section.

[3] See Bulletin No. 62 Am. Ry. Eng. Assoc., pages 3 and 4.

it requires great pressure to make a hot rivet fill the hole, especially when the holes in the parts joined do not come exactly opposite to each other, (see Fig. 7) this pressure is useful in bringing the parts into intimate contact, which *is necessary* to develop the friction.

If no slip occurs, *the only bending stress in a rivet is due to elastic deformation*, if any at all occurs. The longer the rivet the less the bending stress. Usually specifications require that the grip of a rivet shall not exceed from four to five times its diameter, on the supposition that the rivet transmits the stress. This requirement is necessary, because if the grip is great and the number of pieces to be riveted together is large, the pressure exerted by the riveting machine is not sufficient to bring the pieces into intimate contact and thus develop the friction.

When rivet holes are punched, some of the material immediately surrounding the hole is injured, also a riveting machine exerts an enormous pressure on the metal near the rivet, and may overstrain it. These might tend to reduce the permissible unit stress in tension on the net section,[1] but experiments show that where the section is suddenly reduced, as in a notched bar or in a section through rivet holes, the ultimate strength per square inch is increased by an amount which will more than equal the reduction due to injury.[2]

If then the distribution of stress over the net section through the rivet holes is uniform, as per the 7th assumption, *there is no reason why the allowable intensity of stress should not be as great as for a section without rivet holes.* If, however, the stress is unequally distributed, the maximum intensity will be greater than the 7th assumption will give.

There are a number of causes producing non-uniform distribution of stress over the net section through rivet holes. If two plates in tension be joined by several rows of rivets, and there is no slip, the stress is transmitted from one to the other by means of the friction at their surfaces of contact. This friction is greatest under the rivet heads, because the friction is produced by the tension in the rivets. Therefore the intensity

[1] See Proceedings of the Institute of Mechanical Engineers, August, 1887, page 326.

[2] See Proceedings of the Inst. of Mech. Eng., October, 1888, also see Heller's "Stresses in Structures," Art. 13.

of stress is greater under the rivet heads than half way between them. If the stress is tensile in the plates joined, the uniform distribution of stress will be interfered with, as in a notched bar.[1]

The result is, no doubt, a somewhat greater intensity of stress near the rivet holes than half way between them.

If the stress is not equal on all the rivets in a cross section, as per the 8th assumption, there may be a large variation in intensity of stress over the section. On this account *the rivets in a joint should be symmetrically disposed about the center lines of stress,* and eccentric stresses avoided wherever possible. If any of the rivets are defective, the result may be the same as that of an unsymmetrical distribution.

If the friction which is produced by the rivets is greatest under the rivet heads, the stress is transferred from one plate to the other in a series of increments. The stress in one plate increases, while that in the other decreases. The result is that the intensity of stress in the two plates at a cross section is not equal, and this tends to cause one plate to deform more than the other and thus throw more stress on the rivets at one end of the joint in one plate and upon those at the other end in the other plate. But the plates cannot deform unequally as long as there is no slip, so *there is no reason why there should not be a uniform distrubution of stress over the rivets,* as long as they are all in the same condition. This would require perfect workmanship.

16. Requirements for a Good Riveted Joint. From the discussion in Art. 15 the following conclusions may be drawn: A good riveted joint,

1. *Should be as compact as possible,* in order to render the uniform distribution of stress more certain.

2. *Should not be very large,* because the workmanship cannot be perfect, and there is the greatest danger of uneven distribution of stress in a joint having the largest number of rivets. With part of the rivets in a joint defective there may be eccentric stresses and overstrain, causing a redistribution of stress and probably overstrain in other members.

3. *Should have its rivets arranged symmetrically about the center lines of stress.*

[1] See Proceedings of the Inst. of Mech. Eng., October, 1888, also see Heller's "Stresses in Structures," Art. 13.

4. *Should have provision for unavoidable eccentric stresses* (see Art. 20).

5. *Should have rivets of good material, properly driven, under uniform conditions.*

6. *Should have a sufficient number of rivets so that there will be no slip if the stresses alternate in direction.*

7. *Should not have rivets in direct tension.*

17. Design of Riveted Connections. Riveted joints in structural steel work are always designed upon the supposition that the rivets carry the stress according to the assumptions given at the beginning of Art. 15.

According to these assumptions a joint may fail in the following ways:

1. By tearing the parts in tension through a line of rivet holes.

2. By tearing out the metal between the end of the piece and the last rivets.

3. By shearing the rivets on one cross section.

4. By shearing the rivets on two cross sections.

5. By crushing the rivet on one or more of the pieces of metal joined.

Provision against tearing through a line of rivet holes in tension members, will be treated in Art. 19.

The end distances usually specified and which are given in Art. 13, provide against tearing out at the ends.

If there is a tendency to shear off a rivet on one cross section, it is said to be in *single shear*, as in Figs. 9, 10 and 11. If there is a tendency to shear the rivet on two cross sections, it is said to be in *double shear*, as in Figs. 12, 13 and 14.

It is evident that if two plates be joined together, one of them might be so thin that the rivet would be crushed where it bears on the plate before sufficient stress is developed to shear the rivet off. As the safety against crushing depends upon the area of pressure or bearing, and this depends upon the thickness of the plate, a rivet is said to be in *bearing* on the plate.

Rivets are therefore proportioned for single shear, double shear or bearing. It is possible to have all of these to consider in a single joint.

In a lap joint the rivets are in single shear or bearing, depending on the thickness of the plates. In a butt joint with two

splice plates, the rivets are in bearing or double shear. The bearing may be either on the splice plates or on the main plate. The splice plates should always be made thick enough so that the bearing will be on the main plate. That is, each splice plate should be *more than* half as thick as the main plate.

There is no very definite relation, generally recognized, between the working stresses in tension, shear, and bearing. The working stresses for rivets should depend on experiments. Many specifications give a shearing unit equal to about three-fourths of the tension unit and a value in bearing double that in shearing.[1]

The value of a rivet in *single shear* is simply the product of the area of its cross section, by the working unit stress in shear. Thus the area of cross section of a $\frac{3}{4}$ in. rivet is 0.44 sq. in. and its value in *single shear* at a shearing unit of 7500 lbs. per sq. in. is $7500 \times 0.44 = 3300$ lbs. The value of a rivet in *double shear* is twice its value in single shear. The value of a rivet in *bearing* is taken as the product of the area in bearing by the working unit stress in bearing. The area in bearing is assumed to be the diameter of the rivet multiplied by the thickness of the piece against which it bears. Thus the value of a $\frac{7}{8}$ in. rivet in bearing on a $\frac{1}{2}$ in. plate at 15,000 lbs. per sq. in. is $\frac{1}{2} \times \frac{7}{8} \times 15{,}000 = 6562$ lbs. In designing riveted joints the strength of a rivet is always figured at its diameter before driving. Tables of values of rivets in shear and bearing for several different working stresses, are given in "Cambria," pages 292 and 293.

On account of the inferiority of *field driven* rivets an excess of from 25% to 50% over the requirements for power driven rivets is usually specified. The frictional resistance is much less with hand driven than with power driven rivets.

The value allowed for rivets with countersunk heads varies with different specifications. If the metal, in which the countersinking is done, is thick enough to give sufficient bearing below the countersunken part to develop single shear in the rivet, no reduction need be made from the value used for rivets with full heads. No reduction is usually made when the heads are only flattened. Rivet heads $\frac{1}{8}$ inch or less high are countersunk.

[1] For experiments on the ultimate resistance of steel and iron plates in bearing see Johnson's "Materials of Construction," Chapter XXVI.

18. Examples of Riveted Joints. A few examples of the usual forms of riveted joints will now be taken up. In all of the examples in the remainder of this chapter we will assume the following data:

Allowed shearing on rivets 7500 lbs. per sq. in.

Allowed bearing on rivets 15,000 lbs. per sq. in.

All rivets $\frac{7}{8}$ in. in diameter.

The values of rivets in single shear, double shear, and bearing, may be taken from " Cambria," pages 292 and 293.

Fig. 9. The rivets in this single lap joint will transmit $3\times4510=13{,}530$ lbs. in *single shear*, but if either of the plates be less than $\frac{3}{8}$ in. thick the value of the rivets in bearing on the plate will be less than the single shear value, and the amount of stress which the joint will transmit, will be less than 13,530 lbs. If the plates are $\frac{5}{16}$ in. thick, the rivets will transmit only $3\times4102=12{,}306$ lbs.

The zigzag line in the table in " Cambria," as explained at the bottom of the page, separates those bearing values which are less from those which are greater than single shear values.

Fig. 13. In this butt joint with two splice plates it is evident that the stress must go from the main plate on one side of the splice, to the rivets on that side, from these to the splice plates, from the splice plates to the rivets on the other side, and through them to the other main plate.

The rivets are in *double shear* if the plates are thick enough. From " Cambria " we find that the value of a $\frac{7}{8}$ in. rivet in bearing on a $\frac{11}{16}$ in. plate is equal to its value in double shear. If therefore the main plate is $\frac{11}{16}$ in. thick or thicker, and the thickness of each splice plate is sufficient to develop single shear in the rivets ($\frac{3}{8}$ in. or more), the rivets of the joint will transmit $7\times9020=63{,}140$ lbs. If the splice plates are only $\frac{5}{16}$ in. thick, for example, the rivets will transmit only $14\times4102=57{,}428$ lbs. As stated in Art. 17, the sum of the thickness of the splice plates should always be greater than the thickness of the main plate.

Fig. 15 shows the lower end of a post which resists, through the pin, the vertical component of the stress in the diagonal tension member. The post consists of two channels 12 in.$\times$25 lbs. The pin bears against the post in an upward direction, and it is necessary to reinforce the webs of the chan-

nels in order that the pin shall not crush them. Pins are figured in shearing, and bearing, exactly similar to rivets, and usually the same unit stresses are used. Pins must also be figured in bending, and this will be treated in Chapter VI.

Assuming the total stress on the post to be 175,000 lbs., the stress in each channel will be 87,500 lbs. The thickness of bearing on the pin, required to take this stress will be $\frac{87500}{4\frac{1}{2}\times 15000}=1.30$ in. The total thickness of pin plates required is 1.30 in. minus the



FIG. 15.

thickness of the channel web, which is 0.39 in. (See "Cambria," p. 162.) The pin plates must then be $1.30-0.39=0.91$ in. thick or say $\frac{15}{16}$ in., and may be made up of one $\frac{9}{16}$ in. and one $\frac{3}{8}$ in. plate as shown.

Enough rivets must be put through the pin plates to carry the stresses which they get from the pin to the web of the channel. The total stress 87,500 lbs. from the pin, is distributed over $2\frac{1}{16}$ inches thickness of bearing as follows:

$\frac{3}{8}$ in. channel web carries $\frac{6}{21}\times 87{,}500=25{,}000$ lbs.
$\frac{3}{8}$ in. pin plate carries $\frac{6}{21}\times 87{,}500=25{,}000$ lbs.
$\frac{9}{16}$ in. pin plate carries $\frac{9}{21}\times 87{,}500=37{,}500$ lbs.
Total $=87{,}500$ lbs.

There must be enough rivets through each pin plate to transmit its proportion of the stress to the channel web, and there must be enough rivets through the channel web to transmit to it all of the stress from both pin plates.

For that portion of the web which has a pin plate on each side, the rivets will be in bearing on the web, if the web is *not* thick enough to develop double shear in the rivets, and each rivet will transmit from each pin plate, one half the value of a rivet in bearing on the web. Therefore the number of rivets required through the thinner pin plate, will be found by dividing the stress carried by this plate, by one half the bearing value of a rivet on the web.

$$\frac{25000}{\frac{1}{2}\times 4920} = 11 \text{ rivets required through the } \tfrac{3}{8}\text{-in. pin plate.}$$

These 11 rivets will transmit the same amount of stress to the web, from the thicker plate on the other side of the web as from the thinner plate. In addition to these 11 rivets, there will be required through the thicker plate sufficient rivets to transfer the difference between the stresses in the two pin plates, to the web by single shear on the rivets.

$$37500 - 25000 = 12500 \text{ lbs.} \quad \frac{12500}{4510} = 3 \text{ rivets}$$

required through the $\frac{9}{16}$ in. pin plate, in addition to the 11 rivets through both.

It is better to have the pin plates on opposite sides of the web as shown, but if necessary, both plates may be put on the same side, in which case the number of rivets required through each would be determined by single shear, and these numbers would have to be added together to determine the total number required through the web, as none of the rivet values would be determined by bearing on the web, unless the web were not thick enough to develop single shear in the rivets.

In this example, the rivets below the pin have been counted, but it is evident that they can get no stress except by tension in the pin plates. No more stress can be transmitted to these rivets than can be carried by the net area of the pin plates at the sides of the pin hole.

Also usually, some of the rivets at a joint like this, have to be countersunk on account of clearances, in which case their values must be reduced according to the specifications used as stated in Art. 17.

Fig. 16 shows the top chord of a bridge at the hip joint. The chord section is made up as follows:



FIG. 16.

1 cover plate, 22 in. $\times \frac{3}{8}$ in.
2 web plates, 18 in. $\times \frac{9}{16}$ in.
2 top angles, $3\frac{1}{2}$ in. $\times 3\frac{1}{2}$ in. $\times \frac{3}{8}$ in.
2 bottom angles, 4 in. $\times 3\frac{1}{2}$ in. $\times \frac{5}{8}$ in.

We will assume a stress in this chord section of 420,000 lbs., and that the pin is 6 in. in diameter. This then will require

a bearing on the pin of $\frac{420000}{6\times15000}=4.67$ inches, or say $2\frac{3}{8}$ inches on each side. This bearing thickness may be made up as follows:

Web plate	$\frac{9}{16}$ in.
Inside pin plate	$\frac{3}{4}$ in.
Outside pin plate	$\frac{5}{8}$ in.
Outside pin plate	$\frac{7}{16}$ in.
Total, $2\frac{3}{8}$ in. $=\frac{38}{16}$ in.	

The stress will be distributed over the plates as follows:

$\frac{9}{16}$ in. web plate,	$\frac{9}{38}\times210{,}000=49{,}740$ lbs.
$\frac{3}{4}$ in. inside pin plate,	$\frac{12}{38}\times210{,}000=66{,}320$ lbs.
$\frac{5}{8}$ in. outside pin plate	$\frac{10}{38}\times210{,}000=55{,}260$ lbs.
$\frac{7}{16}$ in. outside pin plate	$\frac{7}{38}\times210{,}000=38{,}680$ lbs.
Total $=210{,}000$ lbs.	

The rivets in that portion of the web, covered by pin plates on both sides, will be in bearing on the web, the web not being thick enough to develop double shear in the rivets. The bearing value of a rivet on the $\frac{9}{16}$ in. web is 7383 lbs. The number of rivets required in the $\frac{7}{16}$ in. outside pin plate will be $\frac{38680}{\frac{1}{2}\times7383}=11$ rivets. The number required in the $\frac{3}{4}$ in. inside pin plate will be $\frac{66320}{\frac{1}{2}\times7383}=18$ rivets. More rivets than required are used in each of these plates, to insure a distribution of stress to the upper and lower rivets, and to give such an arrangement as will put the center of gravity of all the rivets as near as possible to the center line of stress.

The number of rivets through the outside pin plate between the angles, is determined by the single shear value of a rivet and is equal to $\frac{55260}{4510}=13$ rivets, all of which must be placed beyond the rivets required by the other two pin plates.

Strictly, the rivets passing through the top and bottom angles are in double shear, instead of bearing, because the angles

and web are both a part of the main chord section, and are held together by rivets beyond the pin plates. These together make up a thickness more than great enough to develop double shear in the rivets. A filler $\frac{1}{4}$ in. thick will be required in this case, under the $\frac{7}{16}$ in. outside pin plate, on the top angle. This filler, of course, takes no stress.

One outside pin plate, and all inside pin plates, should take rivets through the angles, in order that the stress may be distributed over the entire chord section, and to the top plate in particular.

This even distribution of the stress requires that the rivets in the ends of compression members, for a distance equal to about twice the depth, should be spaced closely together, as stated in Art. 13.

The design shown in Fig. 16 is not according to the best practice as the pin plates do not extend far enough back from the pin to perfectly distribute the load over the entire section. No pin plate should be shorter behind the pin than its width and some of the pin plates should extend at least double the width of the member back of the pin.[1]

Here, as in Fig. 15, some of the rivets usually have to be countersunk and their values must be reduced accordingly.

19. Net Sections of Tension Members. In a tension member it is not only necessary to have, in a connection or splice, a sufficient number of rivets, but there must also be a sufficient net area in the parts joined, and in the pieces joining them, to safely carry the stress. Therefore in tension members of a structure with riveted connections, there must be an excess of material, because the joints at their ends, and any splices in them, cannot be made as strong as the body of the member.

Fig. 17 shows a simple tension splice, so made that the net area is as great as possible, and the waste therefore, as small as possible. If the stress to be transmitted across the joint is 65,000 lbs., it will require $\frac{65000}{6560} = 10$ rivets in bearing on the $\frac{1}{2}$-inch plate on each side of the splice.

For getting net areas, the size of the rivet hole is always

[1]See Eng. News, Vol. 58, page 685 (December 26, 1907) and Vol. 65, pages 324 and 328, (March 16, 1911.)

taken as $\frac{1}{8}$ in. larger than the rivet, or 1 in. in diameter for a $\frac{7}{8}$-in. rivet. At the section AB, the net width of the main plate is 11 in. The net area therefore is $11\times\frac{1}{2}=5.5$ sq. in. If the allowed unit stress in tension is 12,000 lbs. per sq. in., this net area will transmit $5.5\times12{,}000=66{,}000$ lbs. Therefore there is sufficient net area at AB.

At the section CD the net area is $10\times\frac{1}{2}=5.0$ sq. in., which at 12,000 lbs. per sq. in. is good for 60,000 lbs. The rivet at T has reduced the stress carried by the main $\frac{1}{2}$ in. plate at CD to $65{,}000-\frac{1}{10}\times65{,}000=58{,}500$ lbs. There is then a little more net area on the line CD than is necessary to carry the stress.

The stress carried by the main $\frac{1}{2}$ in. plate at EF is $65{,}000-3\times6500=45{,}500$ lbs. The net section is $9\times\frac{1}{2}=4.5$



FIG. 17.

sq. in., which is good for 54,000 lbs. In like manner the stress in the main plate at GH is $65{,}000-6\times6500=26{,}000$ lbs., while the net section at GH is able to carry $8\times\frac{1}{2}\times12{,}000=48{,}000$ lbs.

The net area of the splice plates at any section must also be sufficient to carry the stress in them, without exceeding the allowed tension unit. At GH the stress in the two splice plates is 65,000 lbs. This will require a net area of $\frac{65000}{12000}=5.42$ sq.in. The net width of the plates at the point is $12-4=8$ in., which will give a required thickness of the two splice plates of $\frac{5.42}{8}=.68$ in. and hence each plate will have to be $\frac{3}{8}$ in. thick.

The stress carried by the splice plates at EF is $65{,}000-4\times6500=39{,}000$ lbs. The required net area is $\frac{39000}{12000}=3.25$ sq. in.,

which will require a net width of $\frac{3.25}{2\times\frac{3}{8}}=4.33$ in., or a gross width of $4.33+3=7.33$ in. The width of the splice plates may be reduced here some, but not in this case to the limit of 7.33 in. because this would not give sufficient edge distance beyond rivets *K* and *L*.

In figuring these net areas, only square sections have been taken. It is obvious that if the lines of rivets *GH* and *EF* for instance, are close enough together, the zigzag section *GKMPNLH* will have less net area than the square section *GH*. Experiments have been made on steel plates which seem to indicate that rupture will take place on the zigzag line unless its area exceeds the area on the square section by at least 30%,[1] and some specifications require net sections to be figured on this basis. Other and later experiments seem to show that rupture is equally probable on square or zigzag sections if the net areas are equal.[2] None of these experiments may be a good guide, because there is no doubt an entirely different distribution of stress after the elastic limit is exceeded than before, on account of the unequal deformation and distortion produced.

This is a difficult matter to investigate theoretically, and until further experiments are made, it is well to be liberal in allowances for rivet holes. In Fig. 17 the distance between the rivet lines *GH* and *EF* which would be necessary to give 30% excess to the zigzag line *GKLH* over the square section *GH*, is nearly 3 in., and if the transverse spacing were greater, this longitudinal distance would also have to be larger.

In nearly all cases in practice, the least area is taken, whether it be zigzag or square section, and no attention is paid to the 30% rule, unless specially required by the specifications.

Some specifications give a simple rule like the following: "The number of rivet holes to be allowed for in getting net section shall be the greatest number whose centers are $1\frac{3}{8}$ in.[3] or less from any possible square cross section." According to this rule the rows of rivets would have to be more than $2\frac{3}{4}$ in. apart, if the holes in but one row were to be deducted. This

[1] See articles by Prof. A. B. W. Kennedy in Trans. Inst. Mech. Eng., 1881, 1882, 1885 and 1888.

[2] See Engineering News, May 3, 1906, Vol. LV, page 488.

[3] Various specifications give the distance from $1\frac{3}{8}$ in. to $2\frac{1}{4}$ in.

rule is not a safe one to follow in all cases, as will be seen later.

A common case is that of an angle, which may be considered like a plate developed, as in Figs. 18, 19 and 20. The width of the plate will be equal to the sum of the legs of the angle less its thickness. There are four cases according as the angle has one, two, three, or four lines of rivets.

In getting the net area of an angle with one line of rivets, allowance is made for the area cut out by one hole; with two lines for one or two holes; with three lines for one, two, or three holes, and with four lines for one, two, three or four holes, depending upon the pitch and arrangement of the rivets. Fig. 18 represents a piece of an angle with one line of rivets in each leg in which the stagger of the holes in the two legs is $1\frac{3}{4}$ in., and



FIG. 18.

according to the practical rule above, the net section is equal to the gross section, less the area cut out by two holes, or $2.75-2\times\frac{1}{2}=1.75$ sq. in. It is evident that the holes cut out a large percentage of the material. The square section on AE has an area of $2.75-1\times\frac{1}{2}=2.25$ sq. in., while the zigzag area $ABCD$ is $(3.47-1+2\times\frac{3}{4})\times\frac{1}{2}=1.98$ sq. in., showing a deficiency in place of an excess in the zigzag area.

By working the problem in the other direction we can easily find the stagger of holes necessary to give us either an equal area or a 30% excess on the zigzag line, over the square section. In the case of Fig. 18, it would require the stagger to be at least $4\frac{7}{16}$ in. in order that only one hole need be deducted according to the 30% rule. This would make the holes in one line at least $8\frac{7}{8}$ in. apart.

The following table gives the necessary *stagger* of rivets in several sizes of angles with one line of rivets in each leg, to give

an equal area and 30% excess area on the zigzag section, compared with a square cross section through one hole. By this table we see that the areas given by the practical rule are not always safe.

Size of Angles in Inches.	Gage g Inches.	Size of Rivet in Inches.	Area through 1 Hole.	Stagger for Equal Area in Inches.	Area plus 30%	Stagger for 30% excess Area in Inches
$2\times2\times\frac{1}{4}$.....	$1\frac{1}{8}$	$\frac{5}{8}$	0.75	1.89	0.98	3.04
$2\frac{1}{2}\times2\frac{1}{2}\times\frac{1}{4}$.....	$1\frac{3}{8}$	$\frac{3}{4}$	0.97	2.26	1.26	3.78
$3\times3\times\frac{3}{8}$.....	$1\frac{3}{4}$	$\frac{7}{8}$	1.73	2.69	2.25	5.53
$3\frac{1}{2}\times3\frac{1}{2}\times\frac{3}{4}$.....	2	$\frac{7}{8}$	2.75	2.83	3.57	5.05
$4\times4\times\frac{1}{2}$.....	$2\frac{1}{4}$	$\frac{7}{8}$	3.25	3.00	4.22	5.68

In Fig. 19 the net area on EG is $4.5-1\times\frac{1}{2}=4.0$ sq. in. The net area on $EFCD$ is $\frac{1}{2}(3.81+1.5+4-2)=3.65$ sq. in. The



FIG. 19.

net area on $ABCD$ is $\frac{1}{2}(6.18+1.5+1.5-2)=3.59$ sq. in. The net area on $ABFCD$ is $\frac{1}{2}(3.81+1.5+3.91+1.5-3)=3.86$ sq. in. Failure would doubtless take place on $ABCD$ still, according to the 30% rule, three holes would have to be deducted. This would give a net area of only $4.5-3\times\frac{1}{2}=3.00$ sq. in. The best modern practice does not require the use of the 30% rule.

In Fig. 20 the area on AF is $5.75-1\times\frac{1}{2}=5.25$ sq. in. The area on ACG is $\frac{1}{2}(4+6.19+1.5-2)=4.84$ sq. in. The area on $ACDE$ is $\frac{1}{2}(1.5+3.9+6.19+1.5-3)=5.04$ sq. in. The area on $ABCDE$ is $\frac{1}{2}(1.5+3.9+3.81+3.9+1.5-4)=5.31$ sq. in. The area on ADE is $\frac{1}{2}(1.5+8.63+1.5-2\times1)=4.81$ sq. in. The

weakest section is *ADE* on which the net area is 4.81 sq. in. According to the 30% rule four holes would have to be deducted from the square section giving an effective area of only 3.75 sq. in.

If the 30% rule were followed it would make it necessary to make allowance for at least two holes in any angle having rivets in both legs if the maximum pitch of 16*t* or 6 in. were not exceeded. (13.)

In order to provide against undiscovered defects in workmanship and material, it is well to make a liberal allowance in



FIG. 20.

calculating net areas, especially where stresses are eccentric, as they usually are in angles.[1]

Practice is not at all uniform on this point.

20. Eccentric Stresses in Riveted Connections. When the center lines of stress in a connection do not intersect at the center of the group of resisting rivets there is a moment on the connection as well as the direct stress, and the connection is said to be eccentric. This eccentricity should be avoided wherever possible. Eccentric connections are frequently put in by careless or inexperienced draftsmen where by a little thought

[1] See Engineering News, Vol. LVI, page 14 (July 5, 1906) for an account of experiments by Prof. Frank P. McKibben, which show that the eccentricity of stress in angles causes rupture to occur at about 80% of the ultimate strength of test pieces cut from the same material.

they could be avoided. Fig. 21 shows such a connection and Fig. 22 shows how the eccentricity could be avoided.

When it is necessary to use an eccentric connection, the stresses on the rivets should be carefully calculated to see that allowable unit stresses are not exceeded.

Eccentric connections usually cause bending moments in



FIG. 21.

the members connected and may cause overstrain if not properly taken care of.

It is evident that a single lap joint like Fig. 9, is eccentric. The forces form a couple with a lever arm equal to half the sum of the thicknesses of the plates joined, tending to bend the plates and the rivets (14). The plates are therefore subjected to a bending and a direct stress. In a butt joint with two splice plates, (Fig. 12), there are no eccentric stresses in the plates joined, but there are in the splice plates.



FIG. 22.

The stresses on the rivets of the joint shown in Fig. 21 may be calculated as follows:

Two equal and opposite forces P' and P'' may be inserted at the center of the resisting group of rivets without changing the equilibrium. That is the single force P, of 16,000 lbs., may

be replaced by an equal force P' parallel to it, and a couple $P''P$ whose moment is $16000 \times 3.18 = 50{,}800$ in. lbs.[1]

The direct stress on each rivet due to P' will be $\frac{16000}{4} = 4000$ lbs.

To resist rotation about the center of gravity of the group of resisting rivets, *each rivet acts in a direction perpendicular to its lever arm* and thus takes an additional stress *in proportion to its distance from the center of gravity of the group.* If S be the stress on each outermost rivet, due to the moment, the equation of moments will be,

$$2 \times 4.5S + 2 \times 1.5 \frac{1.5}{4.5} S = 50{,}800 \text{ in. lbs.},$$

from which we get $S = 5080$ lbs.

The maximum stress on each outer rivet will be the resultant of 4000 lbs. and 5080 lbs., which may be obtained graphically as shown in Fig. 21. The resultant for the two outer rivets will not be the same, because the stresses due to the tendency to rotate act in opposite directions. If the greater of these resultants exceeds the allowed stress on one rivet, more rivets must be used. The resultant for rivet A is 8370 lbs., and is the greater as would naturally be expected. It is more than double the stress (4000 lbs.) that it would receive if there were no eccentricity as in Fig. 22.

Figure 23 shows another common form of eccentric connection. The direct stress on each rivet is $\frac{20000}{8} = 2500$ lbs. The total moment is $20{,}000 \times 5.66 = 113{,}200$ in. lbs. Writing the equation of moments we have $4 \times 7.5S + 4 \times 6.17 \frac{6.17}{7.5} S = 113{,}200$ in. lbs. Solving, we get $S = 2250$ lbs., which is the stress on A, B, C, or D due to the moment. These stresses act in the directions shown in the figure, which also shows the direct stress on each rivet. Finding graphically, the resultants of the two forces which act on each outer rivet we have for A 400 lbs., for B 3100 lbs., for C 4750 lbs., and for D 3600 lbs.

[1] This is an abstract proposition. See Rankine's "Applied Mechanics," Art. 42, also Heller's "Stresses in Structures," Art. 34.

It is seen from these examples, that if the connection is eccentric, the rivets are not equally stressed, and that simply taking into account the direct stress will often give results far from the truth.

In laying out a joint in which several members connect, rivet lines are often taken in place of center of gravity lines.



FIG. 23.

This is permissible only when the resulting eccentric stresses come within proper limits. If the rivets in a joint are not symmetrically arranged about the neutral axes of the members, there will be eccentric stresses. An angle connected by one or both legs forms an eccentric connection which cannot be avoided. (See foot note, page 40.)

21. Showing Rivets on Drawings. In general only rivet heads in plan are shown on drawings. *They should always be*

drawn to scale. Where there is any possibility of interference the rivet heads may be shown in elevation as well as in plan. In such cases the heads are sometimes only drawn in pencil to determine the clearance.

In certain locations there is not room enough for a full head, therefore rivet heads may be flattened or countersunk as shown in Fig. 24. By this means heads may be made flush with the metal through which they are driven, or be made $\frac{1}{8}$ in., $\frac{1}{4}$ in. or $\frac{3}{8}$ in. high. The usual symbols indicating these various kinds



FIG. 24.

of heads are shown in Fig. 24, which also shows how open holes (into which rivets are to be driven in the field) are indicated. This is called the Osborn system of symbols, and is practically universal in this country now.

All the rivets in a member need not be shown on a drawing, but all of the rivets at the joints should be drawn in. The intermediate portions of the members are frequently omitted and the spacing indicated as so many spaces at so much. In this case the spacing so given should tie up two definitely fixed points at the ends.

CHAPTER III

MILL BUILDINGS

22. Roofs. The roofs of buildings in which it is not desirable to have walls or columns at frequent intervals, are supported by means of trusses which are carried either on the walls or on columns placed at the sides. These trusses may be made either of steel or a combination of wood and steel. Steel trusses are usually used in mill and factory buildings and in fireproof buildings. In the latter the steel must be protected by some method of fireproofing as the steel by itself is *not* a fireproof material. Combination trusses are sometimes used in forge shops and foundries where the sulphurous gases in the atmosphere would quickly corrode steel. The steel parts (tie rods) of a combination truss are usually round or square rods and thus present a minimum surface to the action of corrosive gases. Combination trusses are also frequently used in large public buildings and churches where fireproof construction is not deemed essential.

23. Construction. The roof trusses are placed transversely of the building, their distance apart (see Art. 26) depending on the length of span, type of construction of the building in general and the kind of roof covering. The upper inclined members of the trusses, parallel to the slope of the roof are called *rafters*. (See Fig. 36.) Longitudinal beams extending from truss to truss are supported by the trusses at intervals along the rafters. These are called *purlins*, and they carry the roof covering, either directly or by means of boards, called *sheeting* or *sheathing*, running transversely to the purlins (up and down the roof) or diagonally across them.

24. Roof Coverings. For mill buildings, the commonest kinds of roofing are *currugated steel or iron, slate, tile, tin* and various patent sheet metal roofs, *tar and gravel* and similar patented combinations.

The corrugated steel or iron is usually fastened directly to

the purlins by means of clips.[1] *Slate* is usually nailed to sheeting boards with a layer of roofing felt between, although sometimes heavy slate is fastened directly to small purlins placed about $10\frac{1}{2}$ inches apart. Tile is usually fastened directly to angle purlins spaced about 13 inches apart, without any sheeting. *Tin, and similar types* of roofing are laid on sheeting with roofing felt between. *Tar and gravel* roofs are laid on wooden sheeting or sometimes on reinforced concrete slabs.

The main function of a roof is to shed water, and in order to do this without leakage, it must have a fall or slope. The amount of slope required depends upon the kind of roof covering.

The *pitch* of a roof is the ratio of its rise to its span. Thus for a 60 ft. span. if the rise is 15 ft., the pitch is $\frac{1}{4}$, if the rise is 20 ft. the pitch is $\frac{1}{3}$. The *least pitch* advisable to use with *corrugated steel, slate or tile* is about $\frac{1}{4}$, that is a fall of about 6 inches per foot, and this is the pitch used for most mill and factory buildings. *Tin* and similar roofs with *water tight joints* may have a fall of as little as $\frac{1}{2}$ inch per foot. *Tar and gravel* roofs should have a fall of from $\frac{3}{4}$ in. to 2 in. per foot.

25. Types of Trusses. It is only in unusual structures such as train sheds, exposition buildings, grand stands, etc., that the span of a roof truss exceeds 100 ft. The slope of the roof and local conditions such as required clearances, ventilation, light, etc., will usually determine the general outline of the truss. Any type of bracing may then be selected to suit the materials of construction.[2]

For roofs of ordinary pitch and span, the Fink truss is by far the commonest type. Fig. 25 (*a*), (*b*), (*c*) and (*d*) shows several modifications of this form of truss, to suit spans of varying length. For sake of economy in the rafters it is not desirable to have many loads coming on them from the roof purlins, between panel points, hence the advisability of increasing the number of panels as the span increases.

For combination trusses of wood and iron, one of the forms shown in Fig. 25 (*g*) and (*h*) is used. In these trusses the

[1] See "General Specifications for Steel Roofs and Buildings," by C. E. Fowler, Figures page 17.

[2] See Heller's "Stresses in Structures," Art. 117.
See Ketchum's "Steel Mill Buildings," page 146.

diagonal compression members and the top and bottom chords are made of wood, and the vertical ties are rods.

For *flat roofs* some form of truss must be used similar to Fig. 25 (*f*), (*h*) and (*l*), in order to gain sufficient depth at the center to give economic chord sections.

Another type of roof which is rapidly coming into favor is the "*saw-tooth*" roof, shown in Fig. 25 (*k*). The plane of the steeper rafter is glazed, and this side is made to face the North if possible. By this arrangement the floor below is lighted by



FIG. 25.

an even diffused light, without the necessity of making the building narrow in order to gain light from the sides, and without the disadvantages of sky lights through which the direct rays of the sun may shine.

Roof trusses for very long spans are usually three-hinged arches, the lower hinges being connected by bars under the floor to take the thrust.[1]

[1] See trainsheds for Penna. R. R. at Jersey City and Philadelphia, and of the Phila. and Reading R. R. at Philadelphia, in Eng. News, Vol. 26, p. 276, Vol. 29, pp. 507 and 508, and Vol. 42, p. 212.

The roof trusses of grand stands usually project beyond their supports at both ends. These are called cantilever trusses.

Sometimes for the sake of appearance or to gain clearance, the lower chord of a roof truss is curved upward. This always increases the cost and weight very materially.

Ordinary steel roof trusses are made with riveted connections, because such construction is cheaper and gives greater rigidity than the pin connection. Heavy trusses of long span are sometimes made with pin connections, because the saving in cost of erection is more than the saving in shop work with riveted connections. The members of a pin connected truss offer a smaller percentage of area to the corrosive action of gases than those of riveted trusses. Provision is sometimes made for the weakening effect of corrosion, by increasing the thickness of material above that required to take the actual stresses or by adding a certain percentage to the loads.[1]

In calculating the relative economy of roofs of different pitches, the roof covering must be taken into account, as the greater the pitch, the greater the area of roof covering. Corrugated steel usually makes the cheapest roof, as the dead weight is small. The most expensive roofs are those of tile and heavy slate, laid directly on the purlins.

26. Building Construction. Trusses carrying light roofs are usually spaced from 16 ft. to 20 ft. center to center. Theoretically the shorter this spacing, the less the total weight of trusses and purlins, per sq. ft. of covered area, but on account of practical limitations in the size of materials, etc.,[2] and on account of the greater cost per pound for the manufacture of trusses, than for purlins, the spacing of the heaviest trusses is very seldom less than 10 ft. center to center.[3] When the weight of the roof covering is very great, the purlins are sometimes supported between trusses, on beams called "*jack rafters*," which are supported at the ridge and eave, on longitudinal beams, carried by the trusses.

In addition to vertical loads due to gravity, provision must be made for horizontal forces due to wind or tractive effect

[1] See Fowler's "Specifications for Steel Roofs and Buildings," Art. 10.

[2] See Fowler's "Spec.," Arts. 37, 39, 44, 45, 59 and 64.

[3] See Bulletin No. 16, University of Illinois Engineering Experiment Station, "A Study of Roof Trusses," by N. Clifford Ricker.

of traveling cranes and for vibrations caused by machinery. If the building has brick or masonry walls, these are assumed to be sufficient bracing for the sides of the building, but bracing between the roof trusses must be put in to carry the horizontal forces to the walls.

In buildings with roofs supported on columns, bracing is necessary, both logitudinally and transversely, to carry the horizontal forces to the ground. With trusses of types similar to those shown in Fig. 25 (*a*), (*b*), (*c*), (*d*), (*e*), (*g*) and (*k*), the transverse bracing consists of knee braces connecting the trusses and columns, as shown in Fig. 26, the wind load being carried to the foundations by bending in the columns. If a truss is used having some depth at the ends, (see Fig. 25 (*f*), (*h*), and (*l*),) the knee braces may be dispensed with and the columns run through to the rafter.[1]



FIG. 26.

Longitudinal bracing may be put in, in three planes. That in the plane of the rafters is called *rafter bracing*, that in the plane of the bottom chords is called *bottom chord bracing*, and that in the vertical planes between the columns is called *side bracing*.

Theoretically, only one panel of longitudinal bracing is necessary to take care of the longitudinal wind forces, but for convenience in erecting the steel work, not less than two panels are braced, and in long buildings the braced panels are not farther apart than three or four panels. This arrangement usually requires less material in the bottom chord and rafter bracing diagonals than is given by the smallest size of rod ever used, and these members are therefore usually made of $\frac{3}{4}$ inch round rods. Struts are required between the trusses and columns as members of the lateral systems. In the rafter bracing, the roof purlins are usually made to serve the purpose of struts. Several lines of ties are put between the bottom chords of the trusses in the unbraced panels. These serve to reduce the vibra-

[1] For figuring stresses in Columns see Heller's "Stresses in Structures," Chaps. X and XIV.

tion of the roof, especially when cranes or hoists are attached to the trusses. The general arrangement of the bracing is shown in the stress sheet, Fig. 32.

27. Loads. A roof truss ordinarily carries nothing but dead load, which includes wind and snow loads and the weight of the structure itself, such as the covering, sheeting, purlins, trusses, bracing, ceiling, shafting, etc. A traveling hoist carried by a roof truss would constitute a live load.

In a paper presented before the American Society of Civil Engineers, entitled, "Wind Pressures in the St. Louis Tornado, with Special Reference to the Necessity of Wind Bracing for High Buildings," by Mr. Julius Baier, (Trans. Am. Soc. C.E., Vol. 37, page 221) Mr. Baier makes some deductions as to what the wind pressures must have been in several instances in that tornado, (May 27th, 1896) to produce the destruction which resulted. In his conclusions he states in part:

"It gave evidence that wind pressures existed at least equivalent to or greater than 20 lbs., 60 lbs., and 85 to 90 lbs. per square foot over considerable areas. Whatever the actual distribution may have been, the effects were those of such pressures uniformly distributed over the areas of the respective structures. These pressures were measured by their results in exactly the same manner in which they are ordinarily assumed to act, with consequent elimination of all uncertainties usually involved in readings of pressure gauges or deductions from anemometer records, and they are to that extent positive and definite. In addition, there were indications that a pressure of somewhere from 20 to 40 lbs. was quite general over a comparatively wide area in, or adjacent to, the path of the storm, and that the pressures at higher altitudes were more severe than those measured."

He also says:

"Much of the destruction in St. Louis was undoubtedly caused by an intensity of wind pressure that it would be neither possible nor expedient to provide against in ordinary structures, but much of it was also due to weak construction."

Thirty pounds per square foot has come to be recognized pretty generally as a safe value for the wind pressure on vertical walls of ordinary height. Mr. Baier recommends that this be increased to 50 lbs. per sq. ft. for the upper stories of tall buildings.

The pressure of the wind on an inclined surface, such as

a roof is always assumed to be normal to the roof, although there is no doubt that the roughness of the roofing material would offer some resistance and that there is a component of the force, parallel to the roof.

The amount of the normal pressure on the roof is variously given by different authorities. Prof. N. Clifford Ricker recommends the formula,[1]

$P_n = \frac{2}{3}\alpha$, for $P = 30$ lbs. per sq. ft. horizontal pressure, in which P_n is the normal pressure and α is the angle of inclination of the roof with the horizontal in degrees, when this is less than 45 degrees. For inclinations steeper than 45 degrees use 30 lbs. Many authorities have used the formula,

$$P_n = P \sin \alpha^{(1.84 \operatorname{Cos} \alpha - 1)}$$

brought out by Hutton. This is much more complex than the one recommended by Prof. Ricker, and as both are empirical and give within a few pounds of the same values, it would seem logical to employ the simpler one.

When a roof truss rests on brick or masonry walls, one end must be free to move longitudinally in order to provide for changes in length due to temperature changes. This is usually arranged by providing slotted holes in one end for the anchor bolts, thus allowing the truss to slide on the bed plate. For long trusses rollers are provided to reduce the friction where this movement takes place. If we assume that there is no friction at the expansion bearing, the reaction must be vertical at that point and therefore it is necessary to calculate the stresses in the truss with the wind blowing from both directions. When trusses are fastened rigidly to the tops of columns, the horizontal components of the wind reactions are sometimes assumed to be equal and sometimes the wind reactions are assumed parallel. In this case it is only necessary to calculate the stresses for the wind blowing in one direction. *A vertical equivalent wind load* is sometimes used together with the other loads.

The *snow load* varies with the climate, the slope of the roof and the roughness of the roof covering.[2] The weight of freshly

[1] Bulletin No. 16, University of Illinois Engineering Experiment Station.
[2] See Fowler's "Specifications," Art. 5.

fallen snow is from 5 to 12 pounds per cu. ft.[1] The snow load may act on one side only of a roof, as a heavy wind or the sun on the other side would dislodge it. When the pitch of the roof is variable, as it frequently is for train sheds, snow might stand on only a part of either or both sides, and might be a variable load. It is not usually assumed that the maximum wind and snow loads can act upon one side of a roof at the same time, because the wind would dislodge the snow.

We may therefore have a partial snow load, a partial wind load or a combination of these, in addition to the weight of the structure itself.

The weight of the roof covering should be calculated, remembering that the weight per horizontal square foot is equal to the weight per sq. ft. of the roof surface multiplied by the secant of the angle of inclination of the roof with the horizontal.[2]

The thickness of the sheeting when used depends upon the spacing of the purlins. It varies from $\frac{7}{8}$ in. to 2 in. in thickness, and may be calculated, using an extreme fiber stress of from 1200 to 1500 lbs. per sq. in.[3]

The weight of the purlins may be calculated after they are designed, which should be done before the trusses are figured. For corrugated iron roofs they will usually amount to about 3 lbs. per horizontal square foot.

The weight of the trusses may be estimated from a comparison with a similar building which has been designed, or it may be approximately obtained from an empirical formula.[4] After the design is completed, an estimate of the weight is made and the dead load used in the calculations is verified. If this differs materially from the amount used, corrections in the design should be made.

28. Stresses. The stresses in any statically determinate structure[5] may be calculated from the principles of statics.[6] Since trusses of the same type with the same number of panels are similar figures, the stresses in them are proportional, for

[1] See Trautwine's "Civil Engineer's Pocket Book," p. 384.

[2] For weights of various roofing materials, see Trautwine's "Civil Engineer's Pocket Book." See also Fowler's "Specifications," Art. 8.

[3] See Fowler's "Specifications," Art. 22.

[4] See Fowler's "Specifications," Art. 9.

[5] See Heller's "Stresses in Structures," Art. 42.

[6] See Heller's "Stresses in Structures," Chaps. III, IV, V and VI.

different spans, to the panel loads. Tables of stresses in various types of trusses for panel loads of one pound are given in various hand books.[1] The stress in any member of a truss similar to any of these is gotten by multiplying the coefficient given, by the panel load. This is readily done on the slide rule.

29. The Design of a Building. To illustrate the methods of procedure, a complete design for a mill building will now be worked out.

The building will be assumed to have 13-inch brick walls with pilasters for the support of the ends of the roof trusses.

The extreme width out to out of pilasters will be 81 ft. 1 in.

The extreme length of building will be 221 ft. 1 in. This will give a length of 220 ft. center to center of end walls, and a width of 80 ft. center to center of side walls.

The end walls will run up to the roof and carry the end panel purlins.

We will use 11 bays at 20 ft. = 220 ft.

Roof covering to be No. 20 Corrugated Steel.

Specifications to be Fowler's "Specifications for Steel Roofs and Buildings," 1910 edition.

Pitch of the roof to be one fourth.

The *stress sheet*, Fig. 32, gives a general outline of the arrangement of the purlins, bracing, etc.

The student should familiarize himself with the specifications and refer to them constantly.

30. Purlins. The roof purlins are usually made of channels, I beams, or angles, fastened to the rafters of the roof trusses (23) in such a manner that the roofing material may rest upon one of their flat sides, as shown in Fig. 27.

This places the purlin in an inclined position with regard to the vertical loads. To calculate the stresses on the purlin the loads may be resolved into two components, one parallel to the roof and one normal to it.[2] The purlins are weakest in a direction parallel to the roof and are usually supported in that direction, by tie rods at close intervals. In that case the normal

[1] See Fowler's "Specifications," pages 10 to 15. See also Carnegie's "Pocketbook," page 174.

[2] For a complete discussion of this subject see Heller's "Stresses in Structures," Art. 69.

component of the load is the only one producing a bending moment on the purlin.

Vertical loads,

Snow (Spec. Art. 5)	15 lbs. per horiz. sq. ft.
Corr. steel No. 20 (Spec. Art. 8)	2 lbs. per horiz. sq. ft.
Purlins and ties say	3 lbs. per horiz. sq. ft.
Totals vertical load on purlins	20 lbs. per horiz. sq. ft.



FIG. 27.

For corrugated steel No. 20 the roof purlins must not be spaced over 4 ft. 6 in. center to center (Spec. Art 27). The extreme length of the rafter is $\sqrt{(40.5)^2+(20.25)^2}=45.3$ ft. If we use 11 purlins, their distance center to center will be almost exactly 4 ft. 6 in. This arrangement will not make the purlins come at the panel points of the truss (see Fig. 32) but this cannot be avoided, hence the rafters must also act as beams to carry the purlin loads to the panel points of the truss, as well as members taking the regular truss stress.

The number of horizontal square feet tributary to each purlin is $\frac{81}{20}\times 20=81$ sq. ft., which at 20 lbs. per sq. ft. gives 1620 lbs. total vertical load on each purlin.

The normal component of this vertical load is

$$1620 \cos 26° 34' = 1450 \text{ lbs.}$$

The normal wind load per purlin (Spec. Art 6)

$$= 4.5 \times 20 \times 18 = 1620 \text{ lbs.}$$

Total normal purlin load $= 3070$ lbs.

The maximum moment

$$= \frac{WL}{8} = \frac{3070 \times 20}{8} = 7675 \text{ ft. lbs.} = 92{,}100 \text{ in. lbs.}$$

The maximum allowed fiber stress for purlins is 15,000 lbs. per sq. in. See specifications Art. 19.

$$\frac{M}{s} = \frac{I}{v} = \frac{92100}{15000} = 6.14 = \text{required section modulus.}$$

The lightest I beam with a section modulus greater than 6.14 is a 6 inch $12\frac{1}{4}$ lb. beam. (See "Cambria," page 158.) The lightest channel having a section modulus large enough is an 8 inch channel $11\frac{1}{4}$ lbs., and the lightest angle that can be used is a 7 in. $\times 3\frac{1}{2}$ in. $\times \frac{9}{16}$ in., which weighs 19.1 lbs. per foot.

The most economical section in this case is the channel, also channels are more easily placed in the field than the other shapes as they can rest against the purlin clips (see Fig. 27) until riveted in place, so we will use the channel purlins.

To prevent the purlins sagging and to take the component of the load parallel to the roof, sag ties are inserted at intervals not exceeding about thirty times the width of the purlin. These are usually made of round rods, threaded at the ends, which are run through holes in the purlin webs with nuts to hold them in place. The two ridge purlins are tied across the ridge as shown in Fig. 28 and when the roof is symmetrical the loads on the two sides balance each other.

Thirty times the width of the purlin flange in this case is $30 \times 2.26 = 67.8$ inches. There will then be required, three lines of sag ties in each bay, dividing the purlins into four equal parts.

The component of the purlin load parallel to the roof is $1620 \sin 26° 34' = 725$ lbs. per purlin, there are 10 purlin spaces

on each side of the roof so the component of the stress parallel to the roof in each of the ties across the ridge will be

$$\tfrac{1}{4}\times 10\times 725 = 1810 \text{ lbs.}$$

Then the stress in this ridge tie $= 1810 \sec. 26° 34' = 2025$ lbs. and the required area will be (Spec. Art. 13)

$$\frac{2025}{17000} = .12 \text{ sq.in.}$$

This net area must be provided at the root of the thread on the



FIG. 28.

rod. This will require a $\frac{1}{2}$-inch round rod. (See "Cambria," page 302.) These ties are usually made $\frac{5}{8}$-inch rods and we will follow the custom and use that size.

The roof load going to the ridge purlins is only half as much as that carried by the other purlins, but in addition to this they must take the normal component of the stress in the ridge ties. Fig. 28 shows the arrangement of the purlins at the ridge and the arrows indicate the loads which one of them has to carry.

Normal wind load $= \frac{1}{2} \times 1620 =$ 810 lbs.
Normal comp. of vert. load $= \frac{1}{2} \times 1450 =$ 725 lbs.

Total normal distributed load $= 1535$ lbs.

The normal component of the stress in each ridge tie is

$$2025 \sin 26°34' = 905 \text{ lbs.}$$

at each tie connection.

Fig. 29 shows the distribution of the normal loads on the ridge purlin. The maximum normal moment is 12,890 ft. lbs. and the required section modulus is 10.32. This requires the use of 8 inch channels $18\frac{3}{4}$ lbs. for the ridge purlins.



FIG. 29.

We can now make an estimate of the weight of the purlins to see how it compares with the original weight assumed. One regular purlin weighs $11\frac{1}{4} \times 20 = 225$ lbs. 20 purlins $= 20 \times 225 = 4500$ lbs. per bay. The two ridge purlins weigh $2 \times 18\frac{3}{4} \times 20 = 750$ lbs. per bay. The sag ties $= 2 \times 3 \times 46$ ft. $= 276$ lin. ft. per bay and $276 \times 1.04 = 287$ lbs. per bay. To this must be added about 10% for laps and nuts making 320 lbs. per bay. The total weight of purlins and ties per bay is $4500 + 750 + 320 = 5570$ lbs. This is distributed over $81 \times 20 = 1620$ sq. ft., making the weight per square foot $= \frac{5570}{1620} = 3.4$ lbs. Our original estimate was three pounds.

31. The Trusses. For the purlin spacing which we have, no two panel loads on the truss will, in general, be the same, but it is sufficiently close to assume them equal when getting the stresses in the truss.

For simple trusses resting on walls a vertical equivalent is usually used in place of the normal wind load. This equivalent load is assumed as acting over the entire roof and gives results which are safe and which are close enough for ordinary cases. (See Spec. Art. 6.)

An approximate weight for our trusses may be calculated from the formula given in Art. 9 of the specifications. 0.04

$\times 80 + 0.4 = 3.6$ lbs. per sq. ft. The total load to be used in designing the truss then is

Covering	2.0 lbs. per horiz. sq. ft.
Purlins	3.4 lbs. per horiz. sq. ft.
Trusses	3.6 lbs. per horiz. sq. ft.
Snow	15.0 lbs. per horiz. sq. ft.
Equivalent wind	15.0 lbs. per horiz. sq. ft.
Total	39.0 lbs. per horiz. sq. ft.



FIG. 30.

Mem.	Stress	Allowed Unit	Req. Area	Material used	Rad. Gyr.	Length	Actual Area
aB	+61,100	15,000		Bending and Direct Stress combined — 2 ls 6" × 3½" × ⅝" ┬		11.3	
BC	+57,600					11.3	
CD	+54,100					11.3	
DE	+50,600					11.3	
ab	−54,600	15,000	3.64	2 ls 3½" × 3½" × 13/16" ⅞" Riv. ┴			3.71 Net
bc	−46,800	"	3.12	" " " " " " "			" "
ce	−31,200	"	2.08	2 ls 3" × 2½" × ¼" " " "			2.27 "
Bb	+ 7,000	7,900	0.89	2 ls 2" × 2" × ¼" ┬	0.61	5.6	1.88
Cc	+14,000	6,550	2.14	2 ls 3" × 2½" × 5/16" ┬	0.95	11.3	2.64
Dd	+ 7,000	7,900	0.89	2 ls 2" × 2" × ¼" ┬	0.61	5.6	1.88
bC	− 7,800	15,000	0.52	2 ls 2" × 2" × ¼" ⅞" Riv. ┴			1.50 Net
Cd	− 7,800	"	0.52	" " " " " " "			" "
cd	−15,600	"	1.04	2 ls 2½" × 2" × ¼" " " ┴			1.76 "
dE	−23,400	"	1.56	" " " " " " "			" "
Ee	0	—	—	2 ls 2" × 2" × ¼"			

The panel load per truss will be $\frac{1}{8} \times 80 \times 20 \times 39 = 7800$ lbs.

By means of the table on page 13 of the specifications, we find the following stresses for a panel load of 7800 lbs. (Note that the lettering of the truss in the specifications is not the same as used here.)

The tension members may be proportioned first. The smallest angle allowed is 2 in. $\times$ 2 in. $\times \frac{1}{4}$ in., (Spec. Art. 64,) and all members should be symmetrical (Spec. Art. 39 and 40). Therefore the smallest member allowed will be $2Ls\ 2'' \times 2'' \times \frac{1}{4}''$. The largest rivets allowed in these angles are $\frac{5}{8}$ in. (See "Cam-

bria," page 46.) The gross area is $2\times0.94=1.88$ sq. in. The net area is $1.88-2\times\frac{1}{4}\times(\frac{5}{8}+\frac{1}{8})=1.88-0.38=1.50$ sq. in. This will answer for *bC*, *Cd* and *cd*, but *cd* and *dE* are usually made continuous and should therefore be the same size. 2*Ls* $2\frac{1}{2}''\times2''\times\frac{1}{4}''$ will answer for these, the net area being $2\times1.07-2\times\frac{1}{4}\times(\frac{5}{8}+\frac{1}{8})=1.76$ sq. in. For light trusses *ab* and *bc* are also also usually made continuous. The sizes of the other tension members are easily determined, as shown in the table above.

We will try to make each of the compression members of two angles. These will be back to back, and will be far enough apart to admit the connection or gusset plates between them at the joints. We will try to make all gusset plates $\frac{3}{8}$ in. thick. The radius of gyration for the various sizes of angles may be taken from "Cambria," pages 181 to 183. The least width of compression member allowed is $\frac{1}{50}$ of the length (Spec. Art. 59), therefore $2''\times2''$*Ls* cannot be used in compression members whose length is greater than 100 in. = 8.3 ft. For *Bb* and *Dd* we will try 2*Ls* $2''\times2''\times\frac{1}{4}''$. The least radius of gyration is 0.61. The maximum allowed unit stress is,

$$12500-500\frac{5.6}{0.61}=7900 \text{ lbs. per sq.in.}$$

The required area will be $\frac{7000}{7900}=0.89$ sq.in., while the actual area ia 1.88 sq. in., and therefore *Bb* and *Dd* may be made of 2*Ls* $2''\times2''\times\frac{1}{4}''$.

For *Cc* the least allowable width of member will be

$$\frac{11.3\times12}{50}=2.71 \text{ in.}$$

The least angles that can be used will be 2*Ls* $3''\times2\frac{1}{2}''\times\frac{1}{4}''$ unless "special" angles are used, which usually take longer for delivery from the mills and might thus delay the work. The table of column unit stresses on page 15 of the specifications may be used instead of applying the column formula each time. Trying 2*Ls* $3''\times2\frac{1}{2}''\times\frac{1}{4}''$ for *Cc*, the least radius of gyration = 0.95 and $\frac{l}{r}=\frac{11.3}{0.95}=11.9$. Allowed unit stress from table = 6550 lbs.

per sq. in. The required area $= \frac{14000}{6550} = 2.14$ sq. in. The actual area $= 2 \times 1.32 = 2.64$ sq. in., which is sufficient.

The rafter should be made continuous from eave to ridge, if this length is not too great, say over 60 ft. It must be proportioned for direct compression and bending.[1] The maximum compression occurs in aB, and the bending in this case is also a maximum in this panel, or nearly so. aB is loaded transversely by the purlins, as shown in Fig. 31.



FIG. 31.

Considering the member as a simple beam supported at a and B, the maximum moment will be $2509 \times 3.55 = 8907$ ft. lbs.

The rafter is not really in the condition of a beam simply supported at the ends, nor are the ends fixed, because the connections are elastic. The actual moment lies somewhere between that for the two conditions of free and fixed ends, (Spec. Art. 16) and may safely be taken as $\frac{5}{8}$ of the moment for a simple beam. We have then $M = \frac{5}{8} \times 8907 = 5567$ ft. lbs. $= 66{,}800$ in. lbs.

This is the positive moment under the load nearest the middle.

There is also a negative moment at each support which may be assumed to be equal to the same amount.

The maximum fiber stress will be the sum of the two fiber stresses due to direct stress and bending.

$$s_{max.} = \frac{P}{A} + \frac{Mv}{I}. \quad \text{(See Spec. Art. 16.)}$$

In applying this equation the distance v must be taken as the greatest distance from the neutral axis to the outside fiber as the bending moment is both positive and negative in the length of the member.

[1] For a complete discussion of this subject see Heller's "Stresses in Structures," Art. 111.

We will try $2Ls\ 6'' \times 3\frac{1}{2}'' \times \frac{1}{2}''$. $I = 2 \times 16.59 = 33.18$. $v = 3.92$. $A = 2 \times 4.5 = 9.0$.

$$s = \frac{66800 \times 3.92}{33.18} + \frac{61100}{9.0} = 7891 + 6789 = 14{,}680 \text{ lbs. per sq. in.}$$

The allowed fiber stress is 15,000 lbs. per sq. in., therefore these angles are large enough. If the next size smaller angle be tried it will be found too small.

The lateral struts do not carry much stress, and their size is determined by Art. 59 of the specifications, which requires that their least width be not less than $\frac{1}{50}$ of their length. This requires the use of members not less than 4.8 in. wide. The most economical section will be $2Ls\ 5'' \times 3'' \times \frac{5}{16}''$, the longer legs being back to back. The ridge strut is usually made the same for all bays. The bottom chord ties take no definite stress, but should not be less than one angle $3\frac{1}{2}'' \times 3'' \times \frac{5}{16}''$ with the $3\frac{1}{2}$ inch leg vertical. All the laterals may be $\frac{3}{4}$ in. round rods. The vertical member of the truss at the middle takes no stress, but keeps the lower chord from sagging.

Having completed the designing of the members, the stress sheet and estimate of weight may be made. The stress sheet is usually a line diagram as shown in Fig. 32, on which are written the stresses and sizes for all of the members, as well as the general dimensions of the building. The estimate of weight is given in Fig. 33.

32. Buildings with Columns. When the roof trusses are supported on columns, the wind stresses in them are affected by the thrust of the knee braces which give the building transverse stability. (See Fig. 26.) The stresses in the truss and knee braces would not be changed if the columns were replaced by trussed members as shown by the dotted lines in Fig. 34. The wind stresses in the truss and knee braces may be found graphically by using these auxiliary members.

Theoretically the points a and a' should be taken at the points of contraflexure in the columns.[1] The location of these depend upon the degree of fixity of the ends of the columns, and cannot be determined without making assumptions which are

[1] See Heller's "Stresses in Structures," Art. 153 to 165 for a complete discussion of stresses in portal bracing.


HALF PLAN OF RAFTER BRACING
HALF PLAN OF BOTTOM CHORD BRACING
Purlin acts as Strut
Ridge Strut
2 L's 5" x 3" x 5/16"
Purlin acts as Strut
Strut
Bottom Chord Tie 1 L 3 1/2" x 3" x 5/16"
All Lateral Rods 3/4" Rnd.
Strut
Bottom Chord Tie 1 L 3 1/2" x 3" x 5/16"
Strut
2 L's 5" x 3" x 5/16"
Strut
2 L's 5" x 3" x 5/16"
Purlins 8" 15 11 1/4 #
Ridge Purlins 8" 15 18 3/4 #
81'-1" Out to Out
Sag Ties 5/8" Rnd.
11 Bays at 20'-0" = 220'-0" c. to c. End Walls
221'-1" Out to Out
1/4 Pitch
+61100#
+57600#
+54100#
+50600#
-54600
-46800
-31200
-7800
-15600
-23400
+7800
+15600
+23400
+44000
Rafter
2 L's 2" x 2" x 1/4"
2 L's 6" x 3 1/2" x 1"
2 L's 3" x 2 1/2" x 1/4"
2 L's 3 1/2" x 3 1/2" x 5/16"
80'-0" C. to C. Walls
10 Trusses Req'd.
All Walls Brick 13" thick.
End Walls run up to Roof.
Roof Covering - No. 20 Corr. Steel.
To be built in accordance with
Fowler's "Specifications for Steel Roofs and Buildings." 1909.
DESIGN FOR ROOF
OF
PATTERN SHOP
THE OHIO STATE BRIDGE CO.
COLUMBUS OHIO

FIG. 32.

FORM No. 1

THE OHIO STATE BRIDGE COMPANY

Sheet No. 1 Made by C. T. M. Date 6-24-10

Estimate for Roof of Pattern Shop O. S. B. Co.

Span Extreme 81'-1"	Span C. to C. 80'-0"	Estimated DL per ft. { Steel ; Floor & Track ; Total	Total Steel
Roadway	// Panels at 20'=220'-0"		Steel per ft.
Sidewalk	Depth C. to C. ⅛ Pitch		Total Lumber
Capacity Trusses	Length ~~of Ring.~~ Ext. 221'-1"	Panel Load per Truss DL	
Capacity Floor		" " " " LL	
Specifications	Sec. Tg.		





MEM	DL Stress	LL Stress	Impact	Total Stress	Unit Stress	Req. Area	MATERIAL	Actual Area	No. Pcs.	Wt. P. Ft.	Length	WEIGHT
10 Trusses												
Rafter							2 ⌊s 6"×3½"×⅝"		40	15.3	45.5	27800
Bot. Chd. abc							2 ⌊s 3½"×3½"×5/16"		40	7.2	25.5	7340
" e		ce					2 ⌊s 3"×2½"×¼"		20	4.5	30.0	2700
Bb and Da							2 ⌊s 2"×2"×¼"		80	3.2	5.1	1300
Cc							2 ⌊s 3"×2½"×¼"		40	4.5	10.9	1960
bC and Cd							2 ⌊s 2"×2"×¼"		80	3.2	11.5	2940
cE							2 ⌊s 2½"×2"×¼"		40	3.7	24.2	3580
Ee							2 ⌊s 2"×2"×¼"		20	3.2	19.2	1230
		Purlin Clips					1 L 3½"×3"×5/16"		220	6.6	0.83	1200
		Bed Plates					2 ⌊s 12"×½"		40	20.4	1.0	820
										Details 15%		7630
								58500				
Bracing												
Ridge and Bot. Chd. Struts							2 ⌊s 5"×3"×5/16"		34	8.2	19.5	5430
Bot. Chd. Ties							1 L 3½"×3"×5/16"		16	6.6	19.5	2060
										Details 10%		750
								8240				
Lateral Rods												
		Top					1 Rnd ¾" (Eq)		24	1.5	35.0	1260
		Bot					1 " " "		12	1.5	36.0	650
		"					1 " " "		6	1.5	41.0	370
	Sag	Ties					1 " ⅝" "		660	1.0	5.5	3630
								5910				
Purlins							1 ⌊ 8"×11¼#		20	11¼	224	50400
							1 ⌊ 8"×18¾#		2	18.75	224	8400
										Bolts		200
								59000				
		Anchor Bolts					1" Rnd.		40			150
								150				
							Total Steel					131800
							Actual Weight of Steel per sq ft. = 131800/17600 = 7.48#					
							Estimated for Dead Load = 3+4 = 7.0#					

FIG. 33.

not warranted by the conditions.[1] The bases of the columns are usually not leveled and set true enough to give a guarantee that the lower end of the column would be fixed, and the elasticity of the connection at the top will not permit of the assumption of fixity there. The stresses will be largest when the points a and a' are taken at the bottoms of the columns, and this is the usual assumption.

P', Fig. 34, is the wind load on the upper half of the wall when the wall is supported laterally by the columns. The wind on the lower half of the wall is assumed to go directly to the foundations. H and H' are assumed equal if the columns are alike, and V and V' may be found by statics.

Mem.	Dead Load.	Snow Load.	Wind, Left.	Wind, Right.	Maximum.	
					Comp.	Tens.
aB	+14.1	+23.5	+44.0	−13.1	+81.6	0
BC	+13.3	+22.1	+44.0	−13.1	+79.4	0
CD	+12.5	+20.8	+24.3	+ 3.6	+57.6	0
DE	+11.6	+19.4	+24.3	+ 3.6	+55.3	0
ab	−12.6	−21.0	−12.2	− 4.0	0	−45.8
bc	−10.8	−18.0	−19.6	+ 8.0	0	−48.4
ce	− 7.2	−12.0	− 1.4	− 1.4	0	−20.6
Bb	+ 1.6	+ 2.7	+ 4.0	0	+ 8.3	0
Cc	+ 3.2	+ 5.4	+16.3	− 8.4	+24.9	− 5.2
Dd	+ 1.6	+ 2.7	+ 4.0	0	+ 8.3	0
bC	− 1.8	− 3.0	−22.7	0	0	−27.5
Cd	− 1.8	− 3.0	− 4.6	0	0	− 9.4
cd	− 3.6	− 6.0	−18.2	+ 9.4	+ 5.8	−27.8
dE	− 5.4	− 9.0	−22.6	+ 9.4	+ 4.0	−37.0
Ee	0	0	0	0	0	0

If the trusses of the building of Art. 29 be supported on columns 25 ft. high with knee braces connected 8 ft. below the tops of the columns as shown in Fig. 34, the stresses in the trusses will be as given in the table above. This may be compared with the table of stresses given in Art. 31.

The maximum moment in the columns will occur at the knee brace connection and equals Hc. The columns must be designed so that the maximum fiber stress, $\frac{P}{A}+\frac{Mv}{I}$, does not exceed the unit allowed by the specifications.

[1] See article by the author in Engineering News, Nov. 2, 1911.

33. The Detail Drawings. Drawings giving more or less detail are sometimes made by the purchaser's engineer to accompany the stress sheet, but the detail shop drawings are almost always made in the structural contractor's office. These should be submitted to the purchaser's engineer for approval. Fig. 36 is a shop drawing for the trusses designed in Art. 31. The methods for proportioning the details will now be given.

To avoid eccentric stresses (20) the center of gravity lines of all members coming together at a joint should intersect in a point. This is usually not practical in roof trusses because it would unnecessarily complicate the drawings and templet work. Instead of using the gravity lines as center lines, the rivet gage lines are usually used. For members composed of



FIG. 34.

$2Ls\ 2''\times2''\times\frac{1}{4}''$ the gravity line is 0.59 in. from the backs of the angles while the rivet line is $1\frac{1}{8}$ in. out. This makes the eccentricity of the connection 0.535 in. For a member composed of $2Ls\ 3\frac{1}{2}''\times3\frac{1}{2}''\times\frac{3}{8}''$ the eccentricity is $2.00-1.01=0.99$ in. For an angle having two gage lines, the center should of course be taken on that line which is nearest the gravity line. For a member composed of $2Ls\ 6''\times3\frac{1}{2}''\times\frac{1}{2}''$ the center of gravity is 2.08 inches from the back of the shorter legs. The rivet lines may spaced 2″ and $4\frac{1}{2}''$ from the back, in which case the inside line should be used as the center line.

In roof trusses it is the common practice to have the center lines of the members intersect in a single point at each of the joints except the shoe joint *a*. (See Fig. 36.) The reason for making an exception of this joint is that in order to take the

reaction, the end of the truss must have an appreciable depth. This result is usually accomplished by making the intersection of the center lines of the rafter and bottom chord come at some little distance beyond the center of the bearing plate, as shown in Fig. 36. To facilitate, the driving of the rivets in the shoe plate and in the purlin connection the depth at the end should be *about* 6 inches. The distance from the center of the bearing to the intersection is usually made such an amount as will avoid odd fractions of an inch in the center lengths.

Having determined this point by scale, the slope of the



FIG. 35.

center line of the rafter is made *exactly* 6 in. vertical to 12 in. horizontal, for a ¼ pitch roof.

This method of detailing the joint at the shoe, while the most common is not the best, as it introduces eccentric stresses into the members, causing bending in them and twisting on the rivets of the joint.

A better but slightly more expensive detail, is shown in Fig. 35, in which the center lines of the stresses at this joint intersect in a single point.

The truss outline and the details are not drawn to the same scale. This amounts to drawing the detail of each joint separately and then assembling the joints into the form of a truss.

It is not necessary to show the members broken between joints, although the distances are not to scale. Any rivet spacing between panel points cannot be drawn to scale, but it is not necessary to show all the rivets if the figures locating them are properly given. The scale for details is usually 1 in. or $1\frac{1}{2}$ in. per ft., depending upon the available room. The larger scale is easier to work with, especially for the beginner. The scale for the center lines should be so selected that there will be sufficient room for the elevation of half the truss, the dimension lines, the top view of the rafter and the sectional view of the bottom chord, with all connections for purlins, laterals, etc. The scale for the details must be decided upon first. A sample drawing should be consulted and studied, and if necessary preliminary sketches made of the lateral connections. Compactness is desirable, but crowding, especially of dimension lines. should be avoided. Usually the scale for the outline should not be less than one half that of the details.

Usually on the same sheet with the truss there is put a diagram of the roof showing the location of trusses, bracing, etc., similar to Fig. 32. This is called an erection diagram. In a building with steel columns and other steel work, the erection diagram usually occupies a sheet by itself. Sometimes there is also sufficient room on the sheet with the truss drawing for drawings of struts, purlins, etc.

After the scales have been determined, one half the distance between the intersections of the center lines of the rafters and bottom chord ($40' \; 10\frac{1}{2}''$ in our case) is laid off horizontally to the smaller scale chosen for the outline, and one half of this distance, if the roof has $\frac{1}{4}$ pitch, ($20' \; 5\frac{1}{4}''$) is laid off vertically at the right end, this being the rise of the center line of the rafter above the bottom chord. Now the hypotenuse of the right triangle is drawn, which is the center line of the rafter. This center line in then divided into four equal spaces and the center lines of the members *Bb*, *Cc* and *Dd* are drawn perpendicular to it. The intersections of *Bb* and *Cc* with the bottom chord determine points *b* and *c*, and of *Dd* with *cE*, point *d*. The length of *Cc* is twice that of *Bd* and *Dd*, and equals *aB*. The lengths of *ab*, *bc*, *bC*, *Cd*, *cd* and *dE* are equal. Thus it is seen that the center lengths are very easily determined, as given in Fig. 36, from right triangles.

Joint a. Fig. 36 is a shop drawing of the truss. The forces acting at joint *a* are the rafter stress, the bottom chord stress, the purlin load and the reaction. There must be enough rivets in the joint to safely transmit these forces. To avoid changing punches (12) the rivets will be made $\frac{5}{8}$ in. throughout. (Maximum size for a 2 in. leg.) Joint *a* has larger stresses than any other, and if $\frac{3}{8}$ in. connection plates were used throughout it would result in a large gusset here, consequently, (16) we will use a $\frac{1}{2}$ in. gusset plate at *a* and make all the others $\frac{3}{8}$ in.

The rafter stress is 61,100 lbs. The value of a $\frac{5}{8}$ in. rivet in double shear is 6136 lbs. (This value is less than the bearing value on a $\frac{1}{2}$ in. plate.) The number of rivets required in the rafter connection $=\frac{61100}{6136}=10$ rivets. We will have to add an extra rivet to transfer the purlin load, this makes 11 rivets. The rivets immediately over the bearing plate in the bottom chord must transfer the vertical component of the rafter stress and the purlin load to the bottom chord angles which rest on the bearing plate.

The amount of this reaction will be $4\times7800=31{,}200$ lbs., and the number of rivets required $\frac{31200}{6136}=5$. In addition to these we must have in the bottom chord sufficient rivets to transfer the bottom chord stress, 54,600 lbs. This requires $\frac{54600}{6136}=9$ rivets, making a total of 14 rivets in the bottom chord connection. If the *reaction* acted equally on all the bottom chord connection rivets at this point, the connection would only have to be proportioned for the resultant of the two stresses $\sqrt{54600^2+31200^2}=62{,}900$ lbs. and the rivets required would only be $=\frac{62900}{6136}=11$ rivets.

It is not good practice to put the rivets closer together than $2\frac{1}{2}$ in., and they must not come nearer the edge of any piece than $1\frac{1}{4}$ in. (13). Care must be exercised to see that the rivets in opposite legs of angles stagger so that one rivet head does not interfere with the driving of the other rivet.

Joint C. At this point the components of the stresses in *bC* and *Cd*, parallel to the rafter, balance each other in the plate

and require no rivets in the rafter. The components perpendicular to the rafter must be transmitted to *Cc*. Their sum is 7000 lbs., which may be gotten by laying off the stresses and scaling the components parallel to *Cc*. The balance of the stress in *Cc* (=7000 lbs.) comes directly from the rafter. These together require $\frac{14000}{4690}=3$ rivets in bearing on the $\frac{3}{8}$-in. gusset plate. There must be a sufficient number of rivets through the rafter angles to transmit the 7000 lbs. More are put in here so as not to exceed the maximum allowed pitch.

It will be noted that the rivet spacing dimension line for each member starts at the *center*. A connection by a single rivet should never be used, and preferably at least three rivets should be used in any connection.

Joint c. A splice is made here in the bottom chord because it changes section, and it is made a field splice because the truss is too large to ship in one piece. Each truss is shipped in four pieces. The middle section of bottom chord and the vertical member *Ee* are two of these. The greatest depth of any piece will then be over 12 ft. at *Cc*, and this cannot be handled by all railroads.

The horizontal components of *Cc* and *cd* act toward the right and their sum, equal to 15,600 lbs., must be transmitted to *bc*. (15,600 lbs. is the difference in the stresses in *bc* and *ce*.) This requires $\frac{4688}{15600}=4$ rivets in bearing on the $\frac{3}{8}$-in. gusset plate. The bottom chord splice will require $\frac{31200}{3068}=11$ rivets in single shear. We must have 11 rivets on each side of the splice, in the splice plate, which also acts as a connection for the bottom chord rods, strut and tie. The three rivets through *ce* and the gusset plate are not counted as a part of the splice (Spec. Art. 38) but are put in because there should be a connection between the vertical as well as the horizontal legs of the angles. The splice plate should have as much *net section* as the angles of *ce*. Even with the minimum thickness of plate allowed there is a large excess in this case.

Lateral Connections. The lateral connections should be sufficient to take the full value of the area of a $\frac{3}{4}$ in. rod at 18,000 lbs. per sq. in. (Spec. Art. 13.) We have then

$$0.44\times 18{,}000=7900 \text{ lbs.}$$

If we use a $1\frac{3}{4}$ in. pin for the lateral rods which have forked loops, the allowed bearing pressure of the pin on the $\frac{1}{4}$ in. plate will be $\frac{1}{4}\times1\frac{3}{4}\times25{,}000=10{,}900$ lbs.

It is very essential that clearance be provided where two members come together, except where tight joints are required, as in the bottom chord splice and at the ridge. The usual minimum clearance of members is $\frac{1}{4}$ in.

Rivet holes are made $\frac{1}{16}$ in. larger in diameter than the size of the rivet to be used. In roof work for lateral connections, pin holes are usually punched, and are made $\frac{1}{16}$ in. larger than the pin. Sizes of all rivets and holes must be plainly marked on the drawings.

The exact length of each piece must be given with its other dimensions. The length should invariably be given last. The width of a plate should be given first and the longer leg of an angle should be given first, thus, $1-15''\times\frac{3}{8}''\times1'\ 7\frac{1}{4}''$, $2Ls\ 4''\times3''\times\frac{5}{16}''\times21'\ 7\frac{1}{4}''$. The width of a plate should always be given in inches, and should not contain a fraction less than $\frac{1}{4}$ in.

For the use of the templet maker, the bevel of each inclined line of rivet holes should be given. The longer dimension of the bevel is usually made 1′ 0″. All dimensions, other than the widths of plates, of one foot or more should be given in feet and inches, and not in inches alone, thus $1'\ 1\frac{3}{16}''$ and not $13\frac{3}{16}''$.

While no dimension is ever to be taken by scale, off a shop drawing, it is nevertheless essential to *draw by scale*. This can not be done unless the drawing is worked up in a logical manner. A draftsman who makes many erasures will seldom become interested enough in his work to be a success. *Rivet heads and rivet holes should be drawn to scale.*

Accuracy is essential, but no smaller fraction than $\frac{1}{32}$ of an inch is ever used in structural work. If a line of spacing should add up $10'\ 6\frac{15}{32}''$, $10'\ 6\frac{1}{2}''$ *will not answer.*

All spacing must be continuous from center to center, and the different sets of spacing should be kept separate and in straight lines if possible, not offset lines. First we have the general dimensions such as span and length of rafter, center to center; second, we have the distance center to center for each member; third, we have the rivet spacing which must be con-



Marking Diagram.

All Rivets $\frac{7}{8}$" Holes $\frac{15}{16}$"
Unless otherwise noted.


3 Right Truss Segments Reg. Mark T1R (Shown)
3 Left " " " T1L
3 Right " " " T2R
3 Left " " " T2L
4 " " " T3R
4 " " " T3L
} Omit Lat. Comm. as noted.
All Purlin Clips L 3½ x 3 x 5/16 x 0'-10"
Pinhole 1/16
Fill 2½ x ⅜ x 0'-10½"
} Omit on T3R & T3L
5 Purlin Spaces @ 4'-5" = 22'-1"
20'-2¼" c. to c. Holes
11'-5½"
3 att. sp. @ 2'-2½" = 6'-7½"
2'-3½"
2'-6"
7'-6"
9'-3"
9'-2"
10 att. sp. @ 2'-1⅝"
Pl. 6½ x ⅜ x 1'-1"
Pl. 17½ x ⅜ x 2'-11"
Pl. 11⅜ x ⅜ x 1'-10½"
Pl. 13½ x ⅜ x 2'-11"
Pl. 13⅜
3 sp. @ 2'-7½" = 7'-9½"
12'-9⅝"
2L 3½ x 3½ x 5/16 x 25'-5½"
4½
13 sp. @ 2½" = 2'-8½"
3'-1"
3 sp. @ 2'-11½" = 8'-10½"
81'-9" c. to c.
22'-4⅝"
Shoe Pl. 12'-½" x 1'-0"
13/16" x 2" Slotted holes in T1L, T2R & T3L
13/16" Round " " T1R, T2L & T3R
For Anchor Bolts.
Lat. Pl. 7½ x ½ x 0'-10"
Pin Hole 1/13"
} Omit on Segments T3R & T3L
22'-9⅞" c. to c. holes
Pinhole

Fig. 36.


Omit on 1/3 R & 1/3 L
Omit on 1/3 R & 1/3 L
20'-10" c. to c. Holes
4 Purlin Spaces @ 4'-6 1/2" = 18'-2"
11'-5 3/32"
3 alt. sp. @ 2'-6"=7'-6"
11'-5 3/32"
2'-2 3/32"
11 alt. sp. @ 2'-1'-10"
3 alt. sp. @ 2'-4 1/2"=7'-1 1/2"
Pl. 6 1/2"x 3/8"x 1'-1" Same as Plate B
Same as Bb
Pl. 11 3/4"x 1'-0 1/2" Same as Plate b
Pl. 24"x 3/8"x 3'-8" On Segments TR and L
3-3R @ 2'-7 1/2"=7'-10 1/2"
12'-9 1/2"
10 Verticals Reg. Mark Ec
2 L 2"x 2"x 1/8"
5 sp. @ 3'-0"=15'-0"
20'-5 1/2"
Same as member BC
3 sp. @ 2'-5 1/2"=7'-4 1/2"
11'-5 3/32"
2 L 6"x 3 1/2"x 7/16"x 45'-3 7/16"
2 L 2"x 2"x 1/4"x 11'-5 3/32"
3 sp. @ 2'-10"=8'-6"
12'-9 1/2"
10 Bot. Chords Reg. Mark cc
Pl. 7 1/2"x 3/8"x 0'-10"
2 L 3"x 2 1/2"x 1/4"x 30'-0 3/8"
4 sp. @ 2'-10 1/4"=11'-5"
2'-10 7/16"
15'-3 15/16"
27'-6 3/8"
Make other side of splice plate symmetrical with this on 1/3 R & 1/3 L
Pl. 23"x 1/2"x 2'-5 1/2"
Pinhole 1 1/16"
29'-2" c. to c. holes

(Between pp. 70–71)

nected with the centers; and fourth, we have the open holes, which should be connected up for the benefit of the inspector. If there are holes in both legs of an angle, there must be two lines of spacing.

Each rivet hole must be located definitely, cuts on plates shown, and bevels of center lines given. The gages of all rivet lines must be given.

The good appearance of a drawing goes far to inspire confidence in its accuracy. It should be workmanlike. The appearance of a drawing depends largely upon the lettering and general arrangement. Except in the title, the letters should all be free hand and of a plain style. The figures should be particularly clear. Figures and letters should not all be the same size. The dimensions of a main member should be in larger figures than those for a detail, and center distances larger than rivet spacing. It is essential that the sizes of plates, angles, etc., be in the best possible place for them. Shop men are not supposed to be able to read a drawing as readily as a draftsman or templet maker. To become a proficient letterer, persistent practice is necessary, and will work a wonderful improvement in any man's work.

The title and sheet number should be in the lower right hand corner, if possible. The name of the draftsman and the date when the drawing was finished, should appear in the title as well as a statement of what is shown on the drawing.

CHAPTER IV

PLATE GIRDER BRIDGES

34. Construction and Uses. A plate girder is a built up I-beam. It consists of a single web plate [1] and two flanges (top and bottom) riveted together. Each flange may be composed of two angles, two angles and one or more cover plates, two angles with side and cover plates or, in very heavy girders, four angles with side and cover plates in various combinations. Fig. 37 shows some common flange sections. Types (*e*) and (*f*) are



FIG. 37.

frequently used for crane girders where a load is applied along the edges of the flange.

Plate girders are used in buildings and bridges where something larger than a rolled I-beam or I-beam girder is required. In buildings they are used for floor and crane girders and in bridges, for stringers and floor beams, and for the girders of plate girder bridges.

Plate girder bridges are seldom built for spans of more than 100 ft., though some have been built over 130 feet long. The railways use them almost exclusively for spans from 30 ft. to 100 ft., when steel bridges are used, and many of the better class of highway bridges of these lengths are plate girders.

A plate girder bridge is usually considered to be the most durable kind of metal bridge.

[1] When two web plates are used a few inches apart, it is called a "box girder."

35. Stresses in Girders.[1] A plate girder is treated as a solid beam and the stresses are investigated by the method of sections,[2] the stresses acting upon a cross-section being the ones usually found.

The loads, including the weight of the girder itself, which a girder carries, together with the reactions produced by them, are usually a series of forces parallel to the cross section of the girder. (Vertical loads on a horizontal beam.) These forces produce a shear at the section equal to the algebraic sum of all the forces on one side of the section, and a bending moment equal to the moment of all the forces on one side of the section about the section. These are resisted by a shearing stress S at the section and by the moment of a couple. This resisting couple is produced by the compressive stresses on one part of the section and the tensile stresses on the other. These are shown in Fig. 38, F being the resultant of all the compressive stresses and F' the resultant of the tensile stresses on the section. The lever arm of this couple is d, the distance between these resultants, and the moment Fd must equal the bending moment of the external forces if we are to have equilibrium. The intensities of the compressive and tensile stresses vary uniformly from zero at the neutral axis to a maximum intensity at the top and bottom. Since the greater part of the area of the cross section is in the flanges and the intensities are greatest at the top and bottom, the resultants, F, come near the top and bottom of the girder, making d large. Fd is the *moment of resistance*, and it is well to remember that it is equivalent to the moment of a couple, and that *both the web and flanges resist bending.*



FIG. 38.

36. The Web. It is not known just how the shearing stresses are distributed over an I cross section. We know that their intensities must be zero at the upper and lower edges of the

[1] See Heller's "Stresses in Structures," Art. 75, page 111.

[2] See Heller's "Stresses in Structures," Art. 64, page 85.

girder, and are a maximum at the neutral axis.[1] The law of variation between these extremes depends upon the cross section. For an I cross section, the usual assumption that the shearing stress is uniformly distributed over the area of the web *only*, will give an intensity of shearing stress which will usually be greater than the actual maximum.[2] The flanges form a large part of the cross section and must carry considerable shear.

It is therefore *always assumed* that the web carries *all of the shear*[3] and that its intensity is uniform.

$$A_w = ht = \frac{S_{\max}}{s_s}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)^4$$

Equation (1) will determine the minimum area of web permissible. Its thickness is never made less than $\frac{1}{4}$ inch and seldom less than $\frac{3}{8}$ inch. It must be made thick enough to give sufficient bearing for the rivets which connect the flanges to it, and this consideration frequently determines its thickness.[5]

The depth, h, is determined by considerations of economy as explained in Art. 38, or by local conditions.

When there are splices in the web, it is not strictly correct to take the gross area as effective in resisting shear. It may be assumed that the rivets of the first row in the splice take up one half of their proportion of the shear on one side of the plane through the center of the row. (15.) Then the net section of the web through this row should be sufficient to take the balance of the shear. This would make equation (1) read as follows:

$$\frac{S_{\max} - \frac{1}{2}\text{ Value of rivets in row}}{s_s} = (h - \text{holes})t \quad . \quad . \quad (2)$$

Formula (2) is *not* used in practice, and the difference in the result by the two is usually small.

[1] For a discussion of this subject on the assumption that a sudden change in width of the cross section has no effect upon the distribution of the shearing stress, see Johnson's "Modern Framed Structures," Chapter VIII, Art. 130, page 145.

See also Rankine's "Applied Mechanics," Art. 309, page 338.

[2] See Heller's "Stresses in Structures," Art. 71, page 105.

[3] When the flanges are inclined, they carry a part of the shear.

[4] See Heller's "Stresses in Structures," Eq. 33, page 111.

[5] See an article by C. H. Wood in Eng. News, Aug. 6, 1908.

The web resists considerable bending moment, as will be seen if the formula,

$$M = \frac{sI}{v}, \quad \ldots \ldots \ldots \quad (3)^1$$

is considered. If, for example, the moment of resistance of the web is $\frac{1}{7}$ of the total moment of resistance of the cross section, the web will resist $\frac{1}{7}$ of the total bending moment and the flanges will resist $\frac{6}{7}$ of it. The resultant of the two kinds of stresses caused by shear and bending, in the web is never calculated, but to compensate for this, it is often assumed that the flanges take all the bending stresses, which, of course, has the effect of making them larger and thus reducing the stress in the web. But if it be remembered that the shear is *not* a maximum where the bending is, it will be seen that, theoretically, this increase of flange section is not necessary.

37. The Flanges. The bending stresses in a girder may be provided for by making the cross section such that the extreme fiber stress, given by equation (3) will not exceed the maximum allowed unit. This, however, involves much labor, as there are no complete tables of section moduli of plate girders as there are of I-beams, and the solution, involving the two unknown quantities I and v, must be by trial.

When the flanges are alike, as they usually are, the solution is very much simplified by making two assumptions:[2]

"1. The stresses in the flanges (tension and compression) are uniformly distributed over their areas and their resultants, (F, Fig. 38) therefore, act at the center of gravity of these areas.

"2. That the depth of the web h, may be set equal to d, the distance between the centers of gravity of the flanges."

Granting these, it is easily shown that the moment of resistance of the web is equal to the moment of resistance of $\frac{1}{6}$ of the web area, concentrated at the center of gravity of each of the flanges.

[1] For derivation see Heller's "Stresses in Structures," Art. 66, page 89, or any book on Mechanics.

[2] See Heller's "Stresses in Structures," Art. 75, page 111, for a complete discussion.

Then we have

$$\text{Equivalent flange stress} = \frac{M}{d} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

$$\text{Equivalent flange area} = \frac{\text{Equiv. flg. stress}}{s_w}, \quad . \quad . \quad (5)$$

$$\text{Reqd. flange area proper (net area one flange)} = \text{equiv. flg. area} - \tfrac{1}{6} A_w \, . \quad (6)$$

If, for any reason, there are vertical lines of rivet holes in the web, its moment of resistance is decreased, and this is sometimes taken into account by modifying Eq. (6) as given in equation (7) below.[1]

$$\text{Reqd. flange area proper (net area one flange)} = \text{equiv. flg. area} - \tfrac{1}{8} A_w. \quad . \quad (7)$$

The effect of the rivet holes on the moment of resistance of the web may be easily calculated.

Some specifications require that all of the bending stresses shall be considered as being resisted by the flanges, in which case the equivalent flange area as given by equation (5) becomes the required net flange area proper.

Since d, the *effective depth*, cannot be calculated until the flanges are known, an approximate value must be used on the first trial. Two or three trials will usually give a flange which is practically exact.

In equation (5) the working stress for the tension flange is used, thus giving the required *net* area of that flange. (See Art. 19 for allowance to be made for rivet holes.) The top flange is usually made the same as the bottom flange (gross areas alike) but it must be held so that it will not buckle sidewise.[2] (See Arts. 43 and 44.)

38. Economic Depth.[3] The most economical depth of a plate girder is usually the least weight depth. It depends upon

[1] See "Specifications of the American Railway Engineering Association for Steel Railroad Bridges," 1910, Art. 29.

[2] See "Spec. of the Am. Ry. Eng. Assoc.," Arts. 30 and 80. Also Cooper's "Spec. for Steel Railway Bridges," 1906, Art. 79.

[3] See Johnson's "Modern Framed Structures," Art. 285, page 332.

a number of conditions and may be easily calculated, theoretically, when these conditions are known. The calculated, economic depth is seldom used exactly, on account of local conditions and practical limitations, and is to be regarded merely as a general guide. A variation in depth of as much as 10% or 15% will usually not change the total weight of the girder appreciably.

Formulas will now be deduced for the economic depth for the following three conditions as to flange section:

(a) When $\frac{1}{6}$ of the web area is considered in each flange.

(b) When $\frac{1}{8}$ of the web area is considered in each flange.

(c) When none of the web area is regarded as flange area.

The girder will be assumed of constant cross section from end to end.

(*a*) *When* $\frac{1}{6}$ *of the web area is regarded as flange area.*

The gross area of the cross section of the girder

$$= ht + 2A_F + \text{rivet holes.}$$

From equations (4) and (6), $A_F = \frac{M}{ds_t} - \frac{1}{6}dt$, and then we have, setting $h = d$,

$$A = dt + \frac{2M}{ds_t} - \tfrac{1}{3}dt + \text{rivet holes.}$$

The gross area of the flanges may be taken as 15% greater than the net area, which gives:

$$A = 0.617dt + \frac{2.3M}{ds_t}.$$

As the weight varies directly with the cross section, for a least weight depth we may differentiate this expression with respect to d and set the first derivative equal to zero.

$$\frac{dA}{dd} = 0.617t - \frac{2.3M}{s_t d^2} = 0,$$

from which

$$d^2 = \frac{2.3M}{0.617s_t t}$$

and

$$d = 1.93\sqrt{\frac{M}{s_t t}}. \quad \ldots\ldots\ldots \quad (8)$$

(*b*) *When $\frac{1}{8}$ the web is taken as flange area*, equation (8) becomes

$$d = 1.80\sqrt{\frac{M}{s_t t}}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (9)$$

(*c*) *When no web is considered as flange area*, equation (8) becomes

$$d = 1.52\sqrt{\frac{M}{s_t t}}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (10)$$

When the flange section is not constant for the entire length of the girder, the economic depth will be somewhat less than that given by the above formulas, and will vary with the proportion of cover plates, stiffeners, and web splices. The following equation will give the least weight depth as close as a general formula can give it.

$$d = \sqrt{\frac{M}{s_t t}}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (11)$$

39. Stiffeners. The lines of maximum compression in a plate girder web, cross the neutral axis at an angle of 45° and extend downward toward the supports from the middle.[1] The tendency of the web plate to buckle under these compressive stresses is, in part, resisted by the equal tensile stresses at right angles to them. Just what the resulting effect on the web is, is not well understood, but when the ratio of the depth of the web to its thickness is great (exceeds about 50 or 60) it must be stiffened. Of course the requirement of stiffeners depends upon the amount of shear at the point.[2]

Stiffeners are placed vertically on account of ease of manufacture. They would, perhaps, serve their purpose better if placed parallel to the line of the compressive stresses, but if placed vertically and not more than the depth of the girder apart, or 5 or 6 feet for deep girders, they will prevent any buckling of the web.

There is no rational method of determining the size of these stiffeners. Some specifications[2] give column formulas for this

[1] See Heller's "Stresses in Structures," Art. 73, page 109.
Also see Johnson's "Modern Framed Structures," Art. 130, page 147.

[2] See Cooper's "Specifications for Steel Railway Bridges," 1906, Art. 47.
See also "Spec. of the Am. Ry. Eng. Assoc.," 1910, Art. 79.

but there is no rational basis for it. Experience only determines their size and spacing.

Sometimes fillers are put under the stiffeners, between the flange angles, and sometimes the stiffeners are "off set" or "crimped" over the flange angles as shown in Fig. 39. Fillers should be used under stiffeners bearing concentrated loads, or where there is anything connecting to the girder by means of the stiffener.

FIG. 39.

Stiffeners should be placed at the ends of a girder, to transmit the end reaction from the web, and at all points of concentrated loading. Stiffeners should bear tightly against the horizontal legs of the flange angles at all points of concentrated loading, as the load must be transmitted to the stiffener by direct bearing upon its end, and from the stiffener, by means of rivets, to the web.

The outstanding leg of the stiffener should not project beyond the edge of the flange angle, and the other leg need only be large enough for the rivets.

40. Web Splices. For small girders, such as stringers and floor beams, the web plates can usually be obtained from the mills in one piece, and no web splices are necessary. When, however, the size of the girder is increased, the web plates cannot be obtained in single lengths and must be spliced.[1]

The stresses carried by the web at the point must be transferred through the splice plates from one web plate to the other. If no bending moment is regarded as being carried by the web plate, only the shear has to be provided for, and the calculation of the rivets is a very simple matter. In this case a splice similar to that shown in Fig. 40 is used. The rivets are usually not spaced over 5 inches apart, and usually two rows are used on each side of the splice, although this often gives an excess of rivets.

Two splice plates should always be used and their combined thickness should be greater than the thickness of the web. A pair of stiffeners is usually placed over the splice.

When a part of the bending moment is regarded as being carried by the web, the web splice must be designed to provide

[1] For maximum sizes of plates which may be obtained, see "Cambria," page 28. These limits vary considerably with different mills.

for this stress in addition to the shear. The simplest form of web splice to calculate, in this case, is that shown in Fig. 50, in which the plates *FG*, near the flanges, are *assumed* to take care of the bending moment in the web, and the vertical plates *HK*, are assumed to take all the shear. These assumptions give an excess of plate and of rivets, but a rigid calculation would make a splice of practically the same cost. See Art. 44 for the design of such a splice.



FIG. 40.

In order that the allowed unit stress in the flange proper may not be exceeded, it is necessary to reduce the allowed unit stress in the splice plates *FG*, in proportion to their distance from the neutral axis. The entire solution must, in any case, be by trial.

The form of splice shown in Fig. 40 may be used in place of that of Fig. 50, but the rivets must be calculated so that the resultant of the horizontal and vertical stresses (due to moment and shear) in the outermost rivets will not exceed the allowed stress on a rivet. (20) This would also be the exact method of calculating the rivets in Fig. 50. In Fig. 40 the splice plates act as a beam 8′ 7½″ deep to carry the web bending moment, and the extreme fiber stress in them must not exceed the unit stress in the girder at an equal distance from the neutral axis. If the rivets through the web in the outer rows have a small pitch, one-eighth of the web area may not be available as flange area (37).

41. Flange Riveting. The stress in the flange of a girder, at the end, is zero, and it increases to a maximum somewhere between the supports (for a girder supported at the ends). The increase of the flange stress is due to the addition of the hori-

zontal shears from the web,[1] and the rivets connecting the flange to the web at any point, must be sufficient to transmit this horizontal increment.

Fig. 41 shows any part of a girder, supported in any manner. M and S are the known moment and shear at the section AB, then

$$M_x = M + S(x-m) - P_1(x-a) - P_2(x-b) - P_3(x-c).$$

Differentiating with respect to x, $\frac{dM_x}{dx}$ will give the rate of increase of the moment along the girder.

$$\frac{dM_x}{dx} = S - P_1 - P_2 - P_3 = S_x.$$

The flange stress at any point is $\frac{M_x}{d}$ and, therefore, the rate of increase of the flange stress will be

$$\frac{dM_x}{dx} \div d = \frac{S_x}{d}, \quad \ldots\ldots\ldots \quad (12)$$

or, in words, the increase of the flange stress per inch will be equal to the shear at the point divided by the effective depth of the girder in inches and sufficient rivets must be provided, connecting the flanges to the web, to transmit this increment. Then, to obtain the maximum permissible rivet pitch in inches at any point, the value of a rivet must be divided by the increment per inch. (If there is no vertical load on the flange.)



FIG. 41.

In a girder whose cross section is *constant from end to end*, and in whose design a part of the web has been considered as flange area, the pitch of the rivets may be increased because the part of the flange stress which is carried by the web does

[1] See Heller's "Stresses in Structures," Arts. 17 and 70.

not have to be transmitted by the rivets. Since the flange stresses are directly proportional to the flange areas, we have from equation (12) when one-sixth of the web is regarded as flange area,

$$\textit{Increment of stress in flange proper} = \frac{S_x}{d} \times \frac{A_F}{A_F + \frac{1}{6}A_W}, \quad . \quad . \quad (13)$$

or when one eighth of the web is regarded as flange area,

$$\textit{Increment of stress in flange proper} = \frac{S_x}{d} \times \frac{A_F}{A_F + \frac{1}{8}A_W}. \quad . \quad . \quad (14)$$

In a girder with cover plates which do not extend the full length of the girder, and in whose design a part of the web has been regarded as flange area, equation (13) or (14) may be used for that portion of the girder at the ends, whose cross section is constant, but when, passing toward the middle, the first increase in flange section is made by the addition of a cover plate, the flange angles and the part of the web considered as flange area have already received their maximum allowed stress (see Fig. 48) and, therefore, all of the flange stress increment must go into the cover plate and enough rivets to transmit it must be provided, both through the angles and web, and through the cover plate and angles.

So far we have considered only the flange stress increments as affecting the pitch of the rivets. If there are any loads resting upon the flange of the girder, they must be transmitted to the web, and since the web plate is not flush with the backs of the angles, the rivets in the flange must perform this duty unless the load is carried directly by stiffeners.

The top flange of a deck plate girder is a case of this kind, and the resultant of the two stresses (vertical and horizontal) on a rivet must not exceed the allowed rivet value.

Usually only three or four different groups of rivet pitches are used in the half length of a girder. The pitch need be figured only at three or four points and then a curve can be drawn through these, which will give the pitch at any other point with sufficient accuracy. See Fig. 43 and Fig. 49.

The riveting in the two flanges is always made the same when possible, although this gives an excess in the bottom flange.

Sometimes the pitch of rivets in the flange angles will determine the width of the vertical leg of the angles which may be used. For instance, if 2*Ls* 4″×4″ would answer for the flange of a stringer, and it was found that the pitch of rivets required was less than the minimum allowed in a single line, (13) an angle with a vertical leg wide enough for two gage lines would have to be used.

Sometimes the thickness of the web plate will have to be increased over that which would be required to resist the shear, in order to provide sufficient bearing area for the flange rivets, so that they will not have to be spaced closer together than the minimum allowable pitch. Also the web must be thick enough so that there is sufficient net area, horizontally between the flange rivets, to carry the horizontal increment of flange stress. These considerations sometimes make it necessary to use a thicker web plate at the ends of a girder than in the middle.[1]

42. Flange Splices. There are two conditions which may make it necessary to splice the flange of a plate girder even if the girder is not going to be shipped in more than one piece. These are,

1st. The flange angles may be so heavy that they cannot be obtained in one piece, of the length required.

2nd. When the girder is for a through bridge, frequently the upper corners are rounded for appearance, and the top flange angles and one cover plate run down the ends of the girder. In this case, the flange is spliced near the ends, so that the long pieces will not have to be handled in the blacksmith shop in heating, bending and annealing.

The flange splices should always be made as near the ends as possible, where the flange stress is least; and the joints in the component parts of the flange should break joints.

The splices are made by means of splice angles cut and ground to fit the inside of the flange angles and by splice plates on the top. The net section of the splice plates and angles does not have to equal the entire net section of the flange cut, unless the entire strength of the cut portion is required at the point of splice. The size of the splice plates and angles and the number of rivets required are determined by the *proportion* of the actual stress at the point, carried by the part cut.

[1] See an article by C. H. Wood in Eng. News, Aug. 6, 1908.

To illustrate the application of the principles set forth in this chapter, the design and methods of calculation for a stringer and a deck plate girder bridge, will now be given.

43. Design of a Stringer. The stringer of a railroad bridge is the simplest form of plate girder. We will assume the following data:

Panel length 27′ 0″, Stringers 6′ 6″ center to center,
Loading Cooper's Class E 40,

Specifications, Cooper's 1906 for Railway Bridges, material medium steel, except rivets.

The design of any structure should commence with that part which carries the load directly, and proceed in order, to the foundations. Hence the first part of our structure to be designed is the ties, next the stringers, the floor beams, the trusses and last the foundations.

Sections 12 to 15 of the specifications will govern the design of the ties.

The dead load on a tie consists of the rails, guards, and the tie itself. These may all be considered as concentrated at the rails without appreciable error.

Dead load concentrated at each rail,

Rails. (Spec. §23) ..... $\frac{100}{2}\times\frac{14}{12}=$ 58 lbs.

Guards 6″×8″ ..... $4\times4\frac{1}{2}\times\frac{14}{12}=$ 21 lbs.

Ties, say 8″×8″×10′ ..... $5\frac{1}{3}\times5\times4\frac{1}{2}=$120 lbs.

Total ..... 199 lbs.



FIG. 42.

Section 23 of the specifications requires that not less than 400 lbs. per foot of track be used so the dead load will have to be taken as,

$$\frac{400\times14}{2\times12}=233 \text{ lbs. per rail per tie.}$$

Fig. 42 shows the forces acting on a tie.

The live load concentrated at each rail (Spec. § 15 and 23).

$$=\frac{100000}{4\times 3}=8330 \text{ lbs.}$$

Dead load moment $= 233\times 0.75 = 175$ ft. lbs.
Live load moment $= 8330\times 0.75 = 6250$ ft. lbs.
Total moment $= 6425$ ft. lbs.

Substituting in equation 3, Art. 36 we may solve for the required depth of the tie directly if we assume the width.

Assuming the ties to be 8 inches wide,

$$M=\frac{sI}{v}=6425\times 12=\frac{1000\times 8d^3}{12\times \frac{1}{2}d}.$$

$d^2=57.8$ and $d=7.6$ inches. Use $8''\times 8''$ ties spaced 14 inches center to center, which gives a dead load per linear foot of track from the floor which is less than 400 lbs., so 400 lbs. must be used.

The weight of the stringer will be taken at 160 pounds per lineal foot. This gives a total dead load per lineal foot of stringer of 360 pounds.

$$\text{The dead load moment}=\frac{360\times 27\times 27}{8}=32{,}800 \text{ ft. lbs.}$$

The live load moment (see Spec. Table I) = 344,600 ft. lbs.[1]

Depth. The depth of the stringer must now be decided upon. The economic depth may be determined from equation (10), as § 46 of the specifications directs that no part of the web area may be considered as flange area. The value of s_t to use in the formula is determined from § 31 of the specifications, and is different for live and dead loads. The dead load moment may be reduced to an equivalent live load moment, in this case by dividing it by 2, and then the live load unit stress may be used with the resultant total moment. This will give a total equiva-

[1] For method of calculation of maximum moment see Heller's "Stresses in Structures," Art. 134, page 260.

lent moment of 361,000 ft. lbs. Assuming the web to be $\frac{3}{8}''$ thick we get

$$d = 1.52\sqrt{\frac{361000 \times 12}{10000 \times \frac{3}{8}}} = 51.6 \text{ inches.}$$

There are usually local conditions such as under clearance, height from base of rail to masonry, etc., which limit the depth of the stringers in a bridge and make it necessary to use a depth considerably less than the theoretical economic depth. In this case we will assume that we are not so restricted and that we can use a 51″ web plate. This will give an area of web of $51 \times \frac{3}{8} = 19.13$ sq. in.

The maximum shear is as follows:

Live load end shear = 59,300 lbs. (See Spec. Table I.)
Dead load end shear = 4,900 lbs.

Total max. end shear = 64,200 lbs.

This will give a maximum unit shear on the web of $\frac{64200}{19.13} = 3360$ lbs. per sq. in., which is safe.

The depth back to back of angles is always made $\frac{1}{4}''$ more than the depth of the web plate so that the web will not project beyond the angles at any point.[1] An approximate effective depth must now be assumed (37) for determining the required flange. We will take 50.5 inches.

Flanges. The following are the approximate flange stresses:

$$\text{Dead load} = \frac{32800 \times 12}{50.5} = 7{,}800 \text{ lbs.}$$

$$\text{Live load} = \frac{344600 \times 12}{50.5} = 81{,}900 \text{ lbs.}$$

Dividing these by their respective unit stresses, we get,

[1] Sometimes on stringers without cover plates, the web is made to project an inch above the top flange angles and the ties are notched for this instead of over the entire flange.

$$\text{Approx. req. D.L. area} = \frac{7800}{20000} = 0.39 \text{ sq. in.}$$

$$\text{Approx. req. L.L. area} = \frac{81900}{10000} = 8.19 \text{ sq. in.}$$

$$\text{Approx. req. total net area} = 8.58 \text{ sq. in.}$$

$2Ls\ 6'' \times 3\frac{1}{2}'' \times \frac{9}{16}''$ gives $2 \times 5.03 - 2 \times \frac{9}{16} \times 1 = 8.93$ sq. in. net (using $\frac{7}{8}''$ rivets).

The effective depth, using these angles with the long legs horizontal, will be $51.25 - 2 \times 0.86 = 49.53$ inches. This will give the following flange stresses:

$$\text{Dead load} = \frac{32800 \times 12}{49.53} = 8{,}000 \text{ lbs.}$$

$$\text{Live load} = \frac{344600 \times 12}{49.53} = 83{,}500 \text{ lbs.}$$

and the required areas will be

$$\text{Dead load area} = \frac{8000}{20000} = 0.40 \text{ sq. in.}$$

$$\text{Live load area} = \frac{83500}{10000} = 8.35 \text{ sq. in.}$$

$$\text{Total req. net area} = 8.75 \text{ sq. in.}$$

It will be found that the flange section above given is the most economical for this case. The actual net area only exceeds the required by 0.19 sq. in.[1]

We must now determine the rivet pitch in the flanges in order to see if we can get the required number of rivets in a single line (41) without using a less pitch than is allowed. (See Spec. § 54.)

Flange Riveting. Total max. end shear = 64,200 lbs.

The horizontal increment of flange stress from equation (12) is $\frac{64200}{49.53} = 1296$ lbs. per lineal inch. The top flange also carries

[1] In some cases, the bottom laterals of the bridge are connected to the bottom flanges of the stringers, in that case the net section is reduced by an extra hole out of the horizontal leg of one flange angle.

the weight of the floor and the live load direct, which must be transmitted to the web through the flange rivets. (41) The dead load on the top flange is 200 lbs. per lineal foot, equal to 17 lbs. per lineal inch. The maximum concentrated live load on any point of the stringer will be one driver or 25,000 lbs., (Spec. § 23) which may be considered as distributed over three ties (see Spec. § 15) spaced 14 inches center to center, making the load per inch $\frac{25000}{3\times 14}=595$ lbs. This makes the total maximum vertical load on the top flange 612 lbs. per lineal inch. The resultant of these vertical and horizontal stresses

$$=\sqrt{(612)^2+(1296)^2}=1432 \text{ lbs. per lineal inch.}$$

The value of a rivet in bearing on the web is 3938 pounds. (See Spec. § 40, floor system. See also table of rivet values in Art. 72.) The maximum allowed pitch at the ends then will be $\frac{3938}{1432}=2.75$ inches, which is greater than three diameters of the rivet and is, therefore, allowable in a single line.

The required pitches may be determined in a similar manner at the quarter point and center after the shears at these points have been calculated, and when plotted, as in Fig. 43, we can scale the required pitch at any point. The actual pitches used should come within the curve, as shown by the stepped line.



FIG. 43.

The curve of required pitches in Fig. 43 was plotted by calculating the pitches at a number of points, but a straight line from the end to the quarter point and from the quarter point to the center would give results close enough.

Stiffeners. According to the specifications, § 47, the web must be stiffened when the shearing stress per square inch exceeds $10{,}000-75H$, in which H is the ratio of the depth of the web to its thickness. By this formula, the maximum allowed shearing stress on this web, without stiffeners, is a negative quantity, so stiffeners must be used throughout the length, spaced not

more than the depth of the girder apart (Spec. § 47). We will have to put in six pairs of intermediate stiffeners in order to keep within this limit.

The size of the stiffeners must be determined by the column formula given in the specifications § 48. The smallest angles which can be used with $\frac{7}{8}''$ rivets have 3″ legs ("Cambria," page 46) and the thinnest metal allowed is $\frac{3}{8}''$ thick (Spec. § 82), so for the stiffeners we will try $2Ls\ 3''\times3''\times\frac{3}{8}''$. The radius of gyration of the stiffeners, fillers and enclosed web, perpendicular to the web is 1.35 in.

$$P=10{,}000-45\frac{l}{r}=10{,}000-45\frac{51}{1.35}=8300 \text{ lbs. per sq. in.}$$

The gross area of the stiffeners, fillers and enclosed web is



FIG. 44.

8.72 sq. in., therefore, the stiffeners are good for a shear of $8.72\times8300=72{,}300$ lbs., which is greater than the maximum shear in the girder.

The specifications § 79, require that the *compression flanges* of beams and girders shall be stayed against transverse crippling when the length is more than sixteen times the width. In this case the top flanges may have an unsupported length of about 16 feet. They may be held by means of a subdivided Warren lateral system of single angles between the top flanges, as shown in Fig. 44, making the unsupported length of the flange about 9 feet. The size of these angles may be determined by the minimum requirements of the specifications §§ 82 and 83. A common size is $3\frac{1}{2}''\times3''\times\frac{3}{8}''$.

If the track is on a curve, these angles must be made large enough to take care of the centrifugal force.[1]

Estimate of Weight. An estimate of the weight of the

[1] See Heller's "Stresses in Structures," Art. 166, page 307.

stringer will now be made to see how it compares with the weight assumed in the dead load. (160 lbs. per foot.)

Flanges $4Ls\ 6'' \times 3\frac{1}{2}'' \times \frac{9}{16}''$ @ 17.1	= 68.4 lbs. per foot.
Web $51'' \times \frac{3}{8}''$	= 65.0 lbs. per foot.
Stiffeners $2Ls\ 3'' \times 3'' \times \frac{3}{8}''$ (equivalent)	= 22.6 lbs. per foot.
Bracing $1L\ 3\frac{1}{2}'' \times 3'' \times \frac{3}{8}''$ (equivalent)	= 5.0 lbs. per foot.
	161.0 lbs. per foot.
Rivets, say 3%	= 4.8 lbs. per foot.
	Total = 165.8 lbs. per foot.

This is near enough to the weight assumed so that no recalculation will be necessary.

In all cases the assumed dead load should be checked with the final estimate to make sure none of the actual stresses will exceed those provided for in the design, and also to see if any excess of material has been used over that actually required.

No web splices are necessary, as the web plates can be obtained from the mills in one piece. (See " Cambria," page 28.)

44. Design of a Deck Plate Girder Bridge. The following data will be assumed:

Span, 103 ft. extreme (100 ft. c. to c. of bearings).

Loading, Cooper's Class E 50.

Specifications, American Railway Engineering Association, 1910.

The width center to center of girders should not be less than about $\frac{1}{12}$ the span, and should never be less than 6 feet for a standard gage track. We will use a width of 8 feet center to center.

Floor. The ties will be made 8 inches wide, spaced with 6-inch openings (Spec. § 5). The maximum driver load will be that due to the special loading (Spec. § 7) and will be for one rail $\frac{5}{4} \times \frac{50000}{2} =$ 31,200 lbs. This is assumed to be distributed over three ties (Spec. § 5), making a pair of loads of 10,400 lbs. each on each tie, besides the dead load. To this must be added 100% of the live load for impact (Spec. § 5) and the dead load may be taken at 200 lbs. at each rail for each tie, making a total



FIG. 45.

of 21,000 pounds at each rail. The maximum moment on the tie will be $1\frac{1}{2}\times 21{,}000 = 31{,}500$ ft. lbs. See Fig. 45. Substituting in the formula $M = \frac{sI}{v}$ (Equation 3, Art. 36) we can solve for the depth of the tie directly.

$$31{,}500\times 12 = \frac{2000\times\frac{8d^3}{12}}{\frac{1}{2}d} \text{ from which } d^2 = 141.75. \quad d = 11.9''.$$

The ties, therefore, will be $8''\times 12''\times 11'$ long, spaced 14" center to center.

Dead Load. The weight of the floor can now be calculated (Spec. § 6).

Ties $8''\times 12''\times 11' = 396$ lbs. each $\frac{396\times 12}{14} = 340$ lbs. per lin. ft. of Br.

Guards 2—$6''\times 8''$ $8\times 4\frac{1}{2} = 36$ lbs. per lin. ft. of Br.

Rails and fastenings (Spec. § 6) $= 150$ lbs. per lin. ft. of Br.

Total weight of floor $= 526$ lbs. per lin. ft. of Br.

The weight of the steel work may be estimated by comparison with similar structures, of which the weights are known, or may be approximately determined from an empirical formula of the form

$$w = aL + b^1. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (15)$$

In the above formula b represents that part of the metal work, the weight of which does not vary appreciably with a change in span length, and may be taken at about 200 lbs. in the present example, and a we will assume as 12.5.

The weight of the steel work $= 12.5L + 200$

$= 1450$ lbs. per lin. ft. of Br.

The weight of the floor, from above $= 526$ lbs. per lin. ft. of Br.

Total dead load $= 1976$ lbs. per lin. ft. of Br.

[1] See Heller's "Stresses in Structures," Art. 118, page 219.
See also Johnson's "Modern Framed Structures," Art. 62, page 43.

Stresses. (35) The maximum live load moments and shears should be calculated at several points in the girder. Then a curve can be drawn through these values when plotted, which will represent the values at all points sufficiently close.

The maximum moment (near the center) and maximum shear (at the end) in the girder, should be calculated from the actual wheel loads,[1] and then the moments and shears at the other points may be calculated from equivalent uniform loads[2] derived from this maximum moment and shear.

The maximum moment will occur with wheel 12 near the center of the span (see Fig. 46) and the center of gravity of all the loads on the span must be as far on one side of the center as



FIG. 46.

wheel 12 is on the other. Then from Fig. 46 we can write the following equations:

$$\frac{M_A + W_A x + \frac{wx^2}{2}}{W_A + wx} = 50 + \frac{e}{2},$$

$$40 + x = 50 - \frac{e}{2}.$$

M_A = Moment about A of all loads to the left of A, on the span.

W_A = Sum of all loads to the left of A, on the span.

w = Uniform load per lineal foot.

Substituting in the above equations and solving for e and x, we get $e = 0.2$ ft. $x = 9.9$ ft.

Having determined the position of the loads, the calculation of the moment is a simple matter. The work may be greatly facilitated by the use of a moment table if one is available.

[1] See Heller's "Stresses in Structures," Art. 134, page 260.

[2] See Heller's "Stresses in Structures," Art. 144, page 269.

The maximum live load moment in the girder is 4,025,000 ft. lbs.

The maximum live load end shear will occur with wheel 2 at the end of the girder, and is 187,500 lbs.

The equivalent uniform load for moments is determined by setting the maximum live load moment equal to $\frac{wL^2}{8}$ and solving for w.

$$4{,}025{,}000 = \frac{w \times 10000}{8},$$

$$w = 3220 \text{ lbs. per lin. ft. of girder.}$$

The equivalent uniform load for shears is obtained by setting the maximum live load end shear equal to $\frac{wL}{2}$ and solving for w.

$$187{,}500 = \frac{w \times 100}{2}$$

$$w = 3750 \text{ lbs. per lin. ft. of girder.}$$

These equivalent uniform loads may be taken from the curves of Fig. 56.

From these equivalent uniform loads, the stress at any point can be obtained with sufficient accuracy.

The uniform load moment varies as the ordinates of a parabola, and can be scaled from a diagram drawn as shown in Fig. 48.

The shears will now be figured from the equivalent uniform load at the sixth points $16\frac{2}{3}$ ft., $33\frac{1}{3}$ ft., and 50 ft. from the end.

For location of points A, B, C and D see stress sheet, Fig. 55.

$$\text{Live load shear at } A = \frac{3750 \times 100^2}{100 \times 2} = 187{,}500 \text{ lbs.}$$

$$\text{Live load shear at } B = \frac{3750 \times 83.3^2}{100 \times 2} = 130{,}200 \text{ lbs.}$$

$$\text{Live load shear at } C = \frac{3750 \times 66.7^2}{100 \times 2} = 83{,}300 \text{ lbs.}$$

$$\text{Live load shear at } D = \frac{3750 \times 50^2}{100 \times 2} = 46{,}900 \text{ lbs.}^1$$

[1] The live load shear at D calculated from the actual wheel loads is 49,200 lbs., or 4.9% greater than that given by the equivalent uniform load.

To each of the stresses thus far determined, must be added the impact stress as determined by the formula given in the specifications, § 9,

$$I = S\frac{300}{L+300}.$$

Summary of Stresses.

Maximum live load moment	= 4,025,000 ft. lbs.
Impact $= \frac{4025000 \times 300}{100+300}$	= 3,018,800 ft. lbs.
Dead load $= \frac{1976 \times 100 \times 100}{8 \times 2}$	= 1,235,000 ft. lbs.
Total maximum moment	= 8,278,800 ft. lbs.
Live load end shear	= 187,500 lbs.
Impact $= \frac{187500 \times 300}{100+300}$	= 140,600 lbs.
Dead load $= \frac{1976 \times 100}{4}$	= 49,400 lbs.
Total end shear	= 377,500 lbs.
Live load shear at B	= 130,200 lbs.
Impact $= \frac{130200 \times 300}{83\frac{1}{3}+300}$	= 102,000 lbs.
D.L. $= 49400 - \frac{1}{3} \times 49400$	= 32,900 lbs.
Total shear at B	= 265,100 lbs.
Live load shear at C	= 83,300 lbs.
Impact $= \frac{83300 \times 300}{66\frac{2}{3}+300}$	= 68,200 lbs.
D.L. $= 49400 - \frac{2}{3} \times 49400$	= 16,500 lbs.
Total shear at C	= 168,000 lbs.
Live load shear at D	= 46,900 lbs.
Impact $= \frac{46900 \times 300}{50+300}$	= 40,200 lbs.
Dead load shear	= 000 lbs.
Total shear at D	= 87,100 lbs.

Depth. The economic depth (38) can now be figured from equation (11). Assuming the web to be $\frac{3}{8}$ inch thick,

$$d=\sqrt{\frac{12\times 8278800}{16000\times\frac{3}{8}}}=128.7 \text{ inches.}$$

Section 29 of the specifications directs that the thickness of the web shall not be less than 1/160 of the unsupported distance between the flange angles. If we used a $\frac{3}{8}''$ web plate, the unsupported distance between the flange angles could not exceed $160\times\frac{3}{8}=60$ inches, making the total depth of the girder not over 76 inches if we used $8''\times 8''$ flange angles. This would evidently be too shallow for economy..

We will try $\frac{1}{2}$ inch web plates, these according to § 29 of the specifications, may be made 96 inches deep if we use 8 inch flange angles.

$$\text{Economic depth}=\sqrt{\frac{12\times 8278800}{16000\times\frac{1}{2}}}=111.4 \text{ inches.}$$

The web will have to take the shear (36) without exceeding a unit stress of 10,000 lbs. per sq. in. on the gross section (Spec. 18). The required area of the web is

$$\frac{377500}{10000}=37.75 \text{ sq. in.}$$

Using a depth of 96 inches, the area of the web will be $96\times\frac{1}{2}=48.0$ sq. in.

The cost per pound of plates increases very rapidly as the width increases after 100 inches is passed, until at 130 inches wide the cost has reached about 40% excess per pound over the cost of plates 100 inches and less in width.

We will use web plates $96''\times\frac{1}{2}''$.

Flanges. For a first approximation, the effective depth of the girder (distance between centers of gravity of flanges) may be assumed as 8 ft. This gives an approximate maximum flange stress $=\frac{8278800}{8}=1{,}035{,}000$ lbs. and a required net area $=\frac{1035000}{16000}=64.7$ sq. in. According to § 29 of the speci-

fications one-eighth of the gross web area may be regarded as flange area. The following flange section will be tried.

$\frac{1}{8}$ Web $=\frac{1}{8}\times 48$	$= 6.00$	6.00
2 *Ls* $8''\times 8''\times\frac{7}{8}''$	$=26.48$	$26.48-6\times 1\times\frac{7}{8}=21.23$
$1-20''\times\frac{3}{4}''$	$=15.00$	$15.00-2\times 1\times\frac{3}{4}=13.50$
$1-20''\times\frac{3}{4}''$	$=15.00$	$15.00-2\times 1\times\frac{3}{4}=13.50$
$1-20''\times\frac{5}{8}''$	$=12.50$	$12.50-2\times 1\times\frac{5}{8}=11.25$
Total gross area	74.98 sq. in.	Total net $=65.48$ sq. in.

The net areas have been figured with two rivet holes out of the vertical legs of the angles and one out of each horizontal leg. (19.) To obtain this as a minimum net area the pitch of the rivets in the cover plates must never be less than about $2\frac{3}{4}$ inches.

The location of the center of gravity of this flange is 0.24 inch from the backs of the angles as shown in Fig. 47, making the actual effective depth $96.25-2\times 0.24=95.77$ inches. The actual flange stress then is $\frac{8278800\times 12}{95.77}=1{,}037{,}300$ lbs., making the required area $=\frac{1037300}{16000}=64.83$ sq. in.



Fig. 47.

The flange section given above will answer. A reduction in the thickness of the outside flange plate to $\frac{9}{16}$ inch will reduce the net area below that required.

Length of Flange Plates. The required lengths of the flange plates may be calculated from the equation of the parabola, in this case, as we are using an equivalent uniform load for the moments, or their lengths may be determined graphically by drawing the parabola, as shown in Fig. 48. The graphic method is nearly always used, as the moment diagram is frequently not a simple curve.

As the moments and required flange areas are directly proportional, (when the effective depth is constant) the areas will vary as the ordinates of a parabola also, and it is simpler to lay off areas as ordinates instead of moments. Any convenient scales may be chosen for lengths and areas. In this case the middle ordinate of the parabola is 64.83(=Reqd. net flange

area) and the curve may be drawn in any one of several ways, the method shown is a simple one.

After the curve of required areas is drawn in, the net areas of the component parts of the flange are measured off on the center line and horizontal lines through these points represent the parts. The required lengths of the various pieces may now be scaled off directly. The flange plates are made 2 or 3 feet longer than the theoretic length in order to provide a few rivets through the plate near the ends so that the strength may begin to be effective where it is required, and also to compensate for the fact that the actual wheel loads give slightly larger moments near the ends than the equivalent uniform load. The effective



FIG. 48.

depth decreases a little toward the ends, owing to the omission of the flange plates, and this will also make the flange stress a little greater there than is given by the parabola. For a symmetrical girder, only one half the diagram need be drawn.

The top flange plate next to the angles is nearly always run the full length of the girder, to cover the flange angles and to stiffen them near the ends, against the deflection of the ties. (See specifications § 78.)

Scaling from the diagram, Fig. 48, the following are the required lengths of the flange plates:

20″×¾″—76 ft. use 78 ft.
20″×¾″—61 ft. use 64 ft.
20″×⅝″—42 ft. use 44 ft.

Flange Riveting. The required pitch of rivets in the girder flanges will now be calculated at the end, sixth, third, and center points.

The horizontal increment of flange stress at the end may be determined from equation 14. As the top flange carries the direct load of the floor and the live load, the required pitch will be smaller for it than for the bottom flange, so the bottom flange pitch need not be figured as the two flanges are usually made alike.

$$\text{Horizontal increment} = \frac{377500}{92.58} \times \frac{41.48}{47.48} = 3560 \text{ lbs. per in.}$$

The gross areas are used for proportioning the stress. Note also that the effective depth here is less than at the middle of the girder.

The vertical load from the floor is 263 lbs. per lineal foot and the weight of the flange of the girder here is 141 lbs. per lineal foot, making a total dead load of

404 lbs. per lineal foot	=	34 lbs. per lin. in.
Live load (see Spec. §§ 5 and 31) $= \frac{25000}{40}$[1]	=	595 lbs. per lin. in.
Impact (see Spec. § 5) = 100%	=	595 lbs. per lin. in.
Total vertical load	=	1224 lbs. per lin. in.

The resultant stress on the rivets will be

$$\sqrt{(3560)^2 + (1224)^2} = 3765 \text{ lbs. per lineal inch.}$$

$$\text{Required rivet pitch} = \frac{10500}{3765} = 2.79 \text{ inches.}$$

To find the horizontal increment of flange stress at B, C, and D, we must use equation (12) because the web is here carrying all the bending stress allowed, and all the increment goes into the flanges proper.

$$\text{Horizontal increment} = \frac{265100}{93.55} = 2834 \text{ lbs. per lineal inch.}$$

$$\text{Vertical load (same as before)} = 1224 \text{ lbs. per lineal inch.}$$

$$\text{Resultant stress} = \sqrt{1224^2 + 2834^2} = 3087 \text{ lbs. per lineal inch.}$$

$$\text{Required rivet pitch} = \frac{10500}{3087} = 3.40 \text{ inches.}$$

[1] It is a question of judgment with the designer, whether this figure should be multiplied by ⅘ or not. An engine which will give a maximum shear equivalent to E50 might have a heavier driver concentration.

Horiz. increment at $C = \frac{168000}{95.77} = 1754$ lbs. per lineal inch.

Resultant stress $= \sqrt{1224^2 + 1754^2} = 2140$ lbs. per linea inch.

Required rivet pitch $= \frac{10500}{2140} = 4.90$ inches.

Horiz. increment at $D = \frac{87100}{95.77} = 909$ lbs. per lineal inch.

Resultant stress $= \sqrt{1224^2 + 909^2} = 1524$ lbs. per lineal inch.

Required rivet pitch $= \frac{10500}{1524} = 6.89$ inches.

These rivet pitches are plotted as shown in Fig. 49 and the



FIG. 49.

actual pitches used are made to come within the curve as shown by the stepped line.

The required pitch of rivets through the flange plates is determined by the horizontal increment of flange stress alone. The total shear at the theoretical end of the first flange plate is 295,000 lbs. This gives a horizontal increment of $\frac{295000}{93.55} = 3150$ lbs. per lineal inch and a required rivet pitch of $\frac{2 \times 7216}{3150} = 4.58$ inches. As the maximum allowed pitch is 6 inches (see specifications § 39) it will not be necessary to calculate the pitch at any other points. The pitch of the rivets in the cover plates must bear some relation to that of the rivets through the vertical legs of the flange angles so that they will not interfere.

Flange Splices. (42.) About the maximum length of angle $8''\times8''\times\frac{7}{8}''$ which can be obtained in one piece is 90 feet, therefore the flange angles will have to be spliced. We will splice one angle of each flange about 25 feet from each end of the girder so that both angles of one flange will not be cut at the same point.

At this point the flange angles are carrying the maximum allowed stress, and the total stress in one angle will be $10.61\times16{,}000=169{,}800$ lbs.

To take this stress we will use a splice angle on the inside of the angle spliced and a plate inside of the other angle. The splicing material required, then, will be $1L\ 8''\times8''\times\frac{11}{16}''$ cut down to $7''\times7''\times\frac{11}{16}''$ and ground to fit the fillet of the flange angle, and one plate $7''\times\frac{11}{16}''$. These will have an available net area of 10.53 sq. in. The length of the angles will have to be sufficient to take enough rivets to transmit 169,800 lbs., and one-third of this must be transmitted to the plate on the side opposite the angle cut. According to the specifications § 57, the rivets connecting this plate must be increased $66\frac{2}{3}\%$ over the number required by § 18 for the angle in contact with the cut member.

$$\text{Stress in one leg of splice angle}=\frac{169800}{3}=56{,}600 \text{ lbs.}$$

$$\text{Rivets required in angle on side next to splice}=\frac{56600}{7216}= 7.85$$

$$66\tfrac{2}{3}\%= 5.25$$

$$\text{Rivets required in angle on opposite side} = 13.1$$

The rivet pitch at the splice may be made 3 inches, which gives us a splice plate $6\frac{1}{2}$ ft. long on the side opposite the splice and an angle 4 ft. long on the side next to the splice.

Stiffeners. (39.) The stiffeners must be proportioned according to specifications §§ 16 and 79. The end shear which must be transmitted by the end stiffeners to the abutment is 377,500 lbs. To take this load we will need $\frac{377500}{10500}+50\%=54$ rivets. (See Spec. § 58.)

This number can be put into three pairs of stiffener angles with a single line of rivets in each angle. The stress, then, on

each pair of angles will be $\frac{377500}{3} = 125{,}800$ lbs. The outstanding legs of these end stiffeners must be as wide as the flange angles will allow, so we will try for these $2Ls\ 7'' \times 3\frac{1}{2}'' \times \frac{1}{2}''$.

The allowed unit stress is $16000 - 70\frac{48}{4.24} = 15200$ lbs. per sq. in., but 14,000 is the maximum, so the required area of one pair of angles $= \frac{125800}{14000} = 9.00$ sq. in.

We can, therefore, use for these stiffeners, $2Ls\ 7'' \times 3\frac{1}{2}'' \times \frac{1}{2}''$ whose area is 10.00 sq. in.

The minimum size of angles allowed for the *intermediate stiffeners* is $\frac{96}{30} + 2 = 5.2$ inches for the outstanding leg. (See Spec. § 79.) We will use for these $2Ls\ 6'' \times 3\frac{1}{2}'' \times \frac{3}{8}''$.

The spacing of the intermediate stiffeners must not exceed the distance d allowed by the formula in § 79 of the specifications, with a maximum of 6 ft.

$$\text{Required spacing at } A = \frac{\frac{1}{2}}{40}\left(12000 - \frac{377500}{48}\right) = 52 \text{ inches.}$$

$$\text{Required spacing at } B = \frac{1}{80}\left(12000 - \frac{265100}{48}\right) = 81 \text{ inches.}$$

$$\text{Required spacing at } C = \frac{1}{80}\left(12000 - \frac{168000}{48}\right) = 106 \text{ inches.}$$

$$\text{Required spacing at } D = \frac{1}{80}\left(12000 - \frac{87100}{48}\right) = 127 \text{ inches.}$$

Web Splices. The total length of the girder is 103 ft. Plates $96'' \times \frac{1}{2}''$ may be obtained 300 inches long (see "Cambria," page 28) or 25 ft. It will therefore be necessary to splice the web at at least four points, making it in five pieces. The arrangement of the lateral system will be more convenient if the web is spliced at five points, making a cross frame come at each splice. See Fig. 51.

The end sections may be made 18′ 2″ long and the intermediate sections each 16′ 8″. This will make the spacing of the cross frames uniform.

The maximum bending moment at the first splice B, is as follows:

Dead load = 686,000 ft. lbs.
Live load = 2,236,000 ft. lbs.
Impact = 1,677,000 ft. lbs.

Total = 4,599,000 ft. lbs.



FIG. 50.

The actual net flange area effective at this point is 40.73 sq. in., and therefore the bending moment taken by the web here is $\frac{6.00}{40.73} \times 4{,}599{,}000 = 677{,}500$ ft. lbs. At the splice this moment must be resisted by the splice plates FG, and the stress in these plates due to the moment will be $\frac{677500 \times 12}{68}$ = 119,600 lbs.

The maximum allowed unit stress on the extreme fiber of the girder is 16,000 lbs. per sq. in., and the maximum allowed unit stress on the splice plates FG will be proportional to their distances from the neutral axis of the girder, or,

$$\frac{34}{48.9} \times 16{,}000 = 11{,}125 \text{ lbs. per sq. in.}$$

and the required area in the splice plates will be $\frac{119600}{11125} = 10.75$ sq. in.

This will require 2 plates $12'' \times \frac{11}{16}''$,

(net area $= 16.5 - 4 \times 2 \times 1 \times \frac{11}{16} = 11.00$ sq. in.).

The allowed stress on the rivets must be reduced proportionally to their distance from the neutral axis as was done

with the fiber stresses, so the allowed stress on a rivet in these plates is,

$$\frac{34}{48.9}\times 10{,}500 = 7300 \text{ lbs.}$$

The number of rivets on each side of the splice in these plates will be $\frac{119600}{7300} = 17$.

The vertical splice plates to take the shear will require $\frac{265100}{10500} = 26$ rivets on each side. The design shown in Fig. 50 has 26 rivets on each side.

These figures are for the splice at B, but usually the same design is used for all the splices.

It will be noted that the maximum shear and maximum moment have been used here as occurring simultaneously. This is on the side of safety, but a rigid solution would not give a splice appreciably smaller.

A splice similar to the one shown in Fig. 40 may be used and calculated as follows. Here the number of rivets must first be assumed and then the maximum stress in them calculated, to see that it does not exceed the allowed units.

The splice, as drawn in Fig. 40, contains 40 rivets on each side, the vertical stress on each rivet, due to shear, is

$$\frac{265100}{40} = 6630 \text{ lbs.}$$

The bending moment to be resisted by these rivets is,

$$677{,}500\times 12 = 8{,}130{,}000$$

inch pounds. The amount of stress on each rivet due to bending moment will be in direct proportion to its distance from the neutral axis. (20.)

Calling the stress on the outermost rivet S, we have:

$$4S\times 38 + 4S\times\frac{34}{38}\times 34 + 4S\times\frac{30}{38}\times 30 + \ldots = 8{,}130{,}000,$$

or using the letter y to represent the distance from the neutral axis to the rivet, in each case, we have:[1]

$$\frac{4S}{38}\Sigma y^2 = M.$$

$$\text{In this case } \Sigma y^2 = 5320 \text{ and } S = \frac{8130000 \times 38}{4 \times 5320} = 14{,}050 \text{ lbs.}$$

The resultant maximum stress on the outer rivet is

$$\sqrt{6630^2 + 14{,}050^2} = 15{,}535 \text{ lbs.},$$

which is in excess of the allowed unit, (10,500), and therefore the number of rivets would have to be increased if this type of splice were used in this girder.

The splice plates must be strong enough, when considered as a beam $79\frac{1}{2}$ inches deep, to carry the web's proportion of the bending moment without exceeding a unit stress at the top and bottom, proportional to the distance from the neutral axis, or $\frac{40}{48.9} \times 16{,}000 = 13{,}090$ lbs. in this case. In figuring the moment of inertia of the plates, the rivet holes should be deducted.

Lateral Bracing.[2] To provide for wind stresses and vibrations (see Spec. § 10) a lateral system must be put in the span. Sometimes two systems are used, one in the plane of each flange, and sometimes only one is used, in the plane of the top flange, and the forces from the lower flange are transferred to the upper system by means of cross-frames (see Fig. 53) at intervals. Cross-frames are also put in to stiffen the bridge, when two systems of laterals are used. They are usually placed from 15 to 20 feet apart, depending upon the width of the flanges of the girders.

In a deck plate girder bridge, the lateral system is of the Warren, or sub-divided Warren type of truss with an even number of panels, so as to be symmetrical about the center line. The number of panels is so chosen that the laterals will be efficient, that is, so that they will not be inclined at too great

[1] Strictly, these forces are perpendicular to lines drawn from the center of gravity of the entire group of rivets, to each rivet.

[2] See Heller's "Stresses in Structures," Chapter XIV.

an angle with the direction of the wind. Also, the panels must be short enough so that the actual unit stress in the top flange of the girder will not exceed that allowed by the specifications § 30.

The actual unit stress in the top flange is $\frac{1037300}{74.98} = 13{,}830$ lbs. per sq. in. Equating this to the unit as given in § 30 and solving for l, we get $13{,}830 = 16{,}000 - 200\frac{l}{b} = 16{,}000 - 10l$ from which $10l = 2170$ and $l = 217$ inches $= 18'1''$. The unsupported length of the top flange must not exceed this amount.

We will divide the span into 12 panels, using a single system in the plane of the top flange, and put in cross frames at every second panel point. This will make a cross frame fall at each web splice. This is not necessary, but a *stiffener* must be at each cross frame.

As but one system of laterals is to be used, it must be proportioned to carry the entire lateral force.[1] From the specification § 10 the load is $200+200+10\%$ of $5000 = 900$ lbs. per lineal foot of girder, and all of this is to be considered as a moving load.

The stresses in the laterals will be alternately compression and tension, and will all reverse when the direction of the wind reverses. Laterals, however, are never designed for reversals of stress, (see Spec. § 22) so far as the reversal of the wind is concerned, because such reversals would occur only at long intervals.

Since it requires more material to take care of the compression than the tension in a lateral, we are concerned only with the compressive stresses, and choose that direction of the wind which, for any particular lateral, will give compression in it. It will be assumed that the load is all applied at the windward panel points, although the live load is really applied at both girders. This assumption is on the safe side, and simplifies the calculation of stresses.

On account of the cross frames, there are 12 panels on one side and six on the other. When the wind is blowing as indicated in Fig. 51, all of the panel loads will be equal and are

[1] For the calculation of the stresses in lateral systems of bridges having curved track see Heller's "Stresses in Structures," Art. 166, page 304.

$16.67 \times 900 = 15{,}000$ lbs. each. This direction of the wind will give maximum compressive stresses in BC, DE, and FG, and these will be as follows:

$$\text{Sec. } \theta = \frac{11.55}{8}$$

$$BC = 2\tfrac{1}{2} \times 15{,}000 \times \text{sec.}\theta = 54{,}100 \text{ lbs.}$$
$$DE = \tfrac{10}{6} \times 15{,}000 \times \text{sec.}\theta = 36{,}100 \text{ lbs.}$$
$$FG = \tfrac{6}{6} \times 15{,}000 \times \text{sec.}\theta = 21{,}600 \text{ lbs.}$$

When the wind blows in the other direction as shown in



FIG. 51.



FIG. 52.

Fig. 52, the compressive stresses will occur in AB, CD and EF. The panel loads on the lateral system for full loading are shown.

$$AB = 40{,}420 \times \text{sec.}\theta = 58{,}500 \text{ lbs.}$$
$$CD = 27{,}430 \times \text{sec.}\theta = 39{,}600 \text{ lbs.}$$
$$EF = 16{,}950 \times \text{sec.}\theta = 24{,}500 \text{ lbs.}$$

According to the specification § 25, the unit stress for laterals may be increased 25% over that given for other members, and according to § 74 the smallest angle allowed is $3\tfrac{1}{2}'' \times 3'' \times \tfrac{3}{8}''$. It is usual, where possible, to make laterals of single angles. The least radius of gyration of a single angle $3\tfrac{1}{2}'' \times 3'' \times \tfrac{3}{8}''$ is 0.62." The unsupported length may be taken as the length between edges of flange angles, and in this case will be about $11.55 - 1.95 = 9.6$ ft. $= 115$ inches.

Section 20 of the specifications limits the length of compression members of the lateral system to 120 times the least radius of gyration. This will make it impossible to use a member whose radius of gyration is less than $\frac{115}{120}=0.96$. The smallest lateral permissible then is one composed of a single angle $6''\times6''\times\frac{3}{8}''$. The allowed unit stress is,

$$\left(16000-70\,\frac{115}{1.19}\right)1.25=11{,}550 \text{ lbs. per sq. in.}$$

The maximum total stress which can be put upon this member is $11{,}550\times4.36=50{,}300$ lbs. This will answer for members *FG*, *EF*, *DE*, and *CD*.

Required area for $BC=\frac{54100}{11550}=4.69$ sq. in. Use for *BC* 1*L* $6''\times6''\times\frac{7}{16}''$. Actual area $=5.06$ sq. in.

Required area for $AB=\frac{58500}{11470}=5.10$ sq. in. Use for *AB* 1*L* $6''\times6''\times\frac{1}{2}''$. Actual area $=5.75$ sq. in.

The end cross frames must be proportioned to carry all the wind load to the abutment. It is usually considered that half of this goes through each diagonal to the supports, one diagonal being in tension and the other in compression.



FIG. 53.

The total force acting at the top of the cross frame at *A* (see Figs. 51 and 53) is 43,300 lbs. Stress in top strut $=21{,}700$ lbs.

Stress in diagonal $=21{,}700$ sec. $\theta=30{,}700$ lbs. The diagonal in compression is supported at the middle in one direction by the tension diagonal, so an angle having unequal legs will be more economical than an equal legged angle for the diagonals.

Try 1*L* 6″×3½″ ×⅜″. Allowed unit stress is

$$16000-70\frac{120}{1.94}+25\%=14{,}590 \text{ lbs. per sq. in.}$$

$$\text{Required area}=\frac{30700}{14590}=2.11 \text{ sq. in.} \quad \text{Actual area}=3.43 \text{ sq. in.}$$

As this is larger than necessary we will try 1*L* 5″×3″×⅜″. The allowed unit stress is 13,440 lbs. per sq. in.

$$\text{Required area}=\frac{30700}{13440}=2.29 \text{ sq. in.} \quad \text{Actual area}=2.86 \text{ sq. in.}$$

Use for diagonals 1*L* 5″×3″×⅜″.

For the top strut try 1*L* 3½″×3½″×⅜″. Allowed unit stress = 9000 lbs. per sq. in. Required area $=\frac{21700}{9000}=2.41$ sq. in. Actual area = 2.49 sq. in. This is large enough so *use for top and bottom struts* 1*L* 3½″×3½″×⅜″.

The amount of load transferred by the intermediate cross frames is only 3333 lbs., so the smallest angle allowed by the specifications will be sufficient. *Use for the intermediate cross frames* 3½″×3″×⅜″ angles.

The number of rivets in the end connections of the lateral members is determined by the single shear value of a rivet. The laterals will be field riveted, so the value of a rivet will be 6013 lbs.

AB requires $\frac{58500}{6013}=10$ rivets. *DE* requires $\frac{36100}{6013}=6$ rivets.

BC requires $\frac{54100}{6013}=9$ rivets. *EF* requires $\frac{24500}{6013}=5$ rivets.

CD requires $\frac{39600}{6013}=7$ rivets. *FG* requires $\frac{21600}{6013}=4$ rivets.

End cross frame diagonals require $\frac{30700}{7216}=5$ rivets. (Shop.)

End cross frame struts require $\frac{21700}{7216}=3$ rivets. (Shop.)

The intermediate cross frames will have to have all con-

nections made with 3 rivets each, to comply with the specifications § 74.

Shoes. The shoe should be of such design that it will distribute the end reaction evenly over the masonry. For short spans it is customary to simply rivet a plate, not less than $\frac{3}{4}$



FIG. 54.

inch thick, under the end of the girder, and allow this to rest on another similar plate resting on the masonry. With this form of shoe the load is applied heaviest at the inner edge of the masonry plate on account of the deflection of the girder. The best results are obtained, especially for long spans, by using hinged bolsters. (See Spec. § 63.)

The required bearing on the masonry (assuming sandstone)

FORM No. 1

THE OHIO STATE BRIDGE COMPANY

Sheet No. 1 Made by C.T.M. Date 11-10-13.

Estimate for W.P.Q.Ry. Bridge No. 217 Northern Division.

Span Extreme 103'-0"	Span C. to C. 100'-0"	Estimated DL per ft. Steel 1450	Total Steel 150880
Roadway Single Track	Panels at	Floor & Track 526	Steel per ft. 1509
Sidewalk None	Depth ~~C. to C.~~ 7 to 8 8'-0½"	Total 1976	Total Lumber
Capacity Trusses E50	Length of Diag.	Panel Load per Truss DL.	
Capacity Floor See Spec.	Width C. to C. 8'-0"	" " " " LL.	13.3L+177
Specifications Am. Ry. Assoc.	Sec. Tg.		



Ties 8"×12"×11'-0" 14" c. to c.
Guards 6"×8"

MEM	DL Stress	LL Stress	Impact	Total Stress	Unit Stress	Req. Area	MATERIAL	Actual Area	No. Pcs.	Wt. P. Ft.	Length	WEIGHT
2 Girders							⅛ Web	6.00				
		Moments					2 L's 8"×8"×⅞"	21.23	8	45.0	103.0	37080
	1235.0	4025.0	3018.8	8278.8		64.88	1-20"×¾" Top Full Bot. 78'	13.50	4	51.0	90.5	18460
							1-20"×¾"	13.50	4	51.0	64.0	13060
		End Shear					1-20"×⅝"	11.25	4	42.5	44.0	7480
	49.4	187.5	140.6	377.5			Net	65.48				
		Shear at 1st Splice										
Web	32.9	130.2	102.9	265.9			1-96"×½"		2	163.3	103.0	33620
			End Stiff.				6 L's 7"×3½"×½"		24	17.0	8.0	3260
	Shear at 2nd Splice		Fills				2 ⌶ 3½"×⅞"		24	10.4	6.7	1670
	16.5	83.3	68.2	168.0								
				Int. Stiff			21 L's 6"×3½"×⅜" (Crimp)		56	11.7	8.0	5250
	Shear at Center		"	"			21 L's " " " ——		20	11.7	8.0	1870
	0.0	46.9	40.2	87.1	Fills		1-3½"×⅝"		20	3.7	4.7	350
					"		1-3½"×7/16"		20	2.2	6.7	300
			Web Splice				2 ⌶ 13"×⅜"		20	16.6	4.7	1560
							2 ⌶ 12"×11/16"		40	28.0	2.6	2900
			Flange	"			1 L 8"×8"×11/16" (Cut to 7"×7")		8	35.8	4.0	1140
							1-7"×11/16"		8	16.4	6.5	850
									Rivets 4%			5160
								134.010				
2 End Frames												
			Top and Bot.				1 L 3½"×3½"×⅜"		4	8.5	73	250
			Diag.				1 L 5"×3½"×⅜"		4	10.4	10.0	420
			Conn. Pls.				20"×⅜"		8	25.5	2.0	410
									Rivets 4%			50
								1130				
									Forward ——			135130

FORM No. 2

THE OHIO STATE BRIDGE COMPANY

Sheet No. 2 Made by C.T.M. Date 11-10-13.

Estimate for W.P.Q.Ry. Bridge No 217 Northern Division

MEM	DL Stress	LL Stress	Impact	Total Stress	Unit Stress	Req. Area	MATERIAL	Actual Area	No. Pcs.	Wt. P. Ft.	Length	WEIGHT
								Brought Forward				13513 0
5 Intermediate Frames												
				Top & Bot.			1 L 3½" x 3" x ⅜"		10	7.8	7.3	570
					Diag.		1 L " " "		10	7.8	10.0	780
				Conn. Plates			1 – 18" x ⅜"		20	23.0	1.7	780
								Rivets 4% →				90
							2.220					
Laterals												
AB				58.5	11110	5.27	1 L 6" x 6" x ½"	5.75	2	19.6	10.5	410
BC				54.1	"	4.87	1 L 6" x 6" x 7/16"	5.06	2	17.2	10.5	360
CD				39.6	"	3.56	1 L 6" x 6" x ⅜"	4.36	2	14.9	10.5	310
DE				36.1	9300	3.89	1 L 5" x 5" x 7/16"	4.19	2	14.3	10.5	300
EF				24.5	"	2.64	1 L 5" x 5" x ⅜"	3.61	2	12.3	10.5	260
FG				21.6	6710	3.23	1 L 4" x 4" x 7/16"	3.31	2	11.3	10.5	240
					Conn Pls.		1 – 24" x ⅜"		2	30.6	2.5	150
							1 – "		6	"	4.5	830
							1 – 20" x ⅜"		6	25.5	4.0	610
							1 – 12" x ⅜"		7	15.3	1.5	160
								Rivets 4% →				150
							3.780					
4 Upper Shoes							1 – 20" x 15/16" (planed to ⅞")		4	63.8	3.0	770
							2 ⊑ 6" x 4" x ¾"		8	23.6	3.0	570
							2 ⊏ 6" x ½" (Ar)		8	10.2	2.5	200
							2 ⊏ 11" x ½" (")		8	18.7	1.8	270
							4 ⊑ 5" x 3" x ⅜"		16	9.8	0.9	140
								Rivets 4% →				80
							2.030					
4 Lower Shoes												
							1 – 33" x 1" (planed to ⅞")		4	112.2	3.0	1350
							4 ⊏ 12" x ⅝" (Ar)		16	25.5	2.5	1020
							2 ⊏ 17" x ½" (")		8	28.9	2.3	530
							2 ⊑ 6" x 6" x ¾"		8	28.7	3.0	690
							4 ⊑ 3" x 3" x ⅜" (T)		16	7.2	2.3	270
							4 ⊏ 12" x ⅜" (Ar)		16	15.3	0.7	170
					Guides		2 ⊏ 6" x ½"		8	10.2	3.0	240
					Mas. Pl.		1 – 33" x 1⅛" (planed to 1")		2	126.2	3.0	760
							2 ⊑ 4" x 4" x ⅜"		4	9.8	3.0	120
								Rivets 4% →				200
							5.350					
2 Roller Nests							5 Rounds 6"		10	96.1	1.8	1730
				Side Bars			2 ⊏ 4½ x ½"		4	7.65	3.0	90
				Stay Rods			2 0 1"		4	2.67	3.0	30
				Tap Bolts			1" (Eq)		20	1.0		20
							1.870					
				Miscellaneous			Track bolts &c.	500	1	5	103	500
								Total Steel →				150880



Lateral System

Diagonals in plane of Top Flange only.



End Cross Frames
Top & Bot.
1 L $3\frac{1}{2}$" x $3\frac{1}{2}$" x $\frac{3}{8}$" - 3 Riv.
Diag.
1 L 5" x $3\frac{1}{2}$" x $\frac{3}{8}$" - 5 Riv.

Int. Cross Frames
Top & Bot 1 L $3\frac{1}{2}$" x 3" x $\frac{3}{8}$" - 3 Riv.
Diag. 1 L $3\frac{1}{2}$" x 3" x $\frac{3}{8}$" - 3 Riv.

Masonry Sandstone
Reqd. bearing area 944 sq. in.
Rollers 6" Diam. 105 lin. in. reqd.
Base of Rail to Masonry
Fixed End 10'-$7\frac{3}{4}$"
Roller End 11'-$2\frac{3}{4}$"

Girders

Moment
DL = 1,235,000'#
LL = 4,025,000
Imp = 3,018,800
Total = 8,278,800'#

End Shear at A
DL = 49,400#
LL = 187,500
Imp = 140,600
Total = 377,500#

Shear at B
DL = 32,900#
LL = 130,200
Imp = 102,000
Total = 265,100#

Shear at C
DL = 16,500#
LL = 83,300#
Imp = 68,200
Total = 168,000#

Shear at D
DL = 0
LL = 46,900
Imp = 40,200
Total = 87,100

Flanges
2 Ls 8" x 8" x $\frac{7}{8}$" Full length
1 - 20" x $\frac{3}{4}$" Full length Top Flg.
1 - 20" x $\frac{3}{4}$" x 78 ft. Bot Flg.
1 - 20" x $\frac{3}{4}$" x 64 ft.
1 - 20" x $\frac{5}{8}$" x 44 ft.

Web Plate 96" x $\frac{1}{2}$"

End Stiffners
6 Ls 7" x $3\frac{1}{2}$" x $\frac{7}{16}$" with fillers.

Int. Stiffners
2 Ls 6" x $3\frac{1}{2}$" x $\frac{3}{8}$" Crimped

Approved Dec. 1, 1913.
John D. Jones Chief Engineer

Span 103'-0" Extreme (100' C. to C.)
Alignment Tangent
Grade Level
Loading Cooper's E 50
Dead Load = 1976 #p.l.f.
Specifications
Am. Ry. Eng. Assoc. 1910.
Ties 8" x 12" spaced 14" c. to C.
Guard Rails 6" x 8"

103 FT. DECK PLATE GIRDER
BRIDGE NO 217 NORTHERN DIV.
W. P. Q. RAILWAY.

FIG. 55.

is $\frac{377500}{400}=944$ sq. in. (See Spec. § 19.) Using a shoe 3 ft. long, it will require $\frac{944}{36}=26.2$ inches width.

The smallest rollers allowed are 6 inches in diameter (Spec. § 60 and 62) and it will require $\frac{377500}{3600}=105$ lineal inches of rollers under each bearing. (See Spec. § 19.) This will require five rollers each 21 inches long.

The pin must be large enough to properly transmit the shear, and the required area is $\frac{377500}{2\times12000}=15.7$ sq. in. This requires a pin $4\frac{1}{2}$ inches in diameter.

The shoe must be strong enough to distribute the end reaction, as a beam, from the pin, evenly over the masonry, and must also be strong enough laterally to transmit the wind forces to the abutments.

Fig. 54 shows a good design for the shoe.

The estimate of weight can now be made upon forms as described in Art. 6, and if the actual dead load taken from the estimate does not differ enough from the assumed dead load to cause a change in the size of any of the members, the stress sheet may be drawn, as shown in Fig. 55.

The difference in the actual dead load from that assumed is $1509-1450=59$ lbs. per lin. foot. This would increase the maximum moment $\frac{59\times100^2}{8\times2}=36{,}900$ ft. lbs., which would increase the required flange area at the center $\frac{36900\times12}{95.77\times16000}=0.29$ sq. in., making the total required area $64.83+0.29=65.12$ sq. in. The actual net area is 65.48 sq. in., so no change is necessary.

The stress sheet will now be drawn up. (See Fig. 55.)

45. Through Plate Girders. In a through plate girder bridge, all of the live and dead load, except the weight of the girders themselves, is concentrated at the panel points; and the weight of the girders may also be considered concentrated at the panel points to simplify the calculations.

The shears and moments are found, then, as for a truss bridge.[1]

[1] See Heller's "Stresses in Structures," Chapters XII and XIII.

The flange diagram (similar to Fig. 48) will be polygonal, the area required at each panel point being calculated.

The load on the masonry will equal the end shear of the girder plus the corresponding end reaction of the end floor beam (if an end beam is used).

There is no vertical load on the flange rivets, and the pitch of the rivets will be constant between panel points because the shear is constant.

There can be but one lateral system,[1] and this is made of the Pratt type with two diagonals in each panel. It is assumed that these diagonals take tensile stresses only; they are connected to the lower flanges of the stringers so as to take up the longitudinal force due to the application of the brakes on a moving train. This tractive stress would, otherwise, produce sidewise bending in the floor beams.

The top flanges of the girders are supported at the panel points by means of solid web brackets extending down to the top of the floor beams, and made as wide as the specified clearance will allow.

Sometimes through plate girder bridges have solid floors, in which case the moment and shear vary as for a deck plate girder.

In this case no lateral system would be necessary.

[1] See Heller's "Stresses in Structures," Art. 151, page 275.

CHAPTER V

PIN CONNECTED BRIDGES

46. Construction. In a truss bridge, the loads are delivered to the trusses at the panel points only. In the ordinary bridge this is done by means of floor beams and stringers. The stringers carry the ties and rails direct, and are in turn supported by the floor beams at the panel points of the truss. This construction causes the moment in the truss to vary uniformly between panel points and the shear to be uniform in each panel. (45.)

47. Types of Trusses. Pin connected trusses are nearly always of the Pratt or Baltimore type, because the pin connection is not well adapted to members whose stresses alternate in direction.

The tendency is toward long panels, that is, ordinarily from 20 ft. to 25 ft., because this gives few and heavy members both in the trusses and in the floor system, and these are cheaper to manufacture and give a stiffer structure under traffic. An odd number of panels is preferable to an even number, because the maximum moment will be less and because the structure may be made symmetrical about the center line with regard to field splices.

The panel lengths must be chosen so as to give an efficient lateral system without increasing the width of the bridge beyond that required for clearance of the roadway. For a single track bridge this width is usually about 16 ft., depending, of course, on the width of the truss members.

The economic depth[1] (38) cannot be determined with any degree of certainty, but is usually taken at from one-fifth to one-sixth of the length of span. The deeper the truss is made the stiffer it will be and the less the vibratory stresses will be.

[1] See "Stresses in Bridge and Roof Trusses," by W. H. Burr, Art. 76, page 353.

It is found that considerable variation in the depth will effect the weight and cost but little. In through bridges, the depth must be made sufficient to allow efficient overhead bracing without interfering with the clearances required by the traffic, unless a pony truss is used.[1]

Pin connected pony trusses are not desirable because of the lack of efficient transverse bracing.

48. Loads.[2] Most specifications give a series of wheel loads representing the weights of two locomotives, followed by a uniform train load which is to be used in designing the structures. In bridges over 100 ft. long, if an equivalent uniform load is used which will give the same center moment in the span, the errors in the stresses will not be large. It will be necessary to use several different equivalent loads for different parts of the structure, as, for instance, one for the stringers, one for the floor beams and hip verticals, and one for the trusses. The labor involved in obtaining these equivalent loadings for the floor beams and stringers is about as great as it is to calculate the stresses directly, so the wheel loads are generally used for these.

An equivalent uniform load is usually used for the trusses (except the hip verticals). The stresses in some of the members will be too large and in some too small. The variation will usually be less than about 4% from the stresses obtained by using the actual wheel loads specified.[3] Fig. 56 shows the equivalent uniform loads for Cooper's E40 loading. Curves similar to this may be found in Johnson's "Modern Framed Structures."

Even if the exact loading specified should ever come upon the bridge, the stresses calculated from the wheel loads would not be the true stresses, because the track distributes the wheel loads differently from what we assume, and the stringers are partially continuous while we assume them to be simply supported at each floor beam. Besides, the impact or vibratory stresses cannot be estimated with less than a probable error

[1] See Heller's "Stresses in Structures," Art. 113 and 151.

[2] See Heller's "Stresses in Structures," Art. 119, 130 and 131.

[3] See Trans. Am. Soc. C. E., Vol. 42, pp. 189, 215 and 206.

Also Johnson's "Modern Framed Structures," 9th Edition, Part I, Arts. 168 to 175.

Also DuBois' "Stresses in Framed Structures."

amounting to many times the discrepancy in the stresses obtained by the two methods.

Numerous other methods of obtaining "equivalent" loadings have been proposed, and it is probably due to the disagreement on this point that engine loads are still specified in all but a few specifications, and that some engineers still calculate all stresses from wheel loads.

The *dead load* must be estimated. The weight of the floor (44) including rails, ties and guards for the ordinary floor construction, with stringers not over 6 ft. 6 in. center to center, will not exceed about 400 lbs. per linear foot of track. The weight of the steel work may be estimated approximately by comparison with some previously made estimates of similar structures, or may be taken from an empirical formula (44). After the design and estimate are completed, the dead load must be revised to agree with the final estimated weight, if the discrepancy is sufficient to change the size of any of the members (43) (44).

49. Tension Members. The tension members of pin connected trusses, except the hip verticals, and in some cases the counters and end panels of the lower chord, are usually made of eye bars. The counters and end panels of lower chord are frequently required to be made rigid members, to increase the stiffness of the bridge. The hip verticals should always be rigid members, because this gives a better connection for the floor beams at these points, and because it greatly reduces the vibration.

Eye bars are forged, and the heads are made of such size that in testing, the bar will break in the body instead of through the head. Usually the net section through the pin hole is made about 25% in excess of the section through the body of the bar.[1]

Eye bars should not be thinner than about $\frac{3}{4}$ inch, and should not be too thick, say over about $2\frac{1}{4}$ inches. Thick bars will usually not show as high an ultimate strength as thin ones. The usual proportions of width to thickness lie between 3 to 1 and 7 to 1.

Built tension members, of course, contain more material than tension members of the same strength made of eye bars.

[1] Sizes of eye bars as manufactured by that company are given in "Cambria," page 317.


EQUIVALENT UNIFORM LOADS FOR COOPER'S E40 LOADING
The curves give the equivalent uniform load for maximum moment at points indicated
The curve for equivalent uniform load for maximum moment in the girder very nearly coincides with the curve given for the 5/10 Point
For spans over 294 ft. the equivalent uniform load for the 5/10 Point (Center moment) is given by the equation
$w_{5/10} = 2000 + \frac{15200000}{L^2}$
For spans over 363 ft. the equation for the 4/10 Point curve is:
$w_{4/10} = 2000 + \frac{19000000}{L^2}$
For spans over 480 ft. the equation for the 3/10 Point curve is:
$w_{3/10} = 2000 + \frac{532000000}{21L^2}$
For spans over 101 ft. the equation for the equivalent uniform load for end shear is:
$w_s = 2000 + \frac{144000}{L} - \frac{4398000}{L^2}$
EQUIVALENT UNIFORM LOAD IN POUNDS PER FOOT (ONE RAIL)
LENGTH OF SPAN IN FEET
End Shear
1/10
2/10
3/10
4/10
5/10 Point
4/10 Point
3/10 Point
2/10 Point
1/10 Point

FIG. 56.

The net section through rivet holes (19) and through the pin holes must be carefully investigated. The most common form is an *H* cross section made of four angles latticed together, although two channels latticed are frequently used. Sometimes two eye bars are laced together with bent bars, but this does not give a member much stiffer than the plain eye bar member.

The required net area of a tension member is obtained by simply dividing the stress in the member by the allowed unit stress in tension as given by the specifications.

50. Compression Members. The intermediate posts are usually made of two channels, either built or rolled, latticed together. Built channels are of course more expensive than rolled channels, on account of the extra punching and riveting.

If the toes of the channels are turned in, the backs form plane surfaces to which connections may be more easily made than if the toes are turned out. The distance in the clear between the channels must be great enough to allow the entrance of the riveting tool between the lacing bars, and it is economical to place the channels far enough apart to make the ratio of the unsupported length to the radius of gyration in the two directions equal.[1] Local conditions frequently limit the dimensions of these members.

Experiments show that a column will fail at an average unit stress over the entire cross section, which is less than the ultimate strength of the material in compression, and that the longer the column the less will be this average unit stress at failure. In other words, a column does not fail by compression alone but by a combination of compression and bending.[2]

This is taken into account in the design of compression members by the use of a "*column formula*," which gives us an average unit stress which it is safe to allow on the cross section and after this unit is determined the design of the compression member is as simple as that of a tension member, but the determination of the average unit stress allowable, involves properties of the cross section of the member, so the solution must be by trial.

Most column formulas take into account the slenderness of

[1] See "Cambria," page 195.

[2] For an excellent article on Columns see editorial in Engineering News, January 3, 1907.

the column by using the ratio L/r, in which L is the unsupported length and r is the least radius of gyration.[1] This ratio is applied to the maximum allowed fiber stress in compression as a variable reduction factor.

The column theory[2] assumes that the whole member acts as one piece. When the member is composed of two or more parts connected by stay plates and lacing, it is the function of these to hold the component parts of the member in line and to insure its action as a unit.

Previous to the collapse of the Quebec Bridge in 1907, very few designers attempted the calculation of stresses in lace bars, or their rational design. They were put in by empirical rule and roughly proportioned to the size of the member according to the judgment of the designer.[3] The failure of the Quebec Bridge was due directly to the weakness of the latticing of the lower chord compression members, and since that time much has been written on the subject and now most specifications require the calculation of the stresses in the lace bars.[4]



FIG. 57.

A column under stress will deform into a curve with a point of contra-flexure near each end,[5] the distance from the end depending upon the degree of fixity of the end. At these points of contra-flexure the bending moment is zero, and consequently the stress on the column cross section is uniform. Midway between these points the maximum bending moment occurs, and the maximum unit stress in compression occurs on the concave side, therefore in a distance equal to one half the length between the points of contra-flexure, the unit stress in the concave side of the column must change from the average to the maximum allowed.

[1] See article by the author on "Fixed End Columns in Practice," in Engineering News, Nov. 2, 1911, Vol. 66, page 530.

[2] See Heller's "Stresses in Structures," Chapter X.

[3] See Cooper's "General Specifications for Steel Railway Bridges and Viaducts," 1906, Section 97.

[4] See Report of the Royal Commission on the Failure of the Quebec Bridge, Appendix No. 16, and also the attached Report by Mr. C. C. Schneider.

See also "General Specifications for Steel Railway Bridges," 1910, of the American Railway Engineering Association, Secs. 47 to 50.

[5] See Heller's "Stresses in Structures," Fig. 137, page 178.

Suppose a column to be made up of two leaves connected by lacing or otherwise.

Let s_1 = maximum allowed unit stress on the material in compression.

s_c = average unit stress over the cross section $= \frac{P}{A}$.

F = total change in stress in one leaf of the column in a distance l.

f = change in the total stress in one leaf per unit of length $= \frac{F}{l}$.

l = the least distance from the point of maximum bending moment to a point of contra-flexure.

L = total length of column.

A_1 = area of cross-section of one leaf.

$$F = A_1(s_1 - s_c), \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (16)$$

$$f = \frac{A_1(s_1 - s_c)}{l}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (17)$$

For a pivoted ended column $L = 2l$ and for a square or fixed ended column $L = 4l$. Any column in practice will lie somewhere between these two limits, and in any case eccentricities of manufacture and loading may make l different than theory would indicate. Also this theory assumes that the rate of change of stress in the leaf is uniform, which is not true, therefore, to be on the safe side we will take $L = 4l$ in all cases; then

$$f = \frac{4A_1(s_1 - s_c)}{L}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (18)$$

Equation (18) gives the longitudinal increment of stress in one leaf per unit of length of column, and sufficient connection must be provided between the leaves to transmit this stress (41). The values of s_1 and s_c are taken from the column formula which is being used unless there is bending due to transverse loads (70).

Professors Talbot and Moore, in a paper presented before the American Society of Civil Engineers, (Trans. Vol. LXV,

page 202) give an extended account of experiments made at the Engineering Experiment Station of the University of Illinois upon steel, built-up, compression members. Concerning the stresses in lace bars they say, "The measurements indicate stresses in the lattice bars which would be produced by a transverse shear equal in amount to 1 to 3% of the applied compression load, or to that produced by a concentrated transverse load at the middle of the column length equal to 2 to 6% of the compression load."

The theoretical bending moment which is taken into account by the column formula may be obtained by setting

$$s_1 - s_c = \frac{Mv}{I} = \frac{Mv}{Ar^2} \quad \text{and} \quad M = \frac{(s_1 - s_c)Ar^2}{v} = P\frac{L}{4},$$

from which P, the equivalent transverse load at the middle of the column length may be found. The lacing may be proportioned for the shear due to this load.

When lacing is used the bars must be capable of taking their stress either in tension or compression.

The top chords and end posts are usually made of two built or rolled channels, connected by a cover plate on top and by stay plates and lacing on the bottom. The cover plate being solid aids in taking compression, and its area is always considered in the effective cross section. The cover plate then serves both as a part of the compression area and to tie the two leaves of the column together.

A compression member with a cover plate on one side only is not symmetrical about its center of gravity, and the end connections must be designed to transmit the stresses to the cross section properly (18).

The cover plates should always be made as thin as the specifications will allow unless they have some special duty to perform, so as to keep the eccentricity of the section small. The unsupported width of plates in compression (distance between rivet heads) is usually limited by the specifications to 30 or 40 times the thickness of the metal.

If a compression member is subjected to transverse loads, causing bending [1] in addition to the direct load (29), the maxi-

[1] See Heller's "Stresses in Structures," Art. 111, page 190.

mum fiber stress due to both *must* not exceed the maximum allowed unit compressive stress (s_1), and to be on the side of safety *should* not exceed a unit stress determined by a suitable column formula (s_c), because the accidental eccentricities *may increase* the bending due to the transverse loading.

Horizontal and inclined compression members are in bending due to their own weight in addition to being in compression. In the top chords and end posts of bridges this bending moment is partially neutralized by lowering the centers of the end connections an amount sufficient to produce an upward bending moment due to the eccentricity of the compressive stress, equal to the downward bending moment due to weight.

$$Pe=\frac{wL^2}{8} \quad \text{and} \quad e=\frac{wL^2}{8P}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (19)$$

Equation (19) is generally used in practice to determine the eccentricity of the pins to compensate for the bending due to the weight of the member. Using this value of e would render the bending moment almost zero at the middle, but as the bending moment (Pe) due to the eccentricity is a constant, while the moment due to the weight is a maximum at the middle and zero at the ends, the use of this value of e produces a negative bending moment at the end as great as the original moment due to the weight.[1] It is better to use a smaller value of e as given by equation (20),

$$e=\frac{wL^2}{10P}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (20)$$

as this will give a less resultant maximum bending moment in the column.

Another case in which compression members are subjected to both axial and bending stresses is the end posts of a through bridge with overhead bracing. The end posts must carry the wind load in bending from the portal to the abutments.[2] This bending is in a plane perpendicular to that of the bending due to weight. The lacing and riveting of the cover plates of the

[1] See Article by Prof. J. E. Boyd in Engineering News for April 11, 1907, Vol. LVII, page 404.

[2] See Heller's "Stresses in Structures," Arts. 153 to 165 inclusive.

end posts must be sufficient to transfer the increments of stress as determined by equation (17).

51. Lateral Systems.[1] In a through bridge a lateral system is always provided in the plane of the lower chord and, if the head room permits, in the plane of the upper chord also. In a deck truss bridge, lateral systems should always be provided in the plane of both the top and bottom chords.

Transverse sway bracing is always provided at each panel point. In pony trusses this consists of knee braces to the floor beams which transmit each panel load of wind from the top chord to the bottom lateral system. In truss bridges with two lateral systems (top and bottom) the transverse sway frames will transmit part of the load from the other lateral system to the one in line with the supports, due to the deflection of the end sway bracing. Thus in a through bridge, part of the top lateral load will be transmitted at each panel point to the bottom lateral system by the intermediate sway bracing. The amount of load thus transferred depends upon the relative stiffness of the various members concerned and on the stiffness of the portal bracing. It will usually be safe to assume that half of each top chord panel load is transmitted by the sway bracing to the bottom lateral system at that point. In double track bridges and in bridges on curves the transverse bracing is proportioned to carry part of the load from one truss to the other in order to equalize the deflections of the trusses under eccentric loadings.[2]

The lateral system is a horizontal Pratt truss in which the floor beams act as the posts and the chords of the main trusses act as chords. The diagonal members are put in in both directions to provide for a reversal of wind.

The top lateral system in a through bridge and the bottom lateral system in a deck bridge take the wind load on half the projection of the trusses.

The end reaction of the top lateral system in a through bridge is conveyed to the abutment by means of *portal bracing*

[1] See Heller's "Stresses in Structures," Chapter XIV.

[2] See Johnson's "Modern Framed Structures," 9th Edition, Part I, Art. 191.

See Cooper's "Specifications," Sections 109 and 110.

See "Framed Structures and Girders," by Edgar Marburg, Arts. 246 and 247.

between the end posts and by bending in these end posts.[1] (50.) Provision must be made in all main truss members carrying wind stresses for these, in addition to the dead and live load stresses.

The wind blowing upon the side of a train on a bridge tends to overturn it, and thus produces a greater load on the leeward truss than on the windward. The effect on the top chord of a through bridge is very small because the leeward top chord would be in tension under the wind load alone, and in compression due to the overturning moment. The bottom chords and web members should, however, be proportioned for this additional stress. (56.)

52. Design of a Pin-connected Railway Bridge. To illustrate the methods of solving the various problems connected with the design of truss bridges, the design for a through Pratt truss railway bridge will now be worked out.

We will assume the following data:

Span 189 ft. c. to c. of end pins = 7 panels at 27 ft.
Single track. Alignment tangent.
Specifications Cooper's 1906 for Railway Bridges.
Loading Cooper's E40.
Material medium steel except rivets.

53. Dead Load. (48) The stringers will be spaced 6 ft. 6 in. c. to c., and the size of the tie may be calculated as was done in Art. 43. We will use $8'' \times 8''$ ties 10 ft. long spaced 14 in. c. to c., guard rails $6'' \times 8''$. The weight of the floor comes out somewhat less than 400 lbs. per lin. ft., but the specification § 23 directs that not less than 400 lbs. per linear ft. shall be used (43).

The weight of the steel work may be approximately estimated from equation (15), $w = 7L + 600$ from which $w = 1923$ lbs. per lin. ft. of bridge. The total dead load then will be $1923 + 400 = 2323$ lbs. per lin. ft. of bridge, one-third of which will be considered as acting at the top chord and two thirds at the bottom chord.

54. The Depth of the trusses (47) must be sufficient to allow the required head room and also an efficient portal. The depth of the floor system will govern this to some extent also.

[1] See Heller's "Stresses in Structures," Arts. 153 to 165 inclusive.

An estimate of the depths required for these various parts may be made and an approximate minimum allowed depth calculated in the form of a table.

The stringer should be designed before this table is made up, as the depth of the truss does not affect it. We will use the stringer as designed in Art. 43, for this bridge.



FIG. 58.

Depth of tie over stringer	0′ 7½″	(Spec. § 12)
Depth of stringer	4′ 3¼″	
Bot. of stringer to bot. of fl. bm	0′ 6½″	
	5′ 5¼″	
Bot. of fl. bm. to pin cent	10¼″	
Base of rail to pin cent	4′ 7″	
Required clearance	21′ 0″	(Spec. § 4)
Portal depth say	4′ 5″	(min.)
Total depth c to c. of pins	30′ 0″	(min.)

The depth should be about $\frac{1}{5}$ to $\frac{1}{6}$ the span (47), so we will use a depth of 32′ 0″ c. to c. of pins.

55. Stresses.[1] For all of the truss members except the hip verticals, an equivalent uniform live load will be used, derived



FIG. 59.

Mem.	Dead Load Stresses	Live Load Stresses: Equiv. Uniform	Live Load Stresses: Wheel Loads	Wind Stresses: From Lat. Sys.	Wind Stresses: From Overturning	Wind Stresses: Total Max.	Remarks
aB	+123100	+255400	+264500		∓ 31300	+ 31300	See Portal
Bc	- 82100	-182400	-190000		± 22400	- 22400	Neglect Wind
Cd	- 41000	-121600	-126700		± 14900	- 14900	" "
Dd′	- 0	- 73000	- 74000		± 9000	- 9000	" "
D′c′	+ 41000	- 36500	- 34500		± 4500	- 4500	" "
C′b′	+ 82100	- 12100	- 9600		± 1500	- 1500	No Member
Bb	- 20900	-	- 80100		± 8000	- 8000	Neglect Wind
Cc	+ 41800	+ 93000	+ 96900		∓ 11400	+ 11400	" "
Dd	+ 10500	+ 55800	+ 56600		∓ 6900	+ 6900	" "
ab	- 79400	-164700	-170600	+81600 −0	± 20200	∓ 101800 − 20200	" "
bc	- 79400	-164700	-170600	+136000 −81600	± 20200	+ 156200 −101800	Wind exceeds 30%
cd	-132300	-274500	-274500	+163200 −136000	± 33700	-169700	" " "
dd	-158800	-329500	-330100	± 163200	± 40400	-203600	" " "
BC	+132300	+274500	+274500	∓ 18100 − 0	∓ 33700	+ 33700	Neglect Wind
CD	+158800	+329500	+330100	∓ 27200 − 18100	∓ 40400	+ 27200	" "
DD	+158800	+329500	+330100	± 27200	∓ 40400	+ 27200	" "

from the maximum live load moment for the span (48). This equivalent uniform load for a 189 ft. span is 4820 lbs. per lin. ft. of track. See Fig. 56.

$$\text{Panel load of dead load} = \frac{2323 \times 27}{2} = 31{,}360 \text{ lbs.}$$

$$\text{Panel load of live load} = \frac{4820 \times 27}{2} = 65{,}070 \text{ lbs.}$$

The table under Fig. 59 gives the direct stresses in all of the truss members due to dead load, live load, and wind. The live load stresses calculated from the wheel loads are also given in a parallel column for comparison. The maximum error is seen to be in the end posts and amounts to about $3\frac{1}{2}\%$.

[1] See Johnson's "Modern Framed Structures," Arts. 168 to 175.

The wind stresses in the chords from the lateral systems are gotten by assuming that the trusses are 16′ 0″ c. to c. This will not be far from right.

According to specifications, § 24, 450 lbs. of the wind load shall be treated as acting on a moving train at a height of 6 feet above the base of rail. This gives a height of $6.0+4.58=10.58$ feet above the pin centers. The horizontal force acting at this height (see Fig. 60) will be $450\times27=12{,}100$ lbs. per panel.



FIG. 60.

The additional load on the leeward truss at each panel due to this overturning moment will be

$$V=\frac{12100\times10.58}{16}=8000 \text{ lbs.}$$

The additional stress in each member then will be the direct live load stress in the member, (figured for the equivalent uniform load) multiplied by $\frac{8000}{65070}$.

The specifications § 39 direct that the stresses in the truss members due to wind may be neglected unless they exceed 30%

of the combined dead and live load stresses. Therefore we will have to consider the wind stresses only in the bottom chords. The bending in the end posts due to the portal stresses will be taken up in Art. 58.

56. Design of Tension Members. The required net area for any tension member is obtained by adding algebraically, the areas required for dead load and live load stresses. (Spec. §§ 31 and 35.) There is also a limiting clause for counters. (Spec. §§ 50 and 51.)

Since in these specifications, the dead load unit stress is just twice the live load unit, the same area will be obtained if the live load stress plus *half* the dead load stress be divided by the live load unit stress.

From this relation we may derive an average unit stress which may be applied to the total dead plus live load stress in any member as follows:

Let s_W = this average unit stress.
s_D = the dead load unit stress.
s_L = the live load unit stress.
D = the dead load stress in the member.
L = the live load stress in the member.

$$\frac{\frac{1}{2}D+L}{s_L}=\frac{D+L}{s_W},$$

$$s_W=\frac{2(D+L)s_L}{D+2L}=\frac{2s_L}{1+\frac{L}{D+L}},$$

$$s_D=2s_L \qquad s_W=\frac{s_D}{1+\frac{L}{D+L}}. \quad . \quad . \quad . \quad . \quad . \quad (21)$$

It is not necessary to find this average unit stress except for those members in which the wind stress must be taken into account according to specifications § 39.

The simplest members, those made up of eye bars, will be proportioned first. We will assume that we are limited in the choice of eye bars to those manufactured by the Cambria Company, as indicated in their hand book, pages 316 and 317.

Bc Required D.L. area $= \frac{82100}{20000} = 4.11$ sq. in.

Required L.L. area $= \frac{182400}{10000} = 18.24$ sq. in.

Total $= 22.35$ sq. in.

This may be made up of 4 bars $6'' \times \frac{15}{16}''$ (area $= 22.50$ sq. in.) or 2 bars $7'' \times 1\frac{5}{8}''$ (area $= 22.76$ sq. in.). The 6 inch bars are slightly more economical and will not require such large heads so we will use 4 bars $6'' \times \frac{15}{16}''$ for *Bc*.

Cd Required D.L. area $= \frac{41000}{20000} = 2.05$ sq. in.

Required L.L. area $= \frac{121600}{10000} = 12.16$ sq. in.

Total $= 14.21$ sq. in.

This will require 2 bars $6'' \times 1\frac{3}{16}''$ (area $= 14.25$ sq. in.)

Dd' Required D.L. area $= 00$

Required L.L. area $= \frac{73000}{10000} = 7.3$ sq. in.

This will require 2 bars $4'' \times \frac{15}{16}''$ (area $= 7.50$ sq. in.) or 2 bars $3'' \times 1\frac{1}{4}''$ (area $= 7.50$ sq. in.). The 3 inch bars cannot be used because, probably the size of the pin at *d* will exceed 5 in., which is the largest size that the table in " Cambria " gives for a 3 inch bar, so we will use 2 bars $4'' \times \frac{15}{16}''$.

An increase in live load of 25% or to E50, will increase the unit stress in this counter exactly 25% so § 51 of the specifications is satisfied.

D'c' Required D.L. area $= \frac{41000}{20000} = 2.05$ sq. in.

Required L.L. area $= \frac{36500}{10000} = 3.65$ sq. in.

Difference $= 1.60$ sq. in.

To comply with specifications § 51 an increase in live load of 25% must not increase the unit stresses more than 25%, therefore:

$$\text{Required D.L. area} = \frac{41000}{20000+25\%} = 1.64 \text{ sq. in.}$$

$$\text{Required L.L. area} = \frac{36500+25\%}{10000+25\%} = 3.65 \text{ sq. in.}$$

$$\text{Difference} = 2.01 \text{ sq. in.}$$

This will require 1 bar $1\frac{7}{16}$ in. square (area = 2.07 sq. in.).

cd. The average unit stress allowable, as determined by equation (21) must be used here because the wind stress is more than 30% of the dead and live load stresses. (Spec. § 39.)

$$s_w = \frac{20000}{1+\frac{274.5}{406.8}} = 11{,}940 \text{ lbs. per sq. in.}$$

$$11{,}940+30\% = 15{,}520 \text{ lbs. per sq. in.}$$

$$\text{Total stress in } cd = 132.3+274.5+169.7 = 576.5.$$

$$\text{Required area} = \frac{576500}{15520} = 37.14 \text{ sq. in.}$$

This will require 4 bars $6''\times 1\frac{9}{16}''$ (area = 37.50 sq. in.) or 2 bars $7''\times 1\frac{5}{16}''$ plus 2 bars $7''\times 1\frac{3}{8}''$ (area = 37.64 sq. in.).

The 7 inch bars will be better because the thickness is less, and this will give a less bending moment on the pin, and also probably the next chord *dd'* will necessarily be made of 7 inch bars, in which case the same dies may be used for making all of the eye bar heads in the bottom chords, which would reduce the cost.

dd' Total stress $= 158.8+329.5+203.6 = 691.9.$

Allowed unit stress = 15,520 lbs. per sq. in.

$$\text{Required area} = \frac{691900}{15520} = 44.58 \text{ sq. in.}$$

This will require 2 bars $7''\times 1\frac{5}{8}''$ plus 2 bars $7''\times 1\frac{9}{16}''$ (area = 44.64 sq. in.).

According to the specifications § 10 the vertical suspenders and the two end panels of lower chord must be made rigid members.

abc Total stress $=79.4+164.7+101.8=345.9$

Allowed unit stress $=15{,}520$ lbs. per sq. in.

$$\text{Required area}=\frac{345900}{15520}=22.29 \text{ sq. in.}$$

This member may be made up of 4 angles and 2 plates laced together horizontally as shown in Fig. 61. We will use 4 angles $6''\times3\frac{1}{2}''\times\frac{1}{2}''$, and 2 plates 14 inches wide by as thick as may be necessary to make up the required net area. To comply with specifications § 64 at least two rivet holes must be deducted from each angle (19).



FIG. 61.

Net area 4 angles $6''\times3\frac{1}{2}''\times\frac{1}{2}''=18.00-8\times1\times\frac{1}{2}=14.00$ sq. in.

Required net area of plates $=22.29-14.00=8.29$ sq. in.

Equivalent net width of plates $=14-2\times1=12$ inches.

$$\text{Required thickness of plates}=\frac{8.29}{12}=0.69 \text{ inch.}$$

Use 2 plates $14''\times\frac{3}{8}''$. Total actual net area

4 angles $6''\times3\frac{1}{2}''\times\frac{1}{2}''=14.00$ sq. in. net

2 plates $14''\times\frac{3}{8}''=9.00$ sq. in. net

Total $=23.00$ sq. in. net

It would be more economical to use four angles without cover plates, but it is not well to use metal thicker than about $\frac{5}{8}$ inch in a riveted tension member, besides, according to specifications § 129, material over $\frac{5}{8}$ inch in thickness in tension members must be reamed, which would increase the cost considerably.

Bb will be made of two rolled channels, and will be made the same width as the intermediate posts *Cc* and *Dd* so that the floor beams may all be made alike.

The allowed unit stresses are less for verticals carrying floor beams than for other truss members (Spec. § 31).

$$\text{Required D.L. area}=\frac{20900}{16000}=1.31 \text{ sq. in.}$$

$$\text{Required L.L. area}=\frac{80100}{8000}=10.01 \text{ sq. in.}$$

Total $=11.32$ sq. in.

There will be pin plates on the webs of the channels for the connection at B, and stay plates riveted to the flanges near them. These will make it necessary to take at least 4 holes out of each channel as shown in Fig. 62.

FIG. 62.

The member cannot be made of less than 10-inch channels or there would not be room for the floor beam connection. The lightest weight 10 inch channel cannot be used because specifications § 82 requires that no metal less than $\frac{3}{8}$ inch thick be used, and the web of a 10″ by 15 lb. channel is only 0.24″ thick. $2-10''\times 20$ lb. channels is about the smallest section that can be used.

The rivets in the flanges cannot be larger than $\frac{3}{4}''$, (see "Cambria," page 46), while it is desirable to have the rivets in the web $\frac{7}{8}''$ for the floor beam connections.

The net area then of the 2 channels $10''\times 20$ lb.

$$=11.76-4\times\tfrac{7}{16}\times\tfrac{7}{8}-4\times 0.38\times 1=8.71 \text{ sq. in.}$$

As this is less than the required area we must use heavier channels. Try 2 channels $12''\times 25$ lbs.

$$\text{Net area}=14.70-4\times\tfrac{1}{2}\times\tfrac{7}{8}-4\times 0.39\times 1=11.39 \text{ sq. in.}$$

These will answer.

57. Design of Compression Members. The least allowable section for a post is 2 channels $10''\times 20$ lbs. (see Spec. §§ 35 and 82.) The greatest allowed length for a post composed of these channels is 100 times the radius of gyration (Spec. § 35)

$$=100\times 3.66=366 \text{ inches}=30'\ 6'',$$

which is less than the depth of our truss, so a larger section must be used. Try 2 channels $12''\times 25$ lbs.

$$\text{Allowed length}=100\times 4.43=443''=36'\ 11.''$$

$$\text{Allowed unit stress for D.L.}=17000-90\frac{L}{r}$$

$$=17000-\frac{90\times 32\times 12}{4.43}=9200 \text{ lbs. per sq. in.}$$

Allowed unit stress for L.L. = 4600 lbs. per sq. in.

Dd Required D.L. area $= \frac{10500}{9200} =$ 1.14 sq. in.

Required L.L. area $= \frac{55800}{4600} =$ 12.13 sq. in.

Total = 13.27 sq. in.

Actual area = $2 \times 7.35 = 14.70$ sq. in., which is sufficient.

Cc. The stress for this post is considerably greater than for *Dd*, so we will try 2 channels 15″×33 lbs.

Allowed D. L. unit stress = 10,850 lbs. per sq. in.

Allowed L.L. unit stress = 5,425 lbs. per sq. in.

Required D.L. area $= \frac{41800}{10850} =$ 3.86 sq. in.

Required L.L. area $= \frac{93000}{5425} =$ 17.16 sq. in.

Total = 21.02 sq. in.

Actual area 2 channels 15″×33 lbs. = $2 \times 9.90 = 19.80$ sq. in.
Try 2 channels 15″×40 lbs.

Allowed D.L. unit stress = 10,650 lbs. per sq. in.

Allowed L.L. unit stress = 5,320 lbs. per sq. in.

Required D.L. area $= \frac{41800}{10650} =$ 3.93 sq. in.

Required L.L. area $= \frac{93000}{5320} =$ 17.48 sq. in.

Total = 21.41 sq. in.

Actual area 2 channels 15″×40 lbs. = $2 \times 11.76 = 23.52$ sq. in., which is sufficient.

In the above calculations for the posts we have assumed that the ratio of unsupported length to radius of gyration in the direction parallel to the webs of the channels was greater than that in the other direction (50). In order to make the posts safe according to the specifications, the distance between channels must be sufficient so that the allowed unit stress is greater than the actual.

The actual unit stress on $Cc = \frac{134800}{23.52} = 5730$ lbs. per sq. in. From equation (21) the allowed unit stress

$$= \left[17000 - 90\frac{L}{r}\right]\left(\frac{1}{1+\frac{93}{134.8}}\right) = 10060 - 53.25\frac{L}{r}.$$

Equating these two units we get

$$5730 = 10060 - 53.25\frac{21\times 12}{r}, \text{ from which } r = 3.1 \text{ in.}$$

This is asuming that the post is supported by sway bracing at an elevation of 21 ft. above the floor beam. (Spec. § 107.)

The distance apart of the channels necessary to make the radius of gyration equal to 3.1 in. will now be calculated.

$$r = \sqrt{\frac{I}{A}}, \quad I = I_o + Ad^2,$$

in which

I_o = moment of inertia of channels about their own center of gravity.

d = distance from the center of gravity of the column to the center of gravity of the channel.

$$r = \sqrt{\frac{2\times 9.39 + 2\times 11.76\times d^2}{2\times 11.76}} = 3.1,$$

from which

$$d^2 = 8.81, \qquad d = 2.97 \text{ inches.}$$

The minimum distance back to back of channels (toes turned in) then will be $2\times 2.97 + 2\times 0.78 = 7.5$ inches, but Spec. § 35 says that the least width of post permissible is 10 inches, so we will use this width.

The post *Dd* and the hip vertical *Bb* will be made the same distance back to back in order that the floor beams may be made alike.

The width of the *top chord and end posts* must be made the same throughout, and the depth of the two is usually made the same, although this is not absolutely necessary.

The width must be sufficient to allow all of the web members to connect to the pins inside of the top chord section. In some cases a pair of eye bars are allowed to connect to the pin outside the chord section, but this is unusual.

There are more members connecting at B than at any other point, so the required width there will be determined.

We can only estimate this width approximately at present.

Width of Bb back to back of channels	$= 10''$
Pin plates on Bb say $2-\frac{1}{2}''$	$= 1''$
Bars Bc $2-\frac{15}{16}''$ (2 outside chord)	$= 1\frac{7}{8}''$
Webs of end posts say $2-\frac{3}{4}''$	$= 1\frac{1}{2}''$
Pin plates on end posts say $2-\frac{1}{2}''$	$= 1''$
Top angles on end posts say $2-3''$	$= 6''$
Clearances say	$1\frac{1}{8}''$
Total	$= 22\frac{1}{2}''$

In order to make sure that we have sufficient clearance we will make the cover plate of the chord 24 inches wide.

The depth of the chord section must be made sufficient so that there is room between the pin and the cover plate for the connection of the members. The pin will be somewhat above the geometric center of the web plates because the center of gravity of the section will be above the center of the web.



Fig. 63.

Assuming this eccentricity of the pin to be $1\frac{1}{2}''$ and that the radius of the largest eye bar head is not over $7\frac{1}{2}''$, we have $9''$ as the half depth of the web required by the clearances.

Fig. 63 shows about the dimensions of the minimum chord section which we can use here.

The specification § 80 requires that the thickness of plates in compression shall not be less than $\frac{1}{30}$ of the unsupported width, except for the cover plates of top chords and end posts which are limited to $\frac{1}{40}$. The unsupported width of the plate is the distance between rivet heads. For the cover plate it

will be (9), $21\frac{1}{4}'' - 1\frac{7}{16}'' = 19\frac{13}{16}''$. The minimum allowed thickness of cover plate then will be $\frac{19.8}{40} = \frac{1}{2}''$. The minimum allowed thickness of web plate will be $\frac{13.3}{30} = 0.45''$, or say $\frac{1}{2}''$ also.

For the chord sections CD and DD we will try the following, which is about the least chord section allowable as we have seen:

2 web plates	$18'' \times \frac{1}{2}'' =$	18.00 sq. in.
1 cover plate	$24'' \times \frac{1}{2}'' =$	12.00 sq. in.
2 top angles	$3'' \times 3'' \times \frac{3}{8}'' =$	4.22 sq. in.
2 bot. angles	$4'' \times 3'' \times \frac{3}{8}'' =$	4.98 sq. in.
	Total =	39.20 sq. in.

We will now find the location of the center of gravity of the cross section by taking moments of areas about the upper side of the cover plate (see Fig. 63).

Cover plate	12 ×	0.25 =	3.00
Top angles	4.22 ×	1.39 =	5.86
Web plates	18.00 ×	9.62 =	173.25
Bot. angles	4.98 ×	17.97 =	89.49
		Sum =	271.60

Distance of center of gravity from top of cover plate

$$= \frac{271.60}{39.20} = 6.93 \text{ inches.}$$

The distance of the center of gravity above the center of the web plate $= 9.63 - 6.93 = 2.7$ inches.

The least radius of gyration is required to be used in the determination of the allowed unit stresses. This will be about a horizontal axis through the center of gravity, and is equal to

$$\sqrt{\frac{I}{A}}.$$

The moment of inertia about this axis must now be found.[1]

[1] See Heller's "Stresses in Structures," Art. 67, page 92.

This is done by adding to the moment of inertia of each constituent part the product of its area by the distance squared, of its center of gravity from the center of gravity of the section.

$$\begin{aligned}
\text{Cover plate } \frac{24\times(\frac{1}{2})^3}{12} &= 0.25\\
12.00\times(6.68)^2 &= 535.47\\
\text{Top angles } 2\times1.76 &= 3.52\\
4.22\times(5.54)^2 &= 129.52\\
\text{Web plates } \frac{2\times\frac{1}{2}\times(18)^3}{12} &= 486.00\\
18.00\times(2.70)^2 &= 131.22\\
\text{Bot. angles } 2\times1.92 &= 3.84\\
4.98\times(11.04)^2 &= 606.97\\
\text{Total moment of inertia} &= 1896.79
\end{aligned}$$

From which we get the radius of gyration about the horizontal axis through the center of gravity

$$r=\sqrt{\frac{I}{A}}=\sqrt{\frac{1896.79}{39.20}}=6.95 \text{ inches.}$$

The allowed dead load unit stress is $20000-90\frac{L}{r}=15{,}800$ from specifications § 35.

$$\begin{aligned}
\text{Required D.L. area} &= \frac{158800}{15800}=10.05 \text{ sq. in.}\\
\text{Required L.L. area} &= \frac{329500}{7900}=41.71 \text{ sq. in.}\\
\text{Total} &= 51.76 \text{ sq. in.}
\end{aligned}$$

The area of cross section must therefore be increased. We will try the following:

2 web plates	$18''\times\frac{3}{4}''$	$=27.00$ sq. in.
1 cover plate	$24''\times\frac{1}{2}''$	$=12.00$ sq. in.
2 top angles	$3''\times3''\times\frac{7}{16}''$	$=4.88$ sq. in.
2 bot. angles	$4''\times3''\times\frac{5}{8}''$	$=7.98$ sq. in.
	Total	$=51.86$ sq. in.

Eccentricity $=1.68$ in. $I=2494.$ $r=6.93$ in.

The change in the radius of gyration is seen to be very small, and the corresponding change in the allowed unit will be very small, so this section will answer.

BC. The section for this chord will lie somewhere between the two tried above, and therefore we may use the same allowed unit stresses.

$$\text{Required D.L. area} = \frac{132300}{15800} = 8.38 \text{ sq. in.}$$

$$\text{Required L.L. area} = \frac{274500}{7900} = 34.75 \text{ sq. in.}$$

$$\text{Total} = 43.13 \text{ sq. in.}$$



FIG. 64.

Use the following section:

2 web plates	$18'' \times \frac{9}{16}''$	$= 20.25$ sq. in.
1 cover plate	$24'' \times \frac{1}{2}''$	$= 12.00$ sq. in.
2 top angles	$3'' \times 3'' \times \frac{3}{8}''$	$= 4.22$ sq. in.
2 bottom angles	$4'' \times 3'' \times \frac{9}{16}''$	$= 7.26$ sq. in.
	Total	$= 43.73$ sq. in.

Eccentricity = 1.98 in. $I = 2230$. $r = 7.14$ in.

58. Design of the End Posts. Before the *end posts* can be designed the stresses in them due to the *portal bracing* must be determined.

From Fig. 58 we see that we can make the vertical distance from the upper clearance line to the upper pin center 6 ft. 5 ins.

Fig. 64 illustrates the method of determining the depth of portal which we may use. This may be laid out to scale and the depth scaled. For the purpose of calculating the stresses the depth does not have to be determined closer than the nearest 0.1 ft.

In the following calculations of the stresses in the end posts and portal bracing due to wind, the methods and notation used in Heller's "Stresses in Structures," Arts. 153 to 165 inclusive, will be followed.[1]

The specifications § 106 direct that the portals be latticed and that they be rigidly connected to the end posts and top chords.



FIG. 65.

The bearings of the ends of the posts upon the pins at the top and bottom will tend to hold the ends of the posts fixed in direction. The rigidly connected portal at the top will further tend to fix that end of the post; consequently the flexure lines of the posts will be somewhat as shown in an exaggerated amount in Fig. 65. The degree of fixity of the bottom depends upon the amount of the direct stress in the end post. If the moment, the direct stress multiplied by one half the distance between the centers of the bearings of the end post webs on the pin ($\frac{1}{2}kD$), exceeds the moment due to the wind forces when the ends are considered fixed (M_2), the ends may be considered as fixed. Otherwise the ends will be only partially fixed.

[1] See also Johnson's "Modern Framed Structures," Art. 186, or Marburg's "Framed Structures and Girders," Art. 239.

From Fig. 63 we may determine approximately that

$$k_1 = k_2 = \text{about } 17 \text{ inches.}$$

P = Panel load of wind load on top lateral

$$\text{system} = 200 \times 27 = 5400 \text{ pounds}$$

R = Reaction of top lateral system on the portal $= 2P$ (there are 5 panels in the top lateral system) = 10,800 lbs.

To test for the degree of fixity of the ends of the posts assume $H = H' = \frac{1}{2}(R+P)$. (This is assuming fixed ends.) Then $H = H' = 8100$ lbs.

The portal being rigidly connected to the end posts from B to F, fixes the tops of the posts, then the point of contra-flexure would occur midway between a and F or $x_1 = x'_1 = 17.0$ ft.

Taking moments about the point of contra-flexure in one of the posts,

$$\Sigma M = 0 = M_2 - Hx_1$$

from which

$$M_2 = Hx_1 = 8100 \times 17 = 137{,}700 \text{ ft. lbs.} = 1{,}652{,}400 \text{ in. lbs.}$$

Taking moments of all the forces about a in Fig. 65,

$$V' = \frac{1}{b}\left[(R+P)(a+d) - M_2 - M'_2\right] = \frac{1}{b}(R+P)(a+d-x_1),$$

and from vertical components equal zero

$$V = -V' = \frac{1}{b}(R+P)(a+d-x_1) = \frac{1}{16.15} \times 16{,}200 \times (43.0 - 17.0)$$
$$= 26{,}100 \text{ lbs.}$$

The maximum stress in the end posts occurs in the leeward post when the live load is on the bridge and when the wind is acting.

Dead load stress	= 123,100 lbs.
Live load stress	= 255,400 lbs.
Overturning tendency due to wind on train	= 31,300 lbs.
V due to wind on top lateral system	= 26,100 lbs.
Total maximum direct stress	= 435,900 lbs.

The concurrent direct stress in the windward post will be 123,100+255,400−31,300−26,100=321,100 lbs.

The moment of the direct stress at the bottom of the windward post tending to fix the end is

$$\tfrac{1}{2}k_2D=321{,}100\times\tfrac{1}{2}\times17=2{,}729{,}400 \text{ in, lbs.}$$

As this is greater than the moment M_2 tending to rotate the post at a, the posts will be fixed at the bottoms when the live load is on the bridge.

The maximum bending moment in the post occurs either at a' or at F', and is 1,652,400 in. lbs.

We will try for the end posts the same section as was used for top chord sections CD and DD.

The moment of inertia must be calculated for a vertical axis through the center of gravity, as the bending moment due to the wind is transverse.

Area of cross section = 51.86 sq. in. Eccentricity = 1.68 in.

I (horizontal axis) = 2494; least r (horizontal axis) = 6.93 in.

I (vertical axis) = 3848.

The average allowed unit stress for dead and live loads from equation (21)

$$s_w=\frac{17000-90\frac{L}{r}}{1+\frac{255400}{378500}}=\frac{10460}{1.675}=6245 \text{ lbs. per sq. in.}$$

When wind stresses are added to the dead and live load stresses this unit may be increased 30%, (Spec. § 39), making it 8120 lbs. per sq. in.

For this cross section the actual maximum fiber stress would be (50)

$$s_{max}=\frac{P}{A}+\frac{Mv}{I}=\frac{435900}{51.86}+\frac{1652400\times12.875}{3848}$$
$$=8405+5528=13{,}933 \text{ lbs. per sq. in.}$$

Therefore the section must be increased.

As the moment of inertia increases when the area is increased,

we may arrive at an approximate figure for the area by considering the equation above as follows:

$$8405 : s = 13933 : 8120 \text{ from which } s_w = 4900 \text{ lbs.}$$

This value of s_w assumes that in changing the section we have not changed the radius of gyration, and of course can be used only as a general guide.

Using this value of s_w we find that the required area will be $\frac{435900}{4900} = 89$ sq. in., about.

It will be found by trial that this area cannot be made up without materially reducing the radius of gyration, and consequently the allowed unit stress, unless the width or depth of the section be increased.

If the width were increased it would necessitate an equal increase in width of the top chord sections and add materially to their weight without increasing their efficiency. (See Spec. §§ 80 and 100), but the depth of the end posts may be increased somewhat without changing any of the top chord sizes.

After several trials the following section was chosen:

1 cover plate	$24'' \times \frac{5}{8}'' = 15.00$ sq. in.
2 web plates	$21'' \times \frac{7}{8}'' = 36.75$ sq. in.
2 top angles	$3'' \times 3'' \times \frac{5}{8}'' = 6.72$ sq. in.
2 bot. angles	$4'' \times 3'' \times \frac{5}{8}'' = 7.98$ sq. in.
2 side plates	$15'' \times \frac{5}{8}'' = 18.75$ sq. in.
	Total $= 85.20$ sq. in.

The properties of this section are as follows:

Eccentricity = 1.77 in. Area = 85.20 sq. in.

I (horizontal axis) = 4698. I vertical (axis) = 6424.

r (horizontal axis) = 7.43 in.

$$\text{Allowed D.L. unit stress} = 17{,}000 - 90\frac{L}{r} = 10{,}913 \text{ lbs. per sq. in.}$$

Allowed unit stress for D.L.+L.L. from Eq. (21) = 6516 lbs per sq. in.

Allowed unit stress for D.L.+L.L.+wind = 8468 lbs. per sq. in.

$$\text{Max. extreme fiber stress} = \frac{435900}{85.20} + \frac{1652400 \times 12.875}{6424}$$
$$= 5116 + 3312 = 8428 \text{ lbs. per sq. in.}$$

59. The Portal Bracing. The maximum stresses in the portal bracing will occur when there is no live load on the bridge.

The direct stress then in the leeward post, assuming fixed ends as above, is as follows:

$$\begin{aligned} \text{Dead load stress} &= 123{,}100 \text{ lbs.} \\ V &= \underline{\ 26{,}100 \text{ lbs.}} \\ \text{Total} &= 149{,}200 \text{ lbs.} \end{aligned}$$

The concurrent direct stress in the windward post $= 123{,}100 - 26{,}100 = 97{,}000$ lbs.

The moment of the direct stress at the bottom of the leeward post tending to fix that end is

$$\tfrac{1}{2} k_2 D = 149{,}200 \times \tfrac{1}{2} \times 17 = 1{,}268{,}200 \text{ in. lbs.}$$

The moment M_2 required to fix that end is 1,652,400 in. lbs. therefore the posts are only *partially fixed* at the bottoms. The tops are fixed by the construction. An approximate mean value of x_1 and x'_1 may be gotten from the equation

$$x_m = \frac{\frac{1}{2} k_2 D}{\frac{1}{2}(R+P)}.$$

Neglecting V in the value of D, we get

$$x_m = \frac{8.5 \times 123100}{8100} = 129 \text{ in.} = 10.75 \text{ ft.}$$

We may now get an approximate value for V.

$$\text{1st Approx. } V = -V' = \frac{1}{b}(R+P)(a+d-x_m)$$
$$= \frac{1}{16.15} \times 16{,}200(43 - 10.75) = 32{,}300 \text{ lbs.}$$

2nd Approx. $D = 123{,}100 - 32{,}300 = 90{,}800$ lbs.

2nd Approx. $D' = 123{,}100 + 32{,}300 = 155{,}400$ lbs.

2nd Approx. $M_2 = 8.5 \times 90{,}800 = 771{,}800$ in. lbs.

2nd Approx. $M_2' = 8.5 \times 155{,}400 = 1{,}320{,}900$ in. lbs.

2nd Approx. $$H' = \tfrac{1}{2}\left[R + P + \frac{3}{2a}(M_2' - M_2)\right]$$

$$= \tfrac{1}{2}\left(16{,}200 + \frac{3}{2 \times 34 \times 12} \times 549{,}100\right) = 9110 \text{ lbs.}$$

2nd Approx. $H = R + P - H' = 7090$ lbs.

2nd Approx. $$x_1 = \frac{M_2}{H} = \frac{771800}{7090} = 109 \text{ in.} = 9.08 \text{ ft.}$$

2nd. Approx. $$x_1' = \frac{M_2'}{H'} = \frac{1320900}{9110} = 145 \text{ in.} = 12.08 \text{ ft.}$$

2nd Approx. $$V = -V' = \frac{1}{b}\left[(R+P)(a+d-x_1) - H'(x_1' - x_1)\right]$$

$$= \frac{1}{16.15}\left[16{,}200(43 - 9.08) - 9110 \times 3\right] = 32{,}330 \text{ lbs.}$$

As this value of V does not differ materially from the first approximation the values of the other quantities are also determined closely enough.

Taking a section lm through the portal and a center of moments at the bottom flange Fig. 65,

$$\text{Stress in top flange} = R + \tfrac{1}{2}P + H\frac{a - x_1}{d} - V\frac{x}{d}$$

$$= 10{,}800 + 2700 + 7090\frac{24.92}{9.0} - 32{,}330\frac{x}{9}.$$

The maximum compression in the top flange then will occur where $x = 0$ and the maximum tension where $x = b$.

Max. comp. in top flange = 33,100 lbs. (+)
Max. tens. in top flange = 24,900 lbs. (−)

Taking the same section and a center of moments in the top flange

$$\text{Stress in bottom flange of portal} = H\frac{a + d - x_1}{d} - V\frac{x}{d}.$$

The maximum tension occurs where $x=0$ and the maximum compression where $x=b$.

$$\text{Max. tens. in bot. flange} = 7090\frac{33.92}{9} = 26{,}700 \text{ lbs. } (-)$$

$$\text{Max. Comp. in bot. flange} = 26{,}700 - 32{,}330\frac{16.15}{9} = 31{,}300 \text{ lbs. } (+)$$

The maximum shear at any section is $V=32{,}330$ lbs.

For the portal flanges the least allowable radius of gyration is $\frac{1}{120}\times 14\times 12 = 1.4$ inches. (Spec. § 35.)

This radius of gyration is taken perpendicular to the plane of the portal.

Try 2 angles $5''\times 3''\times\frac{5}{16}''$, 5 inch legs outstanding.

Area $=2\times 2.41 = 4.82$ sq. in. gross; $r=2.47$ in.

$$\text{The allowed unit stress} = 13{,}000 - 60\frac{L}{r} = 8920 \text{ lbs. per sq. in.}$$

$$\text{Reqd. area} = \frac{33100}{8920} = 3.71 \text{ sq. in.}$$

These are large enough for the maximum compression stress.

$$\text{The required net area for tension} = \frac{26700}{18000} = 1.48 \text{ sq. in.}$$

Actual net area $=4.82-2\times\frac{5}{16}\times 1 = 4.20$ sq. in. ($\frac{7}{8}''$ rivets.)

For the lattice of the portals we will use angles spaced about as shown in Fig. 65.

Any vertical section will cut four lattice angles, so we will consider the shear as equally divided among them.

The secant of the angle of inclination of the lattice is about 1.4, so the stress in each lattice angle $=1.4\times\frac{32330}{4} = 11{,}300$ lbs. tension or compression.

The smallest angles allowable to use are $3''\times 2\frac{1}{2}''\times\frac{5}{16}''$, (see Spec. § 83), which will be ample to take the above stress.

60. Design of Floor Beams. The weight of the beam itself is a uniform load, the weights of the floor, stringers and live

load form two concentrated loads on the floor beam 6′ 6″ apart Since the beam's own weight is a very small proportion of the total load, it will be considered as concentrated at the stringer connections also.

The maximum live load concentration on the beam may be taken from the specifications, Table I, or calculated from the wheel loads.

Live load at each stringer connection	= 80,000 lbs.	
Dead load from floor	= 200×27	= 5400 lbs.
Weight of stringers	= 165×27	= 4455 lbs.
Weight of $5\frac{1}{2}$ ft. of floor beam say		= 945 lbs.
	Total dead load = 10,800 lbs.	

at each stringer.

The distance center to center of trusses is 16 ft. $1\frac{3}{4}$ in. This is considered as the distance between supports of the floor beams. The distance between the center of the truss and the nearest stringer connection is 4′ $9\frac{7}{8}$″.

The moments on the floor beam are:

Dead load moment = 10,800×4.82 = 52,060 ft. lbs.
Live load moment = 80,000×4.82 = 385,600 ft. lbs.

Economic depth from equation (10) (no flange plates) is

$$1.52\sqrt{\frac{411600\times 12}{10000\times\frac{3}{8}}} = 55 \text{ inches.}$$

The depth assumed in the calculations for the depth of truss was about 13 inches more than the depth of the stringer, or $64\frac{1}{4}$ inches. (See Fig. 58.)

It is desirable to have the stringer connection come between the flange angles of the floor beam rather than to have it lap over the vertical legs of these angles, in order to dispense with filler plates under the connection angles. For these reasons then we will use a web plate 64 inches deep.

The maximum shear = 10,800 + 80,000 = 90,800 lbs.

Using a $\frac{3}{8}''$ web plate the unit shear $= \frac{90800}{24} = 3780$ lbs. per sq. in., which is safe.

Assuming that the flange angles will be $6'' \times 6''$, the effective depth will be about 61 inches.

$$\text{Approx. D.L. flange stress} = \frac{52060 \times 12}{61} = 10{,}240 \text{ lbs.}$$

$$\text{Approx. L.L. flange stress} = \frac{385600 \times 12}{61} = 75{,}860 \text{ lbs.}$$

$$\text{Approx. D.L. required area} = \frac{10240}{20000} = 0.52 \text{ sq. in.}$$

$$\text{Approx. L.L. required area} = \frac{75860}{10000} = 7.59 \text{ sq. in.}$$

$$\text{Total} = 8.11 \text{ sq. in.}$$

$2Ls\ 6'' \times 6'' \times \frac{7}{16}'' = 10.12 - 4 \times \frac{7}{16} \times 1 = 8.37$ sq. in. net. ($\frac{7}{8}$ inch rivets, no holes out of horizontal legs, two holes out of vertical legs, to comply with Spec. § 64.)

The actual effective depth $= 64.25 - 2 \times 1.66 = 60.93$ in.

This will not change the flange stresses given above appreciably, so the flange as designed will answer.

There must be sufficient rivets through the flange angles and web to develop the entire flange stress between the end of the beam and the stringer connection. This will require more rivets than would be given by the horizontal increment (41) because the flange angles cannot run to the theoretical end of the beam which is at the center of the truss. (See Fig. 80.)

End Floor Beams are required by § 10 of the specifications, and it is always good practice to use them rather than to allow the end stringers to rest directly on the abutments.

The end floor beam must carry the half panel load from the end panel of the bridge, and also the load from the short space between the end floor beam and the back wall, which is usually bridged by a cantilever bracket riveted to the beam opposite each stringer. This space will be about 2 ft. in our case.

The dead load at each stringer connection will be

Floor (13.5+2.0)200 = 3100 lbs.
Stringer 15.5×165 = 2560 lbs.
Floor beam say = 840 lbs.
Total D.L. = 6500 lbs.

The live load reaction at the stringer connection must be determined from the actual wheel loads. The maximum reaction on the end floor beam will occur with the wheels placed as shown in Fig. 66.



FIG. 66.

$$\text{The reaction at } a = \frac{1785000}{27} = 66{,}100 \text{ lbs.}$$

Dead load moment = 6500×4.82 = 31,300 ft. lbs.
Live load moment = 66,100×4.82 = 318,600 ft. lbs.

In order to simplify the connection of the end floor beam to the truss, it should be made as shallow as is consistent. We will therefore make the depth only sufficient to allow the stringer to enter between the horizontal legs of the flange angles. This will require a depth of about $52\frac{1}{2}$ or 53 inches.

We will use a web plate $53'' \times \frac{3}{8}''$.

$$\text{Unit shearing stress} = \frac{72600}{19.87} = 3660 \text{ lbs. per sq. in., which is safe.}$$

The effective depth will be about 51 inches.

$$\text{Approx. D.L. flange stress} = \frac{31300 \times 12}{51} = 7360 \text{ lbs.}$$

$$\text{Approx. L.L. flange stress} = \frac{318600 \times 12}{51} = 75{,}000 \text{ lbs.}$$

$$\text{Approx. required D.L. area} = \frac{7360}{20000} = 0.37 \text{ sq. in.}$$

$$\text{Approx. required L.L. area} = \frac{75000}{10000} = 7.50 \text{ sq. in.}$$

Total = 7.87 sq. in.

If the required rivet pitch (41) is not too small for a single line of rivets in the flange, we may use unequal legged angles for the flange with the long legs horizontal, which will be more economical.

Try $2Ls\ 6''\times3\frac{1}{2}''\times\frac{1}{2}''$. Net area $=9.00-2\times\frac{1}{2}\times1=8.00$ sq. in. ($\frac{7}{8}$ inch rivets and no holes out of horizontal legs.)

Actual effective depth $=53.25-2\times0.83=51.59.$

Actual D.L. flange stress $=\dfrac{31300\times12}{51.59}=7300$ lbs.

Actual L.L. flange stress $=\dfrac{318600\times12}{51.59}=74{,}100$ lbs.

Actual required D.L. area $=\dfrac{7300}{20000}=0.37$ sq. in.

Actual required L.L. area $=\dfrac{74100}{10000}=7.41$ sq. in.

Total $=7.78$ sq. in.

This will not allow a reduction below the section assumed above.

The number of rivets required to connect the flange angles to the web, between the stringer connection and the end of the beam will be the total flange stress 81,400 lbs. divided by the value of a $\frac{7}{8}''$ rivet in bearing on the $\frac{3}{8}''$ web. (See Spec. § 40.)

$$\text{Number of rivets}=\frac{81400}{3938}=21.$$

The distance from the stringer connection to the end of the beam will be about 3′ 9″.

Required rivet pitch $=\dfrac{45}{21}=2.12$ inches, which is less than should be allowed in a single line (13). (Spec. § 54.) Therefore $6''\times6''$ angles must be used for the flange angles.

Try $2Ls\ 6''\times6''\frac{7}{16}''$. Net area $=10.12-4\times\frac{7}{16}\times1=8.37$ sq. in. Actual effective depth $=53.25-2\times1.66=49.93$ in.

$$\text{Actual D.L. flange stress} = \frac{31300 \times 12}{49.93} = 7500 \text{ lbs.}$$

$$\text{Actual L.L. flange stress} = \frac{318600 \times 12}{49.93} = 76{,}600 \text{ lbs.}$$

$$\text{Actual required D.L. area} = \frac{7500}{20000} = 0.38 \text{ sq. in.}$$

$$\text{Actual required L.L. area} = \frac{76600}{10000} = 7.66 \text{ sq. in.}$$

$$\text{Total} = 8.04 \text{ sq. in.}$$

Use for flanges $2Ls\ 6'' \times 6'' \times \frac{7}{16}''$.

61. Top Lateral Bracing. (51) The top lateral system is



FIG. 67.

a horizontal Pratt truss of five panels, with the portals at the ends acting as abutments.

Panel load of wind load for top lateral system $= 200 \times 27 =$ 5400 lbs. $\text{Sec } \theta = \frac{31.45}{16.15} = 1.95$.

The stresses are as follows:

Diagonal $BC = 2 \times 5400 \times 1.95 = 21{,}100$ lbs.
Diagonal $CD = 1 \times 5400 \times 1.95 = 10{,}600$ lbs.
Diagonal $DD = 0$
Strut $CC = 1\frac{1}{2} \times 5400 = 8100$ lbs.
Strut $DD = \frac{1}{2} \times 5400 = 2700$ lbs.

$$\text{Required area for diagonal } BC = \frac{21100}{18000} = 1.18 \text{ sq. in.}$$

To comply with specifications § 11 the lateral bracing must be made of shapes capable of resisting compression. It is not good practice to use angles smaller than about $3\frac{1}{2}'' \times 3'' \times \frac{5}{16}''$ for these laterals. The net area of one angle $3\frac{1}{2}'' \times 3'' \times \frac{5}{16}'' = 1.94 -$

$2\times\frac{5}{16}\times 1=1.32$ sq. in., so that these angles will answer for all the diagonals.

The size of the intermediate struts will be determined by §§ 35, 83 and 107 of the specifications. The unsupported length will be about 170 in. From Spec. § 35 the least allowable radius of gyration $=\frac{170}{120}=1.42$ inches. This will require at least $2Ls\ 3''\times 2\frac{1}{2}''\times\frac{5}{16}''$, which are also required to comply with § 83 of the specifications.

$$\text{Allowed unit stress}=13{,}000-60\frac{L}{r}=6000 \text{ lbs. per sq. in.}$$

$$\text{Required area}=\frac{8100}{6000}=1.35 \text{ sq. in.}$$

$$\text{Actual area}=2\times 1.63=3.26 \text{ sq. in.}$$

These top strut angles are run over the top chords and

FIG. 68.

riveted to the cover plates, and two other angles back to back are riveted between the intermediate posts as low down as the specified head room will allow (see Spec. § 107). These two struts are connected by diagonal lattice work of angles similar to the portal (see Fig. 65).

62. Bottom Lateral Bracing. The bottom lateral system (Fig. 68) must resist a static load of 150 lbs. per lin. ft. and a moving load of 450 lbs. per lin. ft. (Spec. § 24.)

Panel load D.L. wind $=150\times 27=4050$ lbs.
Panel load L.L. wind $=450\times 27=12{,}150$ lbs.
$\sec\theta=1.95$ (same as for top lateral system).

The total stresses in the diagonals are as follows:

Diag. $ab = 4050 \times 3 \times 1.95 + 12{,}150 \times 3 \times 1.95 = 94{,}700$ lbs.
Diag. $bc = 4050 \times 2 \times 1.95 + 12{,}150 \times \frac{5}{7} \times 1.95 = 66{,}500$ lbs.
Diag. $cd = 4050 \times 1 \times 1.95 + 12{,}150 \times \frac{1}{7}\frac{0}{} \times 1.95 = 41{,}700$ lbs.
Diag. $dd = 4050 \times 0 \times 1.95 + 12{,}150 \times \frac{6}{7} \times 1.95 = 20{,}300$ lbs.

$$\text{Required area } ab = \frac{94700}{18000} = 5.26 \text{ sq. in.}$$

$$\text{Required area } bc = \frac{66500}{18000} = 3.70 \text{ sq. in.}$$

$$\text{Required area } cd = \frac{41700}{18000} = 2.32 \text{ sq. in.}$$

$$\text{Required area } dd' = \frac{20300}{18000} = 1.13 \text{ sq. in.}$$

To comply with § 33 of the specifications both legs of an angle in tension must be connected if the area of both legs is regarded as effective section, and therefore according to specifications § 64 at least two holes must be deducted from the gross section of each angle.

Use for diagonal *ab* 2*Ls* $6'' \times 3\frac{1}{2}'' \times \frac{3}{8}''$. Net area $= 6.86 - 4 \times \frac{3}{8} \times 1 = 5.36$ sq. in.

Use for diagonal *bc* 2*Ls* $5'' \times 3\frac{1}{2}'' \times \frac{5}{16}''$. Net area $= 5.12 - 4 \times \frac{5}{16} \times 1 = 3.87$ sq. in.

Use for diagonal *cd* 1*L* $5'' \times 4'' \times \frac{3}{8}''$. Net area $= 3.24 - 2 \times \frac{3}{8} \times 1 = 2.49$ sq. in.

Use for diagonal *dd'* 1*L* $3\frac{1}{2}'' \times 3'' \times \frac{5}{16}''$. Net area $= 1.94 - 2 \times \frac{5}{16} \times 1 = 1.32$ sq. in.

The bottom flanges of the floor beams act as the bottom lateral struts, and the compression from the lateral forces tends to relieve the tension in them from vertical loads.

63. Shoes and Rollers. The end reaction will be $3\frac{1}{2}$ panel loads of D.L.+L.L. $= 3\frac{1}{2} + 96{,}430 = 337{,}500$ lbs.

According to specifications § 113 this will require

$$\frac{337500}{250} = 1350 \text{ sq. in. bearing on the masonry.}$$

The masonry plate may be made say 3′ 6″ long by 33 inches wide, giving a bearing area of 1386 sq. in. According to speci-

fications § 114 the rollers cannot be made less than $5\frac{3}{4}$ inches in diameter.

The maximum allowed pressure on the rollers will be $300 \times 5\frac{3}{4} = 1725$ lbs. per lin. in.

$$\text{Required length of rollers} = \frac{337500}{1725} = 196 \text{ inches.}$$

This might be made up of 6 rollers 33 inches long, or 7 rollers 28 inches long. The details can not be worked out without detailing the end posts, end floor beams and shoes.

64. Estimate and Stress Sheet. The *estimate* of weight will now be given. The details can only be estimated approximately until the detail drawings are made. Ordinarily the details are put in the estimate as a percentage of the main truss members, and an estimator of experience in detailing and estimating can choose his percentages so that the total error in weight will be very small.

The *stress sheet* may now be drawn up. (See Fig. 69.)

This is usually as much as is done until after the contract is awarded. The bridge company which fabricates the work makes the detail shop drawings, which are then approved by the railroad company's engineer.

FORM No. 1

THE OHIO STATE BRIDGE COMPANY

Sheet No. 1 Made by C.T.M. Date 12-10-08

Estimate for A.&T.P.Ry. — Bridge No. 107 Southern Div.

Span Extreme 192.5 ft.	Span C. to C. 182.0'	Estimated Steel 1923	Total Steel 366,250
Roadway Single Track.	7 Panels at 27.0'	DL per ft. Floor & Track 400.	Steel per ft. 1936.
Sidewalk — None	Depth C. to C. 32.0'	Total 2323	Total Lumber
Capacity Trusses E-40	Length of Diag. 41.87	Panel Load per Truss DL 31,360	
Capacity Floor See Spec.	Width c. to c. 16.15'	" " " " LL 65070	
Specifications Cooper's '06	Sec. 41.87/32 Tg. 27/32		



Stringers 6'-6" c. to c.
Ties 8"×8"×10'-0"
Guards 6"×8"

MEM	DL Stress	LL Stress	Wind Stress	Total Stress	Unit Stress	Req. Area	MATERIAL	Actual Area	No. Pcs.	Wt. P. Ft.	Length	WEIGHT
							1-24"×5/8"		4	51.0	42.5	8670
	Wind bending=137700'#						2⊐21"×7/8"		8	44.6	42.0	15000
aB	+123.1	+255.4	±57.4				2⊐15"×5/8"	85.2	8	31.9	42.0	10700
							2L 3"×3"×5/8"		8	11.5	42.5	3910
							2L 4"×3"×5/8"		8	13.6	42.0	4570
Bc	-82.1	-182.4				22.35	4⊐6"×15/16" (Eg)	22.5	16	19.1	46.5	14200
Cd	-41.0	-121.6				14.21	2⊐6"×13/16" "	14.25	8	24.2	46.5	9000
Dd'	0	-73.0				7.3	2⊐4"×15/16" Adj. "	7.50	8	12.8	49.5	5080
D'c'	+41.0	-36.5				2.91	1 Sq. 1 7/16" Adj. "	2.97	4	7.0	49.5	1390
Bb	-20.9	-80.1				11.32	2[12"×25# [ ] Net	11.39	8	25.0	33.0	6600
Cc	+41.8	+93.0				21.41	2[15"×40#	23.52	8	40.0	34.0	10880
Dd	+10.5	+55.8				13.27	2[12"×25#	14.72	8	25.0	34.0	6800
abc	-79.4	-164.7	-101.8			22.79	4L 6"×3½"×5/8" # # Net	23.0	32	15.3	26.0	12730
							2⊐14"×3/8"		16	17.9	26.0	7450
cd	-132.3	-274.5	-169.7			37.14	2⊐7"×15/16"	37.64	8	31.2	30.5	7600
							2⊐7"×13/8"		8	32.7	30.5	7980
dd'	-158.8	-329.5	-203.6			44.58	2⊐7"×15/8"	44.64	4	38.7	30.5	4720
							2⊐7"×17/8"		4	37.2	30.5	4540
							1-24"×5/8"		4	40.8	26.0	4240
BC	+132.3	+274.5				43.13	2⊐18"×9/16"	43.73	8	34.4	26.0	7160
							2L 3"×3"×5/8"		8	7.2	26.0	1500
							2L 4"×3"×9/16"		8	12.4	26.0	2580
										Forward→		157300

FORM No. 2

THE OHIO STATE BRIDGE COMPANY

Sheet No. 2 Made by _____ Date _____

Estimate for A & T.P. Ry. Bridge No. 107 Southern Div.

MEM	DL Stress	LL Stress	Impact	Total Stress	Unit Stress	Req. Area	MATERIAL	Actual Area	No. Pcs.	Wt. P. Ft.	Length	WEIGHT
							Brot. Forwd.					157300
							1-24"×½"		2	40.8	83.0	6780
CD &	+158.8	+329.5				51.76	2-18"×⅜"	51.86	4	45.9	83.0	15240
DD							2L 3"×3"×7/16"		4	8.3	83.0	2760
							2L 4"×3"×⅝"		4	13.6	83.0	4520
												186600
							Truss Details 25%					46650
							Total Truss Members →					233250
								233250				
4 Shoes			Bearing Area = 1350 □"						4	@2000#		8000
	End Reaction = 337500#											
2 Roller Nests							5¾" Rollers 196 lin. in.		2	@1500#		3000
								11000				
6 Intermediate Floor Beams												
	DL. Mom. = 52060'#				Web		1-64"×⅜"		6	81.6	15.3	7500
	LL. " = 385660'#				Flgs.	8.11	2L 6"×6"×7/16"	# Net 8.37	24	17.2	15.3	6320
	Shear = 90800#				Web Spl.		2-12"×⅜"		24	15.3	4.3	1580
					Conn. to		2L 6"×3½"×½"		24	15.3	6.0	2200
					Fills		2-3½"×7/16"		24	5.2	5.0	620
					Knees		1-12"×⅜" (Av.)		12	15.3	2.0	370
					"		2L 6"×3½"×⅜"		24	11.7	2.0	560
											Rivets 4%	760
								19910				
2 End Floor Beams												
	DL. Mom. = 31300'#				Web		1-53"×⅜"		2	67.6	15.3	2070
	LL. " = 318600'#				Flgs.	8.42	2L 6"×6"×½"	# Net 9.50	8	19.6	15.3	2400
	End Shear = 72600#										Details & Riv. 50%	2230
								6700				
14 Stringers					Web		1-51"×⅜"		14	65.0	27.0	24600
	DL. Mom. = 32800'#				Flgs.	9.75	2L 6"×3½"×9/16"	# Net 9.93	56	17.1	27.0	25850
	L.L. " = 344600'#				Conn.		2L 6"×6"×½"		56	19.6	4.2	4610
	End Shear = 6420#				Fills		2-12"×9/16"		56	23.0	3.7	4760
					Stiff		2L 3"×3"×⅜" (Crimp		168	7.2	4.2	5090
											Rivets 4%	2590
								67500				
Stringer Laterals					Diag.		1L 3½"×3"×⅜"		21	7.8	10.0	1640
					Struts		1 " " "		14	"	6.0	660
					Conn.		1-12"×⅜" (Av.)		42	15.3	2.5	1600
											Rivets 3%	120
								4020			Forward →	342380

FORM No. 2

THE OHIO STATE BRIDGE COMPANY

Sheet No. 3 Made by _____ Date _____

Estimate for A.&T.P. Ry. Bridge No. 107 Southern Div.

MEM	DL Stress	LL Stress	Impact	Total Stress	Unit Stress	Req. Area	MATERIAL	Actual Area	No. Pcs.	Wt. P. Ft.	Length	WEIGHT
								Brot. Forwd. →				342380
Bottom Laterals												
ab				94.7	18.0	5.26	2 ⊏ 6" × 3½" × ⅜"	5.38	8	11.7	30.0	28800
bc				66.5	"	3.70	2 ⊏ 5" × 3½" × 7/16"	3.87	8	8.7	30.0	20900
cd				41.7	"	2.32	1 L 5" × 4" × ⅜"	2.49	4	11.0	30.0	13200
dd				20.3	"	1.13	1 L 3½" × 3" × 5/16"	1.32	2	6.6	30.0	4000
				Comm. Pl.			1-36" × ⅜" (Art)		12	45.9	4.0	22000
				"	"		" " "		4	"	3.0	5500
				Spl.	"		1-14" × ½"		2	23.8	6.0	2900
				"	"		1-12" × ⅜"		5	15.3	6.0	4600
				Comm. L's			1 L 3½" × 3" × 5/16"		18	6.6	1.5	1800
										Rivets 3%		3100
								10600				
Top Laterals							1 L 3½" × 3" × 5/16"		10	6.6	32.0	21100
								Details & Riv. 10%				2100
								2320				
2 Portal Struts				+33100#			4 L's 5" × 3" × 5/16"					
				-26700#			Lattice 1 L 3" × 2½" × 5/16"		2 @ 2000#			4000
4 Intermediate Struts							4 L's 3" × 2½" × 5/16"					
							Lattice 1 L 3" × 2½" × 5/16"		4 @ 1500#			6000
							Track bolts & Anchors		-	5	189	9500
								Total Steel →				366250


DL=132300#
LL=274500#
DL=158800#
LL=329500#
51.86"
43.73"
DL=123100#
LL=255400#
Wind=51400#
Cent.=13710#
DL=82100#
LL=182400#
DL=41000#
LL=121600#
DL=0
LL=73000#
DL=79400#
LL=164700#
DL=132300#
LL=274600#
DL=158800#
LL=329500#
Wind=101800#
W=169700#
W=203600#
A=44.64"
37.64"
23.0" Net
23.0" Net
7 Panels at 27'-0" = 189'-0" c. to c.
85.2"
32'-0"
16.12" c. to c.
6'-6"
Intermediate Cross section
End Elevation
Top Laterals
Bottom Lateral System
Top Lateral System
Portal Bracing.
Stresses 33180 +
26700 -
Top & Bot. 2 Lb 5 x 3 x 5/8
Lattice Lb 3" x 2 1/2" x 7/16"
Int. Top Struts.
Top & Bot. 2 Lb 3" x 2 1/2" x 5/8"
Lattice Lb 3" x 2 1/2" x 7/16"
Intermediate Floor Beams.
DL. Mom. = 52060'#
LL. " = 385600'#
Web 64" x 3/8"
Flanges 2 Lb 6" x 6" x 1/2"
Net Area = 837.0"
End Shear 90800#
Stringers.
DL Mom. = 32800'#
LL. " = 344600'#
Web 51" x 3/8" Stiff. Lb 3" x 3" x 5/8"
Flanges 2 Lb 6" x 3 1/2" x 5/8"
Net Area = 8.93"
End Shear 64200#
Live Load Cooper's E40
Dead Load 2323 lbs. per Ft.
Single Track
Alignment Tangent
Grade Level
Ties 8" x 8" x 10'-0"
Guards 6" x 8"
Cooper's Specifications for Railway Bridges 1906.
End Floor Beams.
DL. Mom. = 31300'#
LL. " = 318600'#
Web 53" x 3/8"
Flanges 2 Lb 6" x 6" x 1/2"
Net Area = 9.50"
End Shear 72600#
Stringer Laterals.
12 3 1/2" x 3" x 5/8"
End Shoes & Rollers.
Reaction = 337500#
Regd. Bearing 13.50"
" 196 lin. in. 5 3/4" Rollers.
Base of Rail to Masonry 6'-7"
Approved
W. J. Hamming
Chief Engr.
Strain Sheet
Bridge No. 107
Southern Division A. & T. P. Ry.
Single Track 189 ft. Span.
Submitted by
The Ohio State Bridge Co.
Columbus Ohio.
C.T.M. 12-1-08

FIG. 69.

CHAPTER VI

DETAILS OF PIN CONNECTED BRIDGES

65. Detail Drawings. The design for the bridge and the stress sheet are usually worked out by the purchaser's engineer and submitted to contractors for prices, but sometimes the contractors are requested to submit designs with their bids (3). Frequently a general drawing showing more or less detail is submitted with the stress sheet. These drawings are not shop drawings.

After the contract is awarded the detail shop drawings are made by the contractor and approved by the purchaser's engineer. (See Chapter VIII.) These detail drawings show the sizes and positions of all connections and details of members, together with the number and location of all rivets.

The details must be so proportioned that the stresses will be safely and economically transmitted from member to member and finally to the abutments.

66. Pins. A pin is a beam which transmits the stresses at a joint. It is acted upon by forces in different planes, which produce bending moments and shears in it.

It is usually convenient to resolve these forces into their vertical and horizontal components and get the bending moments in these two planes separately. *The maximum bending moment* at any point in the pin then is the resultant of the horizontal and vertical moments at that point. Likewise *the maximum shear* at any point is the resultant of the horizontal and vertical shears at the point.

Since, in most cases, the maximum stresses in all of the members connecting to a pin do not occur under the same loading, the condition for a maximum moment in the pin is uncertain, and the moment must be calculated for the several conditions which give maximum stresses in the various members.

In proportioning the pin for *shear* it must be remembered

that the maximum intensity of shear on any cross section of a solid cylinder is equal to four thirds the average intensity.[1]

The *bearing areas* of the members on the pin must be sufficient so that the material will not crush (18). On this account it is well to have *large pins*, because the larger the pin the less thickness of pin plates required, and also there will be less danger of unequal distribution of stress to the different parts of a member. For example, if there are four bars in a panel of the lower chord, they should be stressed in proportion to their areas, but this will not occur if the pin should bend so as to relieve some of the bars of stress.

On the other hand, the larger the pins the larger will be the diameters of the eye bar heads, and it is often difficult to find room for them, especially at the hip joint.

The arrangement of the parts of the members on the pin is called *the packing*, and this should be such as to produce as small a moment as possible on the pin while at the same time insuring that the eye bars do not pull out of line in passing from joint to joint, more than about one-eighth of an inch per foot, and that the riveted members are of constant width throughout their length.

The sizes of pins must be found *by trial*, since the moments depend upon the thickness of the bearings, and to get these we must first assume a diameter for the pin.

67. Calculation of Pins. A few of the joints of the truss designed in Chapter V will now be detailed to illustrate the methods.

The Hip Joint. (*B.*) According to § 90 of the specifications the least size of pin which may be used here is $0.8 \times 6 = 4.8$ inches, or say $4\frac{7}{8}$ inches.

The allowed bearing pressure on one linear inch of this pin is $4\frac{7}{8} \times 12{,}500 = 60{,}940$ lbs. for live loads and 121,880 lbs. for dead loads. (See Spec. § 41.)

Required bearing on end post *aB*

$$\text{D.L.} = \frac{123100}{121880} = 1.01 \text{ in.}$$

$$\text{L.L.} = \frac{255400}{60940} = 4.19 \text{ in.}$$

$$\text{Total} = 5.20 \text{ in.}$$

[1] See Heller's "Stresses in Structures," Art. 71. Also Rankine's "Applied Mechanics," Art. 309.

Required bearing on top chord *BC*

$$\text{D.L.} = \frac{132300}{121880} = 1.09 \text{ in.}$$

$$\text{L.L.} = \frac{274500}{60940} = 4.50 \text{ in.}$$

$$\text{Total} = 5.59 \text{ in.}$$

Required bearing on hip vertical *Bb*

$$\text{D.L.} = \frac{20900}{121880} = 0.17 \text{ in.}$$

$$\text{L.L.} = \frac{80100}{60940} = 1.32 \text{ in.}$$

$$\text{Total} = 1.49 \text{ in.}$$

The bearing pressures on the eye bars of member *Bc* is taken care of by complying with § 90 of the specifications.

With these bearing thicknesses the spacing of the forces acting on the pin may be determined approximately, as shown in Fig. 70. Sufficient clearance must be allowed between the different parts to allow them to be easily assembled.



FIG. 70.—Packing at *B*.

Fig. 70 shows a horizontal projection of the joint. In order to render the bending moment as small as possible (Spec. § 90) the eye bars should be packed as near their resistances as possible.

The bending moments and shears will have to be calculated for two positions of the live load, one which gives maximum stresses in the top chord and end post, and one which gives a maximum stress in the diagonal *Bc*.

In figuring pins the same equivalent uniform loads may be used as were used in calculating the stresses in the members. It is a useless refinement in calculating pins, to figure the stresses

by the actual wheel load method, even when the original stresses have been so figured. The algebraic sum of the horizontal and vertical components of the forces acting on the pin must always be zero. When the pins are symmetrically packed, as they always should be, the shear at the middle will be zero also and the moments on only half the pin need be figured. By keeping these facts in mind and putting down the stresses from the stress sheet, for those members in which the stress is a maximum, the others can usually be obtained without calculating them from the loads.

Usually the moments and shears on pins are calculated upon the assumption that the stresses in the members are concentrated at the centers of their bearing areas. This assumption is on the safe side, as the stresses are actually distributed over the bearing areas and, generally, the moments produced by distributed loads are less than those produced by the same loads concentrated.

Cooper's specifications, § 41, permits the calculation of the moments and shears on the assumption that the stresses are distributed uniformly over the middle half of the bearing areas. It is somewhat more laborious to calculate the stresses upon this assumption than upon the assumption of concentrated loads, and in practice the concentrated load method is almost universally used.

The moments and shears have been calculated by both methods for the pin at B and the moment and shear diagrams for the two methods are shown in Fig. 71. The dotted lines indicate the moments and shears figured by the concentrated load method and the full lines those calculated by assuming the pressure uniformly distributed over the middle half of the bearing.

The calculation of the moments is best made in tabular form, remembering that the moment at any force is equal to the moment at the next preceding force plus the product of the shear by the distance between the forces.[1]

In making up the table always begin at the outside where the shear is zero and work toward the center where the shear is again zero.

[1] See any book on Mechanics.

MAXIMUM STRESSES IN *aB* AND *BC*

MOMENTS OF HORIZONTAL COMPONENTS

Mem.	Horizontal Component.	Shear.	Lever Arm in Inches.	Moments.	
				Increment.	Total.
Bc	− 40,700				
		− 40,700	2	− 81,400	
BC	+203,400				− 81,400
		+162,700	¾	+122,000	
aB	−122,000				+ 40,600
		+ 40,700	2	+ 81,400	
Bc	− 40,700				+122,000
		000	2	000	
Bb	000				+122,000

MOMENTS OF VERTICAL COMPONENTS

Mem.	Vertical Component.	Shear.	Lever Arm in Inches.	Moments.	
				Increment.	Total.
Bc	− 48,200				
		− 48,200	2	− 96,400	
BC	000				− 96,400
		− 48,200	¾	− 36,150	
aB	+144,600				−132,500
		+ 96,400	2	+192,800	
Bc	− 48,200				+ 60,250
		+ 48,200	2	+ 96,400	
Bb	− 48,200				+156,650

The maximum resultant moment for this loading occurs at *Bb* and is

$$\sqrt{(122{,}000)^2+(156650)^2}=198{,}730 \text{ in. lbs.}$$

MAXIMUM STRESS IN *Bc*

MOMENTS OF HORIZONTAL COMPONENTS

Mem.	Horizontal Component.	Shear.	Lever Arm in Inches.	Moments.	
				Increment.	Total.
Bc	− 42,800				
		− 42,800	2	− 85,600	
BC	+184,100				− 85,600
		+141,320	¾	+106,000	
aB	− 98,500				+ 20,400
		+ 42,800	2	+ 85,600	
Bc	− 42,800				+106,000
		000	2	000	
Bb	000				+106,000

MOMENTS OF VERTICAL COMPONENTS

Mem.	Vertical Component.	Shear.	Lever Arm in Inches.	Moments.	
				Increment.	Total.
Bc	− 50,500	−50,500	2	−101,000	
BC	− 000	−50,500	¾	− 37,800	−101,000
aB	+116,500	+66,000	2	+132,000	−138,800
Bc	− 50,500	+15,500	2	+ 31,000	− 6,800
Bb	− 15,500				+ 24,200

The maximum resultant moment for this loading occurs at *aB* and is

$$\sqrt{(20400)^2+(138800)^2}=140{,}300 \text{ in. lbs.}$$

Then the maximum bending moment on the pin occurs under full loading and is 198,700 in. lbs.

The maximum moment when figured by considering the pressures distributed over the middle half of the bearing areas is the same in this case. The effect is to round the apexes of the moment diagram. With an allowed fiber stress of 18,000 lbs. per square inch this will require a $4\frac{7}{8}$ inch pin, (see "Cambria," page 300) or exactly the size that was assumed.

The maximum shear is materially different when figured by the two methods, in this case, because the bearing areas of the end post and the top chord overlap. The actual maximum shear is probably more nearly that given by considering the pressures distributed over the middle half of the bearing areas. At other joints the shears will usually be the same when figured by either method.

The maximum resultant shear when the loads are considered distributed, occurs for full load, between members *BC* and *aB* and is $\sqrt{(106060)^2+(96400)^2}=143{,}200$ lbs. This gives a maximum required area of $\frac{4}{3}\times\frac{143320}{9000}=21.22$ sq. in. A $5\frac{1}{4}$ inch pin will answer.

In a similar manner the pins at the other joints are figured with the following results;


Horizontal Projection of Pin
15/16"
2 13/16"
15/16"
1 1/2"
BC
Bc
aB
Bc
Bb
2"
3/4"
2"
2"
5"
Center Line of Truss
162700
106060
74560
40700
Shear Diagram
Horizontal Components
40,700
122060
112520
67370
40,690
15770
Moment Diagram
Horizontal Components
9540
52780
39270
58500
81400
96400
48200
Shear Diagram
Vertical Components
48200
156650
138570
71540
60250
37640
Moment Diagram
Vertical Components
11300
69300
100920
111470
132550

FIG. 71.

At a a $5\frac{3}{4}$ inch pin is required.
At c a $5\frac{1}{2}$ inch pin is required.
At d a $5\frac{3}{8}$ inch pin is required.

It will make the shopwork and erection somewhat simpler



FIG. 72.—Packing at a.



FIG. 73.—Packing at c.



FIG. 74.—Packing at d.



FIG. 75.—Packing at C.

if these pins are all made the same size, so we will use $5\frac{3}{4}$ inch pins at a, c, d, and B.

No pin is used at b, but the bottom chord is run through continuously from a to c, and a riveted connection is made at b between Bb and the chord abc.

At C a $4\frac{7}{8}$ inch pin is required, and we will use the same size at D.

Figs. 72 to 75 inclusive, show the packing at the various joints.

68. Camber. Camber is the slight arching of the bridge which is put into it for appearance. All bridges should be cambered [1] in order that they may not sag below a straight line under the maximum load and also to prevent the appearance of sagging at any time. A perfectly straight girder, when viewed from the side, will appear to be deflected downward.

Trusses are cambered by making the top chord slightly longer than the bottom chord. The diagonals must be figured for this increased length. Some specifications give the amount of increase of length of top chord to put in, and others specify the amount of camber (middle ordinate to the curve) in the span. For a given increase of length of top chord, the amount of cam-



FIG. 76.

ber will vary with the depth of the truss. The following formula is taken from Trautwine's "Civil Engineer's Pocketbook," page 607:

$$\text{Increase in length of top chord} = \frac{\text{Depth} \times \text{camber} \times 8}{\text{Span}}.$$

All in feet or all in inches.

Fig. 76 is an exaggerated diagram of the truss showing the camber. Specifications, § 120, requires that the top chord be made longer than the bottom chord at the rate of $\frac{1}{8}$ inch for each 10 feet. This will make each top chord panel 27′ $0\frac{3}{8}''$.

The length of the diagonals will be

$$\sqrt{(27'\ 0\tfrac{3}{16}'')^2 + (32'\ 0'')^2} = 41''\ 10\tfrac{9}{16}''.$$

[1] See Cooper's "Specifications," § 120.
American Railway Specifications, § 77 and § 81.

From Trautwine's formula we can compute the camber which this will give the truss.

$$2\tfrac{5}{8}'' = \frac{32\times 12\times \text{camber}\times 8}{189\times 12}. \quad \text{Camber} = 1.93 \text{ inches.}$$

69. Details of a Riveted Tension Member. (19) A detail drawing of one end of the lower chord *abc* is shown in Fig. 77.



Fig. 77.

The width of the member is determined by the packing at *a* and *c* as shown in Figs. 72 and 73.

The maximum stress in the member is 345,900 lbs. (D.L.+L.L. +wind). The average allowed unit stress in tension is 15,520 lbs. per sq. in., and the required net area of the body of the member is 22.29 sq. in. (See Art. 56.) According to the specifications § 68 the net section through the pin hole must be one-third in excess of this amount, or 29.72 sq. in., and the least section back of the pin hole 60% of this, or 17.83 sq. in.

The net section of the $2-14''\times\frac{3}{8}''$ plates through the pin hole is

$$2[2\times 2\tfrac{1}{8}+2\sqrt{(2\tfrac{1}{2})^2+(4\tfrac{7}{8})^2}-5\tfrac{3}{4}-2]\tfrac{3}{8}=5.60 \text{ sq. in.}$$

The balance $=29.72-5.60=24.12$ sq. in., must be made up of pin plates.

The effective net width through the pin hole, of plates 16 inches wide is (see Fig. 77):

$$2\times 3\tfrac{1}{8}+2\sqrt{(2\tfrac{1}{2})^2+(4\tfrac{7}{8})^2}-5\tfrac{3}{4}-2=9.46 \text{ in.}$$

Then the required thickness for pin plates 16 inches wide to take the tension is

$$\frac{24.12}{9.46}=2.55 \text{ in., or say } 2\tfrac{5}{8} \text{ inches.}$$

This will require one pin plate $16''\times\tfrac{5}{8}''$ and one $16''\times\tfrac{11}{16}''$ on each side.

The average allowed unit stress in bearing on the pin

$$(\text{D.L.}+\text{L.L.}+\text{W.})=\frac{25000}{1+\dfrac{274.5}{406.8}}\times 1.3=19{,}400 \text{ lbs. per sq. in.}$$

(from Eq. (21) and Spec. § 39), and the allowed bearing pressure per linear inch of pin is $5\tfrac{3}{4}\times 19{,}400=111{,}550$ lbs.

None of the bearing plates can however be counted on to take more stress in bearing than they transmit past the pin hole in tension.

The net area through the pin hole is as follows:

$$\begin{aligned}
2-14''\times\ \tfrac{3}{8}''&=7.46\times\tfrac{3}{4}\ =\ 5.60 \text{ sq. in.}\\
2-16''\times\ \tfrac{5}{8}''&=9.46\times 1\tfrac{1}{4}=11.82 \text{ sq. in.}\\
2-16''\times\tfrac{11}{16}''&=9.46\times 1\tfrac{3}{8}=13.01 \text{ sq. in.}\\
&\text{Total}=30.43 \text{ sq. in.}
\end{aligned}$$

The stress transmitted by the $2-14''\times\tfrac{3}{8}''$ plates past the pin hole will be proportional to the areas, and is

$$\frac{5.60}{30.43}\times 345{,}900=63{,}650 \text{ lbs.}$$

The stress transmitted by the other pin plates is

$$345{,}900-63{,}650=282{,}250 \text{ lbs.}$$

Then the required bearing thickness of the 16 inch pin plates $=\frac{282250}{111550}=2.53$ inches, therefore the 16 inch pin plates used are sufficient.

The required net length back of the pin hole $=\frac{17.83}{3\frac{3}{8}}=5.3$ in. Allowing one rivet hole out this will require the pin plates to extend $5\frac{3}{8}+1+2\frac{7}{8}=9\frac{1}{4}$ inches beyond the pin center.

The stresses taken by the component parts of the *body* of the member will be in proportion to their gross areas because their deformations must be equal, and the connection must distribute this stress properly to the component parts.

The stress taken in the body of the member by 1—14″×⅜″ plate $=\frac{5.25}{28.50}\times 345{,}900=63{,}700$ lbs.

Therefore $63{,}700-\frac{1}{2}\times 63{,}650=31{,}875$ lbs. must be transmitted from each of the 14″×⅜″ plates to the 16 inch pin plates before the pin hole is reached.

The stress transmitted past the pin hole by each of the 16 inch pin plates is as follows:

$$16''\times\ \tfrac{5}{8}''\text{ plate}=\tfrac{10}{42}\times 282{,}250=67{,}200\text{ lbs.}$$
$$16''\times\tfrac{11}{16}''\text{ plate}=\tfrac{11}{42}\times 282{,}250=73{,}925\text{ lbs.}$$

and sufficient rivets must be provided to transmit these stresses from these plates to the body of the member.

The six countersunk rivets between the pin and the end of the angles may be considered as transmitting stress from the outside pin plate to the 14″×⅜″ plate so long as this does not raise the total stress in that plate above its proportion of the stress in the body of the member, 63,700 lbs.

The value of the six countersunk rivets in the ⅜ inch plate is $6\times\frac{3}{7}\times 4922=12{,}660$ lbs. (Spec., § 40). This would bring the total stress in the 14″×⅜″ plate at the end of the angles up to $12{,}660+\frac{1}{2}\times 63{,}650=44{,}490$ lbs., which is less than 63,700 lbs., and therefore safe.

Further rivets will be required in the outside pin plate to transmit $67{,}200-12{,}660=54{,}540$ lbs. The rivets will be in single shear and the number required $=\frac{54540}{5412}=10.$

The rivets to transmit the stress from the inside $16'' \times \frac{11}{16}''$ pin plate must be placed beyond those required for the outside pin plate. The number required $= \frac{73925}{5412} = 14$.

The required net area of the body of the member through the first line of rivets of the connection plates is 22.29 sq. in., and the required net area on a zig zag line of holes $= 1.3 \times 22.29 = 28.98$ sq. in. (Spec. § 64.)

Assuming that a lacing rivet comes opposite the first rivet in the pin plate (which is not exactly the case here) we may write an equation as follows, and solve for the least allowable pitch of rivets in the connection plate at this point (19). Calling this distance x we have

$$28.98 = \tfrac{1}{2} \times 4\left(1\tfrac{1}{2} + 1\tfrac{1}{2} + \sqrt{(2\tfrac{1}{4})^2 + x^2} + \sqrt{(3\tfrac{3}{4})^2 + x^2} - 3\right) + 2 \times \tfrac{3}{8}\left(2\tfrac{1}{8} + 2\tfrac{1}{8} + 5\tfrac{1}{4} + 2\sqrt{(2\tfrac{1}{4})^2 + x^2} - 4\right)$$

Solving we get $x = 3\frac{1}{2}$ inches.

This pitch may safely be reduced to 3 inches after the first line of rivets is passed, as the stress in the body of the member has been reduced by the value of the rivets passed.

The lacing of a tension member does not have to comply with § 97 of the specifications, and may be put in according to the judgment of the engineer.

70. Location of Pins in Top Chord and End Posts. (50) The location of the pins in the top chords and end posts depends upon the location of the centers of gravity of the sections and upon the amount of the displacement of the pins necessary to compensate for the bending due to the weight of the member.



FIG. 78.

The pin at the hip cannot be placed in the exact theoretical location for both the end post and top chord, and its location must necessarily be a compromise between the two.

Fig. 78 shows the factors which must be taken into consideration in this problem. From § 43 of the specifications we

see that the bending moment due to the weight of the member need not be considered unless it increases the fiber stress more than 10% above the allowed unit.

The weight of the end post will be as follows:

1 cover plate	$24'' \times \frac{5}{8}''$	$= 51.0$
2 web plates	$21'' \times \frac{7}{8}''$	$= 89.2$
2 side plates	$15'' \times \frac{5}{8}''$	$= 63.8$
2 top *Ls*	$3'' \times 3'' \times \frac{5}{8}''$	$= 23.0$
2 bottom *Ls*	$4'' \times 3'' \times \frac{5}{8}''$	$= 27.2$
		254.2
Details say 10%		$= 25.8$
Total		$= 280.0$ lbs. per lin. ft.

The weight per linear foot horizontal will be 280 csc $\theta = 434$ lbs., and the bending moment due to the weight will be

$$\frac{434 \times 27^2}{8} = 39{,}550 \text{ ft. lbs.}$$

The maximum compressive fiber stress due to weight $= \frac{39550 \times 12 \times 9.48}{4698} = 960$ lbs. per sq. in. in the top of the cover plate. (See Art. 58.) The allowed unit stress for D.L.+L.L. is 6516 lbs. per sq. in., therefore the bending moment due to weight must be considered in the end post.

The maximum compressive fiber stress due to weight or to displacement of the pins may reach 651 lbs. per sq. in.

The weight of the end section of the top chord is as follows:

1 cover plate	$24'' \times \frac{1}{2}''$	$= 40.8$
2 web plates	$18'' \times \frac{9}{16}''$	$= 68.8$
2 top *Ls*	$3'' \times 3'' \times \frac{3}{8}''$	$= 14.4$
2 bottom *Ls*	$4'' \times 3'' \times \frac{9}{16}''$	$= 24.8$
		148.8
Details say 10%		$= 14.2$
Total		$= 163.0$ lbs. per ft.

The bending moment due to the weight $= \frac{163 \times 27^2}{8} = 14{,}880$

ft. lbs. The distance from the middle of the web to the center of gravity is 1.98 in., and the moment of inertia about the horizontal axis is 2230.

The maximum compressive fiber stress due to weight $= \frac{14880 \times 12 \times 7.64}{2230} = 612$ lbs. per sq. in.

The average allowed unit stress for D.L.+L.L. from equation (21) is 9490 lbs. per sq. in., therefore the bending due to weight need not be considered in the top chord.

The most desirable location for the pin will be obtained from equation (20) as follows:

$$\text{For the end post } e = \frac{434 \times 27^2 \times 12}{10 \times 378500} = 1.00 \text{ in.}$$

$$\text{For the top chord } e = \frac{163 \times 27^2 \times 12}{10 \times 406800} = 0.36 \text{ in.}$$

For the end post the pin should be $1.77 - 1.00 = 0.77$ in. above the center line of the web.

For the top chord the pin should be $1.98 - 0.36 = 1.62$ in. above the center line of the web.

If x_2 in Fig. 78 is made 8 in. to agree with the most desirable position for the top chord, from similar triangles $x_1 : x_2 = d_1 : d_2$ or $x_1 = 9.33$ in., which would place the pin in the end post above the center of gravity.

If x_1 is made $10\frac{1}{2}$ in. to agree with the most desirable position for the end post, $x_2 = 9.00$ in.

This will place the pin $\frac{3}{4}$ in. above the center of the web of the end post and $\frac{5}{8}$ in. above the center of the web of the top chord. This location will be used.

The pins at the intermediate top chord points are placed on the same center line as those at the hips, as they only have to transmit the increments of stress from the diagonals.

Fig. 79 is a detail of the hip joint.

71. Lacing of Compression Members. (50) The lacing for the top chord will be calculated by each of the three methods given in Art. 50, so that the results may be compared. The lacing is in a horizontal plane to resist bending about a vertical

axis so we will have to use the radius of gyration about the vertical axis.



FIG. 79.

For the top chord CD (which is the largest) the allowed unit stress for D.L.+L.L. from equation (21) is

$$\frac{20000-90\frac{L}{r}}{1.675}=11{,}940-53.7\frac{L}{r}=9920 \text{ lbs. per sq. in.}$$

(using the radius of gyration about the vertical axis).

From equation (18)

$$f=\frac{4\times19.93\times20}{27\times12}=497 \text{ lbs. per in.}$$

Length of member covered by one lace bar (single lacing, Spec. § 97) $=22\frac{1}{4}$ cot $60°=12.8$ in.

Longitudinal increment of stress taken by one bar $=497\times12.8\times\frac{1}{2}=3180$ lbs. (Half is taken by cover plate.)

The stress in one bar $=3180$ sec $60°=6360$ lbs.

Second Method. The total safe compressive load on the member is $\frac{15800}{1.675}\times51.86=489{,}200$ lbs. (See Art. 57.) The transverse shear equals 1 to 3% of this, which is 4890 to 14,680 lbs.

$$\text{Stress in one bar}=\tfrac{1}{2}\times\begin{Bmatrix}4890\\14680\end{Bmatrix}\times\csc 60°=\begin{Bmatrix}2825\\8475\end{Bmatrix}.$$

Third Method.

$$\frac{Mv}{I}=\frac{Mv}{Ar^2}=53.7\frac{L}{r}=2020,$$

$$M=\frac{2020\times51.86\times(8.61)^2}{12\frac{7}{8}\times12}=50{,}250 \text{ ft. lbs.}=\tfrac{1}{4}PL.$$

Transverse shear $=\frac{1}{2}P=3725$ lbs.

Stress in one bar $=\frac{1}{2}\times3725\times\csc 60°=2150$ lbs.

From these calculations it is seen that the three methods agree fairly well.

In the lattice it is safe to use the unit stresses allowed for lateral bracing.

Specifications § 97 require the lattice for this chord to be $\frac{5}{8}$ in. thick.

Allowed unit stress in compression is

$$13{,}000-60\frac{L}{r}=13{,}000-\frac{60\times25.6}{0.181}=4520 \text{ lbs. per sq. in.}$$

$$\text{Required area}=\frac{6360}{4520}=1.41 \text{ sq. in.}$$

$$\text{Required width}=\frac{1.41}{.625}=2.26 \text{ in.}$$

Use lace bars $3'' \times \frac{5}{8}''$ for top chords to comply with specifications § 97.

The lacing for the end posts can not be obtained directly from equation (18) because the end post carries transverse shear in addition to the direct stress.

The total difference in extreme fiber stress due to column action is obtained from the column formula for D.L.+L.L.+wind.

$$\text{From Eq. (21)} \qquad s_c = \frac{17000 - 90\frac{L}{r}}{1.675} \times 1.3 = 13{,}200 - 69.8\frac{L}{r}.$$

The values of L and r here must be taken about a vertical axis because we are figuring for the shear in that direction.

The difference in unit stresses due to column action $= 69.8 \times \frac{34 \times 12}{8.68} = 3280$ lbs. per sq. in.

The difference in unit stresses due to transverse bending from Art. 58 = 3310 lbs. per sq. in.

Total difference = 3310 + 3280 = 6590 lbs. per sq. in.

Total stress to be transferred by the lacing and cover plate in a distance of 17 ft. (distance from end to point of contraflexure) $= 6590 \times A_1 = 6590 \times 35.1 = 231{,}300$ lbs.

$$f = \frac{231300}{17 \times 12} = 1134 \text{ lbs. per inch.}$$

Longitudinal increment of stress taken by one bar $= 1134 \times 12.8 \times \frac{1}{2} = 7260$ lbs.

Total stress in one bar = 7260 sec 60° = 14,520 lbs.

Using bars $\frac{5}{8}$ in. thick, the allowed compressive unit stress is 4520 lbs. per sq. in.

$$\text{Required area} = \frac{14520}{4520} = 3.21 \text{ sq. in.}$$

$$\text{Required width} = \frac{3.21}{.625} = 5.12 \text{ in.}$$

Use lace bars $5'' \times \frac{5}{8}''$ with two rivets in each end.

For the intermediate posts Cc, the radius of gyration perpendicular to the channel webs is 4.31 in., and the unsupported length in that direction about 21 ft.

$$\text{The allowed unit stress for D.L.+L.L.} = 10{,}060 - 53.25\frac{L}{r}$$

$$= 6950 \text{ lbs. per sq. in.} \quad \text{(See Art. 57.)}$$

From equation (18) we get

$$f = \frac{4 \times 11.76 \times 3110}{21 \times 12} = 580 \text{ lbs. per inch.}$$

The length covered by one lace bar (single lacing, Spec. § 97) is $3\frac{1}{2}$ inches.

Longitudinal increment of stress taken by one bar $= 580 \times 3\frac{1}{2} \times \frac{1}{2} = 1015$ lbs. (Lacing on two sides.)

Stress in one bar $= 1015 \sec 60° = 2030$ lbs.

Specifications § 97 require that the lacing for this case be $\frac{7}{40}$ inch thick, but § 82 limits us to $\frac{3}{8}$ in.

$$\text{Allowed unit stress} = 13{,}000 - \frac{60 \times 7}{.108} = 9100 \text{ lbs. per sq. in.}$$

$$\text{Required area} = \frac{2030}{9100} = 0.23 \text{ sq. in.}$$

$$\text{Required width} = \frac{.23}{.375} = 0.61 \text{ in.}$$

Specifications § 97 requires $2\frac{1}{2}$ in. $\times \frac{3}{8}$ in.

For post Dd specifications require lacing $2\frac{1}{4}'' \times \frac{3}{8}''$.

72. Details of the Floor Beams. In all calculations relating to the floor beams, the span of the beam is considered as the distance between the center lines of the trusses. The ends of the floor beams must be cut away at the bottom to allow the connection of the diagonal and chord members on to the pin, and where this is cut away the cross section must be reinforced sufficiently so that the maximum extreme fiber stress does not exceed that allowed by the specifications.

RIVET VALUES

COOPER'S GENERAL SPECIFICATIONS FOR STEEL RAILWAY BRIDGES AND VIADUCTS—1906

	Diameter	Single Shear, 9000 #	Double Shear, 18000 #	Bearing Value for Different Thicknesses of Plate in Inches at 15,000 Lbs. per Square Inch.												
				1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4	13/16	7/8	15/16	1
SHOP TRUSSES AND FIELD LATERALS	3/4"	3,976	7,952	2,813	3,516	4,219	4,922	5,625	6,328	7,031	7,734	8,438				
	7/8"	5,412	10,823	3,281	4,102	4,922	5,742	6,563	7,383	8,203	9,023	9,844	10,664	11,484	12,305	
	1"	7,069	14,137	3,750	4,688	5,625	6,563	7,500	8,438	9,375	10,313	11,250	12,188	13,125	14,063	15,000
	Diameter	Single Shear, 7200 #	Double Shear, 14400 #	Bearing Value for Different Thicknesses of Plate in Inches at 12,000 Lbs. per Square Inch.												
				1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4	13/16	7/8	15/16	1
SHOP FLOOR	3/4"	3,181	6,362	2,250	2,813	3,375	3,938	4,500	5,063	5,625	6,188	6,750				
	7/8"	4,329	8,659	2,625	3,281	3,938	4,594	5,250	5,906	6,563	7,219	7,875	8,531	9,188	9,845	
	1"	5,655	11,310	3,000	3,750	4,500	5,250	6,000	6,750	7,500	8,250	9,000	9,750	10,500	11,250	12,000
	Diameter	Single Shear, 13500 #	Double Shear, 27000 #	Bearing Value for Different Thicknesses of Plate in Inches at 22,500 Lbs. per Square Inch.												
				1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4	13/16	7/8	15/16	1
SHOP LATERALS	3/4"	5,964	11,928	4,219	5,273	6,328	7,383	8,438	9,492	10,547	11,601	12,656				
	7/8"	8,118	16,236	4,922	6,152	7,383	8,613	9,844	11,074	12,305	13,535	14,766	15,996	17,226	18,457	
	1"	10,603	21,206	5,625	7,031	8,438	9,844	11,250	12,656	14,063	15,469	16,875	18,281	19,688	21,094	22,500
	Diameter	Single Shear, 6000 #	Double Shear, 12000 #	Bearing Value for Different Thicknesses of Plate in Inches at 10,000 Lbs. per Square Inch.												
				1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4	13/16	7/8	15/16	1
FIELD TRUSSES	3/4"	2,651	5,302	1,875	2,344	2,812	3,281	3,750	4,219	4,687	5,156	5,625				
	7/8"	3,608	7,216	2,187	2,734	3,281	3,828	4,375	4,922	5,469	6,015	6,562	7,109	7,656	8,203	
	1"	4,712	9,424	2,500	3,125	3,750	4,375	5,000	5,625	6,250	6,875	7,500	8,125	8,750	9,375	10,000
	Diameter	Single Shear, 4800 #	Double Shear, 9600 #	Bearing Value for Different Thicknesses of Plate in Inches at 8000 Lbs. per Square Inch.												
				1/4	5/16	3/8	7/16	1/2	9/16	5/8	11/16	3/4	13/16	7/8	15/16	1
FIELD FLOOR	3/4"	2,121	4,241	1,500	1,875	2,250	2,625	3,000	3,375	3,750	4,125	4,500				
	7/8"	2,886	5,772	1,750	2,188	2,625	3,063	3,500	3,937	4,375	4,812	5,250	5,687	6,125	6,562	
	1"	3,770	7,540	2,000	2,500	3,000	3,500	4.000	4,500	5,000	5,500	6,000	6,500	7,000	7,500	8,000

Fig. 80 shows a detail drawing of one of the intermediate floor beams and the lower end of the post with the connecting members. The cross section at the end has been reinforced by the addition of 2 plates $35'' \times \frac{7}{16}''$ on the web, and by the bent flange angles at the end.

Cooper's specifications § 40, require the use of a number of different unit stresses for rivets in various positions, and these must be kept in mind in detailing. The table below gives these values. The bearing values below the lower zigzag lines are less than single shear; between the upper and lower zigzag lines they are greater than single shear and less than double shear, and above the upper zigzag line they are greater than double shear.

Neither the top nor the bottom flange angles extend to the theoretical end of the beam (center of the truss) and therefore the rivet pitch in the flanges cannot be calculated by the methods of Art. 41, but sufficient rivets must be put in between the stringer connection and the end of the flange angles to carry all the stress in the flange at the stringer connection. (60.)

To get sufficient connection for the bottom flange the expedient is resorted to of riveting plates on top of the flange angles, to transfer a part of their stress to the web. The rivets through these plates and the angles are in double shear plus bearing on the web.

The total flange stress to be transferred is

7500 lbs. D.L. + 76,600 lbs. L.L. = 84,100 lbs. (See Art. 60.)

The connection of the bottom flange as shown is good for the following stress:

16 rivets bearing on $\frac{3}{8}$ in. web = 16×3938 = 63,000 lbs.
6 rivets in double shear = 6×8659 = 51,900 lbs.

Total = 114,900 lbs.

The connection of the top flange is good for 26 rivets bearing on $\frac{3}{8}$ in. web = 26×3938 = 102,400 lbs.

Rivets required for the stringer connection = $\frac{90800}{2625} = 35$.


All Rivets ⅞" except in flanges of channels ¾"
Post Dd
Lacing 2½"×⅜"
Stay Pl. 10"×⅜"×1'-3"
16'-1⅞" c. to c. Trusses.
15'-3¾" b. to b. of Angles.
2'-0"
6'-6" c. to c. String.
2 Fills 4"×⅜"
Pl. 28½"×⅜"×7'-1½"
2 L 6"×3½"×⅜"×2'-3"
Diaphram {4 L's 4"×3½"×⅜"×5'-0¼"
1-Pl. 9"×⅜"×5'-4¾"
2 L's 4"×4"×⅜"×5'-3¼"
2 Bent L's 6"×3½"×7/16"
2 Bent Fillers 6"×½"
2 Reinforcing Pls. 35"×⅜"×4'-4"
Holes for Stringer Conn.
2 L 6"×6"×⅞"×15'-3¾"
Web 64"×⅜"×10'-6"
Center Line
5'-4½" b. to b. L's
10½"
1'-0"
5"
10½"
2 L 6"×6"×⅞"×13'-6¾"
2-Pl. 8½"×½"×1'-6⅜"
2 L 6"×3½"×7/16"×1'-1"
Lateral cd
Center Line of Truss
⅜" Gusset
d
Lateral dd

FIG. 80.

Rivets required for the end connection angles of the floor beam through the web $= \frac{90800}{8659} = 11.$

Rivets required for the field connection to the post $= \frac{90800}{2886} = 32.$

Rivets required on each side of web splice $= \frac{90800}{3938} = 23.$

CHAPTER VII

HIGHWAY BRIDGES

THE problems met in highway bridge design are in many respects more difficult of satisfactory solution than those in railway bridges. There are many more uncertain features present. Chief among these is uncertainty as to the amount and position of the loads and their distribution through the flooring materials to the other parts of the structure.

Notwithstanding this fact there is usually less time and thought devoted to the design of highway bridges, per dollar of expenditure, than there is to the design of railway structures. This is probably in part due to the lack of knowledge of the existence of these uncertainties, on the part of the public officials who have the design in charge, and in part to the more permanent and efficient organization in railway engineering departments.

73. Kinds of Bridges. The following points should be considered in selecting the type of bridge to be used in any particular case:

1. Use,
2. Location,
3. Permanence,
4. Strength and rigidity,
5. Economy,
6. Artistic effect.

Most specifications for highway bridges give a list of types recommended for use for various spans.[1] These recommended

[1] The "Standard Specifications of the State Highway Department of Ohio, for Steel Highway Bridges," are printed as an appendix to this book. See § 2.

See also "Standard Specifications," by John C. Ostrup, Art. 50.

See also "General Specifications for Steel Highway and Electric Railway Bridges," by Theo. Cooper, 1909, § 2.

types usually take into consideration only the questions of strength, rigidity and economy.

Any person having authority in the selection of a design for a bridge should give due consideration to harmony with the surroundings, and artistic effect. If the *location* warrants it an architect should be employed to *work in connection with* the engineer, not called in after the design is completed, simply to design some ornamental railings or crestings. A structure which will fit in with the surroundings and be pleasing to the eye will frequently cost no more than some uncouth structure which will forever be an eyesore.[1]

74. Flooring Materials. The ideal bridge floor should be such that in crossing the bridge one would be unconscious of a change. The same surfacing that is used on the roadways approaching the bridge should be continued across it if possible. This, of course, is not always practicable, but in any case the joint between the floor of the bridge and the approach should be so constructed that a rut will not form at this point.

The most common forms of flooring are:

Plank on wood or steel joists,
Creosoted wood block on creosoted plank,
Reinforced concrete, plain or with bituminous surface,
Macadam on reinforced concrete base,
Brick, asphalt or block paving on a reinforced concrete or buckled plate base.

Sufficient crown for drainage should be given to all water tight bridge floors and scuppers provided along the curbs to carry the water away, clear of the steel work.

With plank floors on steel joists, nailing strips should be provided for securing the planking to the joists. Sometimes spikes are driven through the plank and simply clinched over the edge of the I-beam joists, but this is a poor connection as the spikes soon rust and break off leaving the plank loose. Fig. 81 shows two methods of putting on the nailing strips. The placing of the nailing strips at the side of the joist is somewhat preferable as it is easier to maintain a true surface to the roadway when the plank rest directly on the steel joists. The

[1] See "Artistic Bridge Design," by H. G. Tyrrell and "Engineering Studies," by Charles Evan Fowler.

nailing strips should always be bolted to the steel joists at intervals not exceeding 4 feet.

Wheel guards should be provided at the sides of the roadway and should be hook-bolted to the outside line of joists.[1]

The creosoted plank base for a creosoted wood block floor is put down with nailing strips similar to any plank floor. Tar paper and hot tar are used between the plank and the wood block.[2]



FIG. 81.

The traffic should never be allowed to come directly upon a reinforced concrete slab floor, as it soon wears into ruts, making a rough roadway and also weakening the slab. The surface of the concrete is sometimes protected with a coating of tar and gravel. This coating will require renewing about once in two years under ordinary country traffic. The cost of the treatment is small and the concrete is very effectively protected.



FIG. 82.

For short span bridges in the country, a macadam covered roadway on a concrete base makes a very satisfactory floor.

Fig. 82 shows two types of paved roadways.

75. Loads. The selection of the proper live loads for which to figure highway bridges, and the assumptions as to their dis-

[1] See Cooper's "Specifications for Steel Highway Bridges," § 21.
See "Specifications of the State Highway Department of Ohio," § 40.

[2] See "Specifications of the State Highway Department of Ohio," §§ 22 to 36.

tribution, are perhaps the most difficult problems in the design. Bridges, even in the most remote country districts, must be designed to safely carry traction engines or road rollers. The proper weight of engine to use depends somewhat upon the topography of the country. Engines used in level countries may be considerably heavier than those used in hilly countries. The weight of the engine is usually considered as two thirds on the rear axle and one third on the front.

The loads given in most specifications[1] consist of a road roller for the floor system and members carrying floor loads directly, and a uniformly distributed load for the girders or trusses. It is usually not considered probable that more than one road roller or traction engine will be on the bridge at the same time and consequently the uniform loads for which trusses are designed usually diminish as the span increases.

When bridges carry electric cars in addition to the highway traffic, the loading used for the car track should be considered as acting simultaneously with any possible highway loading.

76. Impact. The moving loads are applied to the bridge with more or less impact[2] depending upon the character of the load and the smoothness of the floor. Prof. F. O. Dufour, in a paper entitled "Some Experiments on Highway Bridges under Moving Loads,"[3] read before the Western Society of Engineers, gives considerable data on the question of impact.

The heavier loads, such as road rollers and traction engines, are usually slow moving and consequently produce a less percentage of impact than the lighter loads, but the combined effect on the bridge (static load plus impact) is usually greater for the heavy loads. That is, the percentage to use for impact in connection with the usually specified loads, should be comparatively small. Prof. Dufour's conclusions point out this fact and state that with concrete floors on bridges the impacts observed were very small indeed, even when heavy loads were allowed to run over boulders as large "as two fists." On plank floor bridges the

[1] See Cooper's "Specifications," § 38.

See "Specifications of the State Highway Department of Ohio," §§ 43 to 48.

[2] See "Specifications of the State Highway Department of Ohio," § 50.

[3] Journal of the Western Society of Engineers, June, 1913.

impacts observed were very much higher than on concrete floor bridges, due to the lighter dead load, less rigidity and more uneven surface.

77. Distribution of the Load. The distribution of the load through the flooring materials is even more difficult of satisfactory solution than the selection of the proper loads to use or the treatment of impact.

Prof. Dufour found that with reinforced concrete floors, the joist immediately under the load did not carry more than 20% of the load, the balance being distributed to the other joists by the concrete slab. This distribution would be very much less with plank floors and would probably vary with the ratio of thickness of slab to distance between joists. Experiments by the State Highway Department of Ohio indicate that the maximum load carried by a joist never exceeds 50% of the wheel load, when the ratio of slab thickness to slab span is greater than one eighth and the slab is continuous over 6 or more lines of joists.

Cooper's specifications § 17, allows the joists of plank floor bridges to be figured for two thirds of the wheel load as long as the joists are not spaced more than two feet apart.

With wood block floors on plank it is safe to consider two thirds of the wheel load as going to one joist as long as the joists are spaced not over $2\frac{1}{2}$ feet centers.

78. Calculation of Joists. Investigation of existing structures will, in a majority of cases, show that the joists and floor beams are, relatively, the weakest points in the bridge. They should always be calculated to carry the specified roller load, and it should be borne in mind that they are the parts of the bridge which receive the greatest impact effect.

If the roadway is wide enough (more than 20 feet) the possibility of turning the roller on the bridge should be considered.

To illustrate the methods, the joists for an ordinary plank floor, country bridge, and for a paved floor city bridge will now be calculated.

For the plank floor bridge let us assume a 16 ft. clear roadway, a 19 ft. panel length and the specifications of the State Highway Department of Ohio, Class D loading. (See §§ 1 and 48.) The plank will be 3 inches thick and we will use 2 lines of channels and 5 lines of I-beams for joists, arranged as shown in Fig. 81.

This will make the joists about $2\frac{1}{2}$ ft. center to center. The dead load per joist will be as follows:

Plank 3 inch $=3\times2\frac{1}{2}\times4\frac{1}{2}$	$=33\frac{3}{4}$ lbs. per lin. ft.
Nailing strips $3\times6=1\frac{1}{2}\times4\frac{1}{2}=$	$6\frac{3}{4}$ lbs. per lin. ft.
Steel joists say	$=30$ lbs. per lin. ft.
Total dead load	$=70\frac{1}{2}$ lbs. per lin. ft.

$$\text{Dead load moment}=\frac{70\frac{1}{2}\times\overline{19}^2}{8}=3180 \text{ ft. lbs.}$$

The live load consists of ten tons on two axles ten feet centers. (See Spec. § 48.) Two thirds of this will be taken on the



FIG. 83.

rear axle and one third on the front. If we consider that only two thirds of this goes to one joist, we get a loading per joist as shown in Fig. 83. This loading gives a maximum live load moment in the joist of 24,060 ft. lbs.

The total moment for which to design the joist is

Dead load moment =	3,130 ft. lbs.
Live load moment =	24,060 ft. lbs.
Impact $\frac{100}{319}\times$L.L. =	7,550 ft. lbs.
Total =	34,790 ft. lbs.

$$\text{Required section modulus}=\frac{34790\times12}{16000}=26.1.$$

Use 10 inch I beams, 30 lbs. for the intermediate joists.

The outside joists are usually made of channels the same depth as the intermediate I beams. They do not carry as much load as the intermediate joists and therefore it is not customary to make any calculations for them. We will use 10 inch channels, 20 lbs. See specifications § 85.

For the city bridge let us assume a roadway wide enough so that a road roller could be easily turned on the bridge, a panel length of 19 ft. and Cooper's specifications, Class A_1 (see Spec. §§ 16, 23 to 29 and 38). The floor will be of 4 inch brick on a $1\frac{1}{2}$ inch sand cushion on an 8 inch reinforced concrete slab resting on steel joists spaced 5 ft. center to center. The general arrangement is as shown in Fig. 82.



FIG. 84.

The dead load per joist will be as follows:

Brick 4 inch	$=\frac{4}{12}\times150\times5=$	250 lbs. per lin. ft.
Sand $1\frac{1}{2}$ inch	$=\frac{1}{8}\times100\times5=$	62 lbs. per lin. ft.
Concrete 8 inch	$=\frac{2}{3}\times150\times5=$	500 lbs. per lin. ft.
Steel joist say	$=$	55 lbs. per lin. ft.
Total dead load	$=$	867 lbs. per lin. ft.

$$\text{Dead load moment} = \frac{867\times\overline{19}^2}{8} = 39{,}120 \text{ ft. lbs.}$$

The live load consists of 24 tons on two axles 10 ft. centers. Two thirds of this will be assumed on the rear axle and the spacing of the wheels on the axle will be assumed at 6 ft. center to center. When the roller is turned across the roadway and it is assumed that the concrete floor distributes the load over the joists so that not more than 50% goes to one joist, the loading per joist is as shown in Fig. 84.


D.L. = 36400#
L.L. = 45500#
I = 13900#
TOTAL = 93900#
D.L. = 54600#
L.L. = 78300#
I = 20800#
TOTAL = 153500#
2 I 8" x 13 1/2" 1 PL 12" x 7/8" = 12.58 sq in
2 I 8" x 13 1/2" 1 PL 12" x 7/8" = 11.83 sq in
D.L. = 27400#
L.L. = 34000#
I = 6900#
TOTAL = 68300#
D.L. = 13700#
L.L. = 17000#
I = 3500#
TOTAL = 34200#
D.L. = 0
L.L. = 11000#
I = 3500#
TOTAL = 14500#
2 I 6" x 6" x 7/8" Req. Net A = 9.58 sq in
2 I 6" x 6" x 7/8" Req. Net A = 7.34 sq in
2 I 4" x 3" x 5/8" Req. Net A = 2.94 sq in
2 I 6" x 5" x 7/8" Req. Net A = 8.58 sq in
2 I 6" x 5" x 7/8" Req. Net A = 6.80 sq in
2 I 6" x 5" x 7/8" Req. Net A = 2.94 sq in
D.L. = 18200#
L.L. = 22800#
I = 6000#
TOTAL = 47000#
D.L. = 45500#
L.L. = 57000#
I = 15000#
TOTAL = 117500#
D.L. = 54600
L.L. = 78300
I = 20600
TOTAL = 153500
5 Panels @ 16'-0" = 80'-0" c to c Roadway 18 Ft.
81'-0" Out to Out
STRESS DIAGRAM
ESTIMATED QUANTITIES
Steel . . . . . 54120 lbs.
Creosoted lumber . . . 5980 B.M.
Creosoted 3" block . . . . 153 sq yds.
SPECIFICATIONS
All workmanship and materials shall conform to "General Specifications for Steel Highway Bridges" of the State Highway Department of Ohio.
Approved James R. Marker
State Highway Commissioner
Adopted
Commissioners of
County, Ohio.
Floor System
Floor Beams 4-20" I's 65#
Joists { 6 lines of 12" I's 31 1/2#
2 lines of 12" @ 25# }
Clear Roadway
Note: All timber shall be creosoted.
Floor crowned 1"
Batter 3/4 in 12
Lacing
1/2" Pl
1'-0"
3/4" hook bolts 3'-0" c to c
4" x 6" Guard
2" x 6" x 1'-0" blocks 3'-0" c to c
3" x 6" side strip
3" block
3" plank
Nailing Strips
All laterals 1 L 3" x 2 1/2" x 1/4"
SECTION OF FLOOR
End Dam
11 Pl 10" x 7/16"
1 L 6" x 3 1/2" x 7/16"
Bent to fit crown
6" x 3 1/2" x 5/8" L
END OF FLOOR
Shoe Cover and Guard Angle riveted to Bed Plate
Shoe Cover 15" x 5/16" Bent Pl
1 L 2 1/2" x 2" x 1/4"
1 L 2 1/2" x 2" x 1/4"
Lattice 13" x 1/4" c
HIP JOINT
2-3/4" Plates
Splice Pl
SECTION AT FLOOR BEAM
SECTION OF END
STANDARD STEEL BRIDGE
WITH WOOD BLOCK FLOOR
SPAN 80 Ft. 18 Ft. ROADWAY
CLASS "C" LOADING
STATE HIGHWAY DEPARTMENT
COLUMBUS, O.
DEC. 1913
BUREAU OF BRIDGES

FIG. 85.

This loading gives a maximum live load moment in the joist of 41,260 ft. lbs. The total moment will be

$$41{,}260+39{,}120=80{,}380 \text{ ft. lbs.}$$



FIG. 86.

The required section modulus is $\dfrac{80380\times 12}{13000}=74.2.$

Use 18 inch I beams, 55 lbs. for the intermediate joists. The outside joists will have to be built up to form a curb as

shown in Fig. 82, or a concrete curb may be built resting on I beam joists.

79. Types of Steel Highway Bridges. The use of pony trusses for spans between 50 and 100 ft. is permissible in highway bridge work in locations where plate girders would be difficult of transportation or erection. Pony trusses can also be built at a slightly less total cost than equivalent plate girder bridges. Pony trusses should always be riveted structures and should have the top chord stayed by suitable knee braces at every panel point. Fig. 85 shows a design for a pony truss highway bridge with creosoted block or plank floor.

The plate girder bridge is the most desirable form of steel bridge for spans up to about 80 ft. on account of its rigidity and durability. On account of the necessity of shipping the mina girders in one piece it is not well adapted to some locations. Fig. 86 shows a design for a plate girder highway bridge with concrete floor. Note the absence of joists, the concrete slab being carried directly by the floor beams.

Fig. 87 shows a through riveted truss bridge with creosoted block floor.


Top Laterals all L 3½"×2½"×7/16"
STRESS DIAGRAM
8 Panels @ 18'-9" = 150'-0" c. to c.
151'-6" out to out
PORTAL
ESTIMATED QUANTITIES
Steel: . . . . . 126400#
Creosoted Lumber. : 10200' B.M.
Creosoted 3" block. . . 2525 sq yds.
SPECIFICATIONS
All workmanship and materials shall conform to "General Specifications for Steel Highway Bridges" of the State Highway Department of Ohio.
Approved James R. Masker
State Highway Commissioner
Adopted
Commissioners of
County, Ohio.
Intermediate Bracing
Note
All timber shall be creosoted
Floor crowned 1"
End Dam
Floor Beams 20" I 65#
Joists
Lateral Angle
Lattice
End Strut
END OF FLOOR
STANDARD STEEL BRIDGE
WITH WOOD BLOCK FLOOR
SPAN 150 FT. 16 FT. ROADWAY
CLASS "C" LOADING
STATE HIGHWAY DEPARTMENT
COLUMBUS, O.
DEC, 1913
BUREAU OF BRIDGES

FIG. 87.

CHAPTER VIII

MANUFACTURE AND ERECTION

80. Shop Operations. Before taking up the subject of shop drawings, we will consider, briefly, the method of proceedure in the shop work and the erection. This description will be general, as all classes of work are not handled alike and various plants differ somewhat in their equipment and methods.

When the shop drawings on a contract are complete, blue prints of them and the accompanying bills of material are sent to the various departments of the shop. In the *templet shop*, a wooden [1] templet is made for each constituent piece of each different member, excepting, of course, such parts as rods, eyebars, pins, rollers, etc. This templet is of the exact length (or half length) of the finished piece, gives bevels and has holes at every point where a rivet hole is to be located. It is to be clamped to the metal for the purpose of laying out the work to be done on each piece. Laying out directly upon the metal is seldom done because of the danger of making errors and ruining the steel for the purpose for which it was intended.

When the steel arrives from the mill it is unloaded at one end of the plant and marked with the contract number and sizes for future identification. Pieces of the same size are piled together and separated from other sizes as far as possible, so that any material can be gotten out easily at any time without handling other material which is not wanted. The unloading is usually done with a crane of some sort which deposits the material in the yard, or at some plants, in the shop.

When enough material on any contract has been received from the mill and that contract is reached on the shop program, the material is run into the shop as it is needed, and usually continues straight through to the opposite end of the plant where the finished product is loaded.

[1] Some shops are using paper maché for their large flat templets.

The first operation after the material is run into the shop is to *straighten* it so that the templet may be applied and that all pieces may be laid out accurately. This is done with presses, rolls and sledges. The next operation is *laying out*, that is, marking the lines on which the material is to be sheared, and with a center punch, which fits closely in the holes in the templet, the position of each rivet hole. Some material is sheared to length first and then laid out. From the shears or laying out skids, the material passes to the *punches* where all holes for rivets are punched. Next the various pieces which are to be riveted together are *assembled* and fitted, putting enough bolts through the rivet holes to hold the pieces in position until the riveting is completed. These bolts are taken out at the riveting machine as the riveting progresses. Before the pieces are assembled, such faces as will be inaccessible after riveting are painted, and before the riveting is done the holes are reamed out to correct inaccuracies in punching, or if *reaming* is required it is done at this time (10). Some pieces require planing, boring, chipping and hand riveting after the power riveting is done.

After all the operations have been performed on a piece, it is run on to a scale and *weighed* by the shipper, who makes out a shipping bill. Having been weighed and inspected to see that it conforms with the drawing it is *painted* and loaded upon cars or stored to go out when wanted.

All bending, forge work, upsetting, etc., are usually done in the blacksmith shop. Turning, planing (except rotary planing) and all machine work are done in the machine shop.

81. Erection. Putting up the work in the field may be a very simple operation or one involving the use of a large plant and considerable risk, depending upon the character of the structure and its location.

Bridges are usually erected on *false work*, which consists of wooden trestles, by means of a *traveler* or *gallows frame*, to which the tackle for hoisting all material into place is fastened. A *gallows frame* consists simply of two wooden posts connected together at their tops by a beam and braces. The posts usually rest upon temporary stringers outside of the line of the girders or trusses. A *traveler* has four legs, at least, braced together longitudinally and transversely, allowing room enough under it

to erect the bridge inside of it. It runs on wheels so that it may be moved lengthwise of the bridge as the erection progresses.

Generally during the erection of railroad bridges the traffic must not be interfered with, but trains usually reduce their speed and run slowly over a bridge which is being renewed. The floor system is sometimes put in place before the trusses and blocked up somewhat higher than its final position. The trusses are erected beginning at the center, putting up one half and then moving the traveler back to the center and working toward the other end. Enough bolts are put into the connections, which are to be riveted, to fill about two thirds of the holes. After everything is connected together, the bridge is "*swung*," that is, the blocking between it and the false work is taken out and it becomes self-supporting. Rivets for connections of tension members of trusses are driven before the bridge is swung and all others after it is swung.

In the designing and detailing of steel structures it is important that the manner of erecting them be constantly kept in mind. Field splices must be placed in the proper positions, connections should be designed with a view to facility in making them under the conditions which obtain in the field; field rivets should be located where they can be easily driven; sufficient clearance must be provided at all joints. All pieces should have plain marks for identification and a good erection diagram, showing all marks, should be made.[1]

82. The Drafting Department. The organization of the drafting department in various companies differs greatly. Usually there is a *chief draftsman* who has general supervision of all work and assigns the work to the various men under him, whom he deems best fitted to get out the drawings for it. Generally a contract is given to a *squad foreman*, who has three or four men working under him and who directs the method of getting out the work, writes the order bills for the material, and sometimes makes some of the more complicated drawings. When the drawings are made and traced they are sent to a "*checker*," who is generally an old experienced draftsman, and he checks

[1] For details of tools, tackle, traveler, false work, etc., see Chapter XIII in Du Bois' "Framed Structures," by John Sterling Deans, M. Am. Soc. C. E., and Appendix C in Johnson's "Modern Framed Structures." Eighth edition.

every dimension and size given on the drawing and marks such changes as are necessary, in pencil. The drawing is then corrected by the one who made it, and after being accepted and signed by the checker is ready to send to the blueprint room. The man who makes the drawing and the checker are held equally responsible for any errors.

Drawing boards should be used, as it is very inconvenient to have to remove a tracing from a table top in order to make a lay out or to work a short time on another drawing. The drawing boards should be of pine so made that they will not warp or split. They should have one true edge, preferably of hard wood, at the left hand end.

T-squares should have rigid heads and true edges.

The *drawing table* should be large enough to accommodate the drawing board, reference drawings, etc. It should be at least six feet long, and supplied with a drawer for instruments, etc. It should be, preferably, adjustable as to height and slope of top. The *stool* accompanying it should be adjustable for height.

The *lighting* of the drawing room should, of course, be the best possible. If artificial light is used at any time, it should be a diffused light reflected from the ceiling. A comparatively quiet, well ventilated, clean and orderly office will be conducive to good work and little friction. Unfortunately all of these reasonable conditions are not usually obtained.

A suitable *filing system* should be provided for all drawings and other data, preferably in a fireproof vault.

83. A Draftsman's Equipment. Shop drawings are the working drawings used in the shop and give all details. Making shop drawings is the foundation upon which a bridge engineer's future advancement is based. A draftsman makes his own reputation. Conditions have been such in the past that advancement comes to the draftsman about as rapidly as he is able to take advantage of his opportunities. One who makes himself thoroughly acquainted with the theory of everything he does, one who is not afraid of a little work outside of office hours, who carefully studies and considers every piece of work entrusted to him, will not find the work growing monotonous. A reputation for making mistakes is perhaps the worst a draftsman can make for himself. The fact that every drawing is checked should

have no influence upon the amount of care bestowed on it. Errors will sometimes pass the checker and are expensive in nearly all cases. Errors are especially liable to occur when changes are made necessary after a drawing is made, either before or after it is checked. For this reason a draftsman should do everything according to some method. There is a best place to begin on a structure and a most logical order in which to work it up, not only each drawing but every detail. If this is followed very little erasing will have to be done, and everything will be better designed than if one detail is worked out regardless of everything else and afterwards fudged to correspond with other requirements. After changes are made the drawing is usually out of scale, and not drawing to scale is usually conducive to mistakes. *Even rivet heads should be to scale.*

Every drafting room has some peculiar practices of its own, and it is generally the part of wisdom for a new-comer to conform with them as soon as he can find out what they are.

A draftsman's outfit should include the following *tools:*

1st. Triangles, ruling pen, compass, bow pen, bow pencil, dividers large and small, pen knife, pen wiper, scales, oil stone, etc.

2nd. A copy of some rolling-mill's handbook.

3rd. Tables of squares and logarithms of dimensions in feet, inches and fractions.

4th. A copy of the office standards.

5th. A five place table of the natural functions of angles varying by minutes.

6th. A five place logarithmic table of numbers and functions of angles.

7th. A slide rule.

8th. Reference books.

9th. The following which are usually supplied by the office: drawing tables, drawing boards, T-squares, erasers, soapstone, pencils, pens, tacks, tracing cloth, drawing paper, ink, and chalk.

The *drawing instruments* should be of the best quality. Loss of time due to poor instruments is inexcusable. *Triangles* should be transparent and not less than $\frac{1}{16}$ inch thick. A 5 in. or 6 in. 45 degree triangle and an 8 in. or 10 in. 30-60 degree triangle will be found convenient. For some classes of

work a quarter pitch triangle (slope 1 in 2) and a small triangle that will fit the standard bevel of the flanges of I beams and channels (1 in 6) will save time. The ruling pen should be of a kind that is easily cleaned because the ink used dries rapidly. There are pencil sharpening machines which do very good work. If there is not one conveniently located in the office, a sharp pen knife can be made to do good work in connection with a piece of sand paper or a file for sharpening the lead. A draftsman who wishes to make a workmanlike drawing will not work with a blunt pointed pencil.

The architects' scale is used for all shop drawings. This is a scale of feet and inches. Scales should not be over 6 inches long for detail work and preferably have white celluloid faces. A long scale necessitates moving the T-square and triangles too much. A 12 inch decimal scale for longer dimensions and graphic calculations should also be provided. A triangular architects' scale is usually divided into the following scales per foot: $\frac{3}{32}$ in., $\frac{1}{8}$ in., $\frac{3}{16}$ in., $\frac{1}{4}$ in., $\frac{3}{8}$ in., $\frac{1}{2}$ in., $\frac{3}{4}$ in., 1 in., $1\frac{1}{2}$ in., 3 in. and 12 in. or full size. As most of these scales are used infrequently, it is more convenient to have two flat scales covering the more often used scales. One divided into scales of $\frac{1}{8}$ in., $\frac{1}{4}$ in., $\frac{1}{2}$ in. and 1 in. per foot and another divided into $\frac{3}{8}$ in., $\frac{3}{4}$ in., $1\frac{1}{2}$ in. and 3 in. per foot will answer most purposes. A scale of $1\frac{1}{4}$ in. per foot makes a very nice scale for some classes of work but it is not a standard scale. The scale of $\frac{1}{4}$ in. per foot is much used by architects.

A good *pencil eraser*, one that will not " smear," is, of course, necessary. Ink on tracings should be erased with a *rubber ink eraser* although a steel eraser (knife) may be used occasionally. To prevent ink " running " and dirt accumulating on the spot which has been rubbed, the tracing cloth should be rubbed with soapstone. To confine the rubbed surface within the required limits, it is convenient to have a thin metal *erasing shield* with holes and slots of different sizes.

The *ink* should be waterproof india ink of good quality.

For drawing lines on detail paper a *6H* pencil should be used, because it does not require such frequent sharpening as a softer pencil. For putting in dimensions and figures a *4H* pencil will be about right. On tracing cloth a *3H* pencil will work best, and a soft pencil is needed for scratch figuring.

A pen must be "broken in" before good lettering can be done with it. After it has been used for some time the point becomes blunt and may be improved by using a knife on it as on a pencil in sharpening it.

The *rolling-mill hand books* contain much information of use to the draftsman, and he should know what may be found in them. The pages most frequently referred to should be indexed for quick reference in some manner similar to a ledger index. The principal shapes rolled by the various mills are all alike and in accordance with the standard adopted by the Manufacturers' Association. All properties of these shapes are given in the hand books. The American Bridge Company's Standards give much other valuable information.

Each office usually has a set of *standard tables* and drawings. Many of these are of general value, but some correspond with certain local shop practices.

Tables of squares and logarithms of dimensions in feet and inches are in constant use, and are a much greater help than would appear on first thought.[1] In working with right angle triangles, only the table of squares is necessary. The table of logarithms is not used so often, but when there is use for it it saves much time. These tables give results to the nearest 1-32 of an inch, and this is the smallest fraction ever used on structural steel drawings.

The above tables, together with a good table of the natural functions of angles such as is given in "Trautwine's Pocket-book," and a five place table of logarithms such as Gauss' or Jones' will enable the draftsman to solve all problems in mensuration which may arise, if he is thoroughly familiar with the fundamentals of geometry and trigonometry.

The draftsman should be familiar with the use of the *slide rule*, and should use it to calculate pins, rivets, bearings, etc. (5). If the office is provided with a *Thacher cylindrical rule* it may be used to good advantage in calculating the dimensions

[1] "Tables of Squares," by John L. Hall and "Buchanan's Tables of Squares," by E. E. Buchanan, give the squares of dimensions under 50 feet, expressed in feet and inches. Tables by Thos. W. Marshall give the logarithms of the same quantities. "Smoley's Tables of Squares and Logarithms," by Constantine Smoley, give both the squares and logarithms of these dimensions in parallel columns.

in oblique triangles, and will give results within $\frac{1}{32}$ of an inch so long as none of the lengths involved exceed about 30 feet.

A note book is very convenient for keeping calculations which one may wish to refer to again. Many figures which a draftsman makes will be on scratch paper, but all figures which may be needed for future reference and for consultation when the changes made by the checker are gone over, should be kept in a permanent and methodical form. A careful man will find satisfaction in seeing how he made a mistake, and this record will also be valuable in giving reasons for certain things he has done, and prevent his being misled by some one who, perhaps, has not considered all the conditions.

A draftsman should have at hand *reference books* in order that he may look up any point in theory with which he is not familiar. A few may be mentioned here but, of course, for structures out of the ordinary special works should be consulted. The most useful are:

Johnson's "Theory and Practice of Modern Framed Structures," Heller's "Stresses in Structures," some good work on the strength of materials, Wright's "The Designing of Draw Spans," Tyrrell's "Artistic Bridge Design," Merriman and Jacoby's "Bridge Design" (Part III of Roofs and Bridges), Kent's "Mechanical Engineer's Pocketbook," Trautwine's "Civil Engineer's Pocketbook," Engineering News, etc. Access to the Transactions of the American Society of Civil Engineers, and of other engineering societies will be valuable. An individual card index should be kept in order that any subject may be looked up when occasion requires.

84. Ordering Material. As soon as a contract has been secured and entered, complete data relating to the construction are turned over to the drafting department. The first thing to be done by this department is to prepare a list of the material required, which is called an "*order bill.*" The draftsman to whom this is entrusted should first carefully examine all data. If any necessary information is found lacking at any point in the progress of the work, it should be promptly reported. Care should be taken to include everything in the order bill that will be required to make the structure, unless upon inquiry it is found that certain materials may be ordered later.

Since the order bill must, in general, include all details such

as pin plates, batten plates, lacing bars, rollers, pins, eye bars, rods, timber, lead, corrugated iron, windows, doors, crane runway rails, etc., it is necessary to proportion all details, to calculate pins, rivets, bearings and connections, and to determine clearances, splices, etc. In some cases considerable drafting will be required, but not nearly so much as will be necessary to make complete detail drawings. In general, this preliminary drafting should be done so that after the order bill is complete the drawings may be developed into final shop drawings. This method will save much drafting, which is expensive work.

In order to expedite the placing of the orders for the material at the mills, no more drafting than necessary should be done. It may be supplemented by free hand sketches and notes, which should be preserved with other data for reference by the checker and draftsman making the shop drawings.

For a contract of any magnitude the order bills would be gotten out in sections; those parts which will be needed first should be gotten out first. In any case, the first attention should be given to the kind of material which will be most difficult to get promptly.

However, time spent upon a consideration of the entire contract in all its bearings, and especially with regard to duplication of parts, is never wasted.

The order bills are checked and a copy sent to the order department. The originals are retained for the guidance of the draftsmen who make the shop drawings. The element of time is so important that most companies do not make blue prints of the order bills, but use some more rapid duplicating process.

The order department makes up a "*mill order*" from the order bills, bringing together all items of the same kind and combining some of the shorter lengths into long lengths (multiple lengths) to be sheared to the proper lengths at the shop.

Some companies keep more or less material in *stock* in order to be able to make prompt deliveries of certain classes of work. In this way considerable waste (short pieces) accumulates, which must be applied on contracts whenever an opportunity offers. It is the duty of the order department to keep track of the stock, to keep up the supply of stock sizes, and not to allow an accumulation of waste. When stock material is applied to a contract it should be so marked, in order that it may be

reserved. The *shop bill* generally shows what items are to come from the mill and what items from stock. Stock material cannot always be used on contracts, as some specifications require a different quality of material from that carried in stock and require inspection at the mills.

The importance of avoiding *errors* and *omissions* in the order bills is apparent, since they may cause serious delay to the entire work.

In making up the order bill, it should be remembered that odd sizes of angles and other shapes should be avoided in order to get prompt delivery from the mill; $\frac{1}{4}$ inch extra material should be ordered for all tool finished (milled or planed) surfaces, except for the flat surfaces of plates for which $\frac{1}{16}$ in. or $\frac{1}{8}$ in. extra should be ordered, depending upon the size of the plate. Stiffener angles which are to be crimped or offset, are usually ordered as long as the depth back to back of angles of the girder to which they belong. The length of bent angles and plates is taken on the center of gravity line. Other material is ordered the exact length required (avoiding smaller fractions than eighths of an inch) and usually comes a little longer so that it may be sheared to the finished length.

Plates are of two kinds, "*sheared*" and "*universal mill.*" The former have sheared edges and the latter rolled edges. The maximum width of universal mill plates varies from 20 in. to 48 in., depending upon the mill where they are rolled. In the rolling mill hand books will be found tables showing the maximum length to which plates of various widths and thicknesses can be rolled. Plates up to 7 in. in width are called *bars*. Flange plates for plate girders are usually obtained as long as wanted, but web plates must be spliced. It is usual to order web plates of a width $\frac{1}{4}$ in. less than the depth back to back of angles, and to allow $\frac{1}{4}$ in. clearance between their ends. It is permissible to order odd shaped plates sheared to the dimensions wanted, as shown by a sketch.

Angles may be obtained in single pieces up to about 90 feet long, provided that they do not weigh more than about 3000 lbs. apiece. Special sizes should be avoided on account of slow delivery. The order bill should indicate the kind of material (soft or medium steel) and the specifications governing its quality and inspection.

85. Shop Drawings. Drawings should be made on the dull side of *tracing linen*, because they will not lie flat when made on the smooth side. An experienced draftsman will work directly on the tracing cloth and this cannot be done except on the dull side. Drawings may be fastened to the board with thumb tacks, but it will be found more satisfactory to use very small carpet tacks, tacking the four edges like a carpet so that the drawing will be stretched and present as smooth a surface as possible. Changes in temperature and moisture of the air may sometimes necessitate restretching. The drawing should be covered up at night with a heavy cloth or a piece of table oil cloth. If the drawing is made on the tracing linen direct, the principal lines may be inked before the drawing is completed in pencil. This will bring out the main parts and make it more satisfactory to work with, especially if there is much work on the drawing, as the lines are liable to become faint from rubbing over them. It is, however, safer for an inexperienced man to make a complete pencil drawing before doing any inking.

In order that the tracing cloth may "*take*" the ink it is necessary to rub it with pulverized chalk, fuller's earth, or blotting paper. This is especially necessary during cold and damp weather.

The draftsman should not get the idea that the *appearance* of a shop drawing is of no importance. A drawing should have a workmanlike appearance or it will not inspire confidence in its correctness. The general arrangement and the lettering are the main features so far as appearance is concerned. All *lettering* should be free hand and the draftsman should, at the beginning, practice with exceeding patience some simple style of lettering.

The style used in the drawings published in the Engineering News is a very good one to follow. A very important point is to have the letters and figures of different sizes, depending upon their importance. The sizes of materials should be more prominent than the rivet spacing, and center lengths than secondary dimensions. There is also a best position for each dimension. The letters and figures should be made as carefully as is consistent with rapidity. It is only practice, persistent and patient, that can make a good letterer. Not all can hope to become equally proficient, but all can *improve*.

The *general appearance* of a drawing depends very much upon the general arrangement, the scale, and the relative sizes of letters. A drawing may cover practically all the available space within the border lines, if there is no evidence of crowding anywhere, and if the various parts or pieces represented stand out clearly so that the different views of the several pieces can not be confused. There is an advantage in compactness, but *clearness is the first consideration.* Not every one who uses a drawing can read it as readily as the man who made it. **He should make it so plain that it will explain itself and that only gross negligence will allow anyone to make a mistake in using it.**

The object should be, not to make it " good enough " but to make it *first class.*

The length of a structure, like a truss, seldom determines the *scale* of the drawing. Usually the available width of a sheet determines the scale to be used. If the structure is too long to show on one sheet to this scale two or more sheets may be used. The center line diagrams of trusses are usually drawn to a smaller scale than the details, say $\frac{1}{2}$ in. or $\frac{3}{4}$ in. per foot while the details would be 1 in. or $1\frac{1}{2}$ in. per foot. In this case, of course, there is a part of the member near the middle which is cut out and which need not be shown, but the spacing of rivets, etc., is indicated. True projections are not always made if they do not serve to make matters clear. Bottom views are seldom made but sections instead, placed below the elevation. The top view should always be above the elevation. A half top view and half section are sometimes made together when symmetry will allow. A single view or two views will sometimes suffice, especially if it is a construction with which the shop is familiar. There should be no more drafting than is necessary for clearness.

Drawings should have one or two plain *border lines.* If two are used the blue prints may be trimmed to the outer one. (See Fig. 88.) In some drafting rooms an outfit for printing *titles* on tracings is used; in some rubber stamps are used. Printing is the most satisfactory method when the number of drawings turned out is large. Titles should correspond with some standard as indicated in Fig. 88. The title should, when possible, be in the lower right hand corner. When necessary it may be divided in two parts placed side by side. A supplementary


36"
35½
35"
THE OHIO STATE BRIDGE CO.
COLUMBUS, OHIO
Bridge No. 34 Western Div. Q.R.&M.Ry.
1 Through Truss Span - Double Track, Skew
126'-6" C. to C.
Floor Beams Stringers and Portals.
In Charge of Smith
Drawn by A.J.K. 7-1-07 Revised 8-6-07
Checked by J.M. 7-24-07 Revised 8-7-07
Shop Bills Nos. 1, 2, 3 & 4
CONT. NO. 746
2
24"
23½"
23"
(Trim Blue Print on this Line)
(Trim Tracing on this Line)

FIG. 88.


36"
35½"
35"
Specifications - Cooper's Ry. 1901.
Material Soft O.H. Steel.
Rivets ⅞" Holes 15/16" Unless otherwise noted.
Reaming - none.
Planing sheared edges - none.
Shop Paint - 1 Coat Red Lead.
23"
23½"
24"

FIG. 89.

form for general information is frequently placed in the lower left hand corner as shown in Fig. 89.

Dimension lines and rivet gage lines should be very fine and preferably made with black ink. They are sometimes made with red ink, but the ink should be of known quality in order that it may not run or spread with age. Center lines which form one end of a view should be heavy dot and dash lines; other center lines should be fine lines. No *shading* is attempted on shop drawings except to show curved surfaces.

All lines of dimensions should connect completely with the centers, and there should be separate lines for center distances, rivet spacing, lacing spacing, etc.

Rivets connecting lacing bars to compression members should stagger with those in the web of the member. The end bars should connect to the first rivet in the batten plate or one not over 5 in. from this rivet. Batten plates should be made of such widths as will fit the spacing of the lacing and meet the requirements of the specifications.

Dimensions which determine clearances for field connections, the position of open holes, etc., should be given in such a manner as to be convenient for the inspector. It should not be necessary for him to add rows of figures. If the inside distance at the end of a member is the important one for clearance, that should be given. If the member is to be entered inside of another, its outside width should be given. In some cases both are necessary. See Figs. 77 and 79.

For *identification* in the drawing room, shop and field, each piece should have a mark. All pieces which are *exactly* alike, should have the same mark. The marks should all appear on the general marking diagram, or erection plan, which shows the relative location of all the pieces by their marks.

Under the drawing of each piece the number required should be plainly given together with the numbers which are to be right and left, thus,

2 Right girders req. Mark G. R (shown).
2 Left girders req. Mark G L.

The system of marking, for each kind of structure, should be standard as far as possible. For example, U might always

stand for upper, L for lower, P for portal, V for vertical, D for diagonal, B for bracket, S for stringer, F for floor beam, etc. Marks should be as simple as possible, and preferably consist of capital letters and figures, avoiding primes and subscripts. To insure shipment, small pieces which the drawings show bolted to large ones, may be given separate marks and noted on the shipping bill.

Steel in *section* is shown by uniform cross hatching or in black. See Figs. 90, 92 and 93. Other kinds of material are seldom used except for draw-bridge machinery. If some convention is adopted for each kind of material, it will serve to make the drawing clearer.

It is well to follow some *conventions*. If a member is vertical in a structure, it should be drawn with its axis parallel with the sides of the drawing unless this would necessitate the use of too small a scale, in which case it may be drawn parallel with the top of the drawing, with the top of the piece at the right. Inclined members, when not shown in their natural position, should be drawn lengthwise of the sheet.

Notes may be used when they will save considerable drafting, but should generally be avoided. Making the drawing complete will guard against mistakes in the office and the shop. *A note should be so worded that its meaning cannot possibly be mistaken.* It is not permissible to refer to a reference; the drawing referred to should give full information. In any case each drawing should give sizes of all material, pin sizes, center dimensions, and other important information.

Duplication in details, in spacing, in parts of members and in members is very important. The number of templets is by this means reduced to a minimum. It is permissible to use a little extra material to obtain duplication in some cases. When two members differ but slightly from each other, one drawing, with proper notes, will answer for both. If two drawings are necessary and some parts of one are the same as for the other, it is better not to repeat the rivet spacing but to refer to the other drawing, as this will call attention to the fact that there is a duplication of templets. A templet is frequently made to answer for two different pieces by putting into it all the holes for each piece and marking one set of holes in some way to distinguish them from the other set.

Rivet spacing should be as regular as possible. All rivet heads need not be shown but they should not be omitted at the ends of members, where clearances are important, in pin plates, or where countersinking or flattening is needed. *Field holes* should always be shown blackened, and it is generally a good thing to show them in at least two views. The conventional signs for countersinking and flattening (see Fig. 24) should be made very plain lest they be confused with dimension lines. No countersinking is allowed in the tension flanges of stringers, floor beams or girders. All countersinking should be avoided in long pieces since it involves an extra shop operation and long pieces are expensive to handle.

All open holes should be so located that the field rivets may be easily driven. Rivets are driven from the sides or from above, never from below. It is not good practice to put two consecutive rivets on the same line in an angle having two gage lines, except for purposes of symmetry, and when it cannot be avoided, as in the connection of a floor beam to a girder.

Punching of holes of different sizes in the same piece should be avoided as much as possible, especially in long pieces, because it requires extra handling. Avoid two or more shearings at the end of an angle or the edge of a plate when one will answer just as well. Projecting corners should, however, not be allowed. Whenever a reentrant cut has to be made, there should be no sharp angle but a curve.

In giving dimensions over 9 inches the feet and inches should generally both be given, thus 0′ 11″, 3′ 7″. All dimensions over one foot, except the widths of plates, should be given in feet and inches; widths of plates are always given in inches, thus, 1 Pl. $37'' \times \frac{3}{8}'' \times 3'\ 6\frac{1}{2}''$. The longer leg of an angle should be given first. Rivet spacing should not be given by repeating a number of consecutive spaces that are just alike, but should be indicated as follows:

8 spaces at $3'' = 2'\ 0''$
8 alternate spaces at $1'\ 3'' = 10'\ 0''$.

Unless the stringers rest on the bottom flange of the floor beam, shelf angles should be provided for them to rest on for convenience in erecting. See Fig. 80. Where stringers rest on

the bottom flanges of the floor beams, and where inside splice angles are used, they should be ground to fit the fillet of the flange angle.

If angle laterals are used, which have lugs riveted to them, it is easiest to make the back of the angle the center line.

It should be remembered that angles are not exactly of the nominal size, but that the lengths of the legs overrun, except for sizes rolled in finishing rolls. Making fillers and splice plates $\frac{1}{4}$ inch shorter than the nominal distance between flange angles will not always answer.

Entering connections should be avoided. They make erection expensive and are liable to result in injury to the material.

Wherever two or more members come together, clearance should be allowed if possible. The thickness of an eye bar head, if figuring clearances, is always taken $\frac{1}{16}$ inch greater than the nominal thickness. A total further clearance of $\frac{1}{4}$ inch to $\frac{3}{8}$ inch is allowed where several members enter between the sides of another, the amount depending upon the members so entering, the number of pin plates, etc. Pin fillers are, for the same reason, made $\frac{1}{4}$ inch shorter than the space they are to fill.

Projecting plates should not be riveted to large pieces, but shipped loose. It is better to drive a few more rivets in the field than to have these details broken off in shipping and handling, or have them interfere with the handling of heavy pieces. Lateral plates for plate girder spans may be riveted to one of the laterals connecting to them if the laterals are not too long.

Care should be exercised so that no part of the lateral system will interfere with the floor construction or the masonry.

It is important to know in what order the spans of a viaduct will be erected and to arrange the details at the tops of the columns so that each span may be put up independently.

Holes for anchor bolts must be so located that the masonry may be drilled after the steel work is in place.

At panel points, not only those rivets which come opposite a member in its final position should be flattened or countersunk for clearance, but also enough to allow the members to be easily assembled. Batten plates should not come too close to a diagonal member.

Top chord splices should come opposite each other in the two trusses, and the sections nearest the center should extend

over at least two panel points so that in erection this panel will be self-supporting. It should be remembered that the traveler must be moved and cannot generally support pieces except for about one panel length.

There are two general methods of making shop drawings. *First*, a structure or part of a structure may be drawn showing all parts assembled in their proper relative positions. A bridge, for example, may be drawn showing the truss members (usually half of one truss for a square span) in the relative positions in which they belong, while a separate drawing is made of each of the other pieces such as floor beams, portals, etc. This method, of course, is not adapted to some structures, like floors and columns of office buildings. *Second*, each kind of piece belonging to a structure is drawn separately and complete in itself. In the case of a truss for example, this necessitates the making of a layout of each joint beforehand, in order to determine clearances, and the fitting together of the parts. This method requires more drafting than the first, and is therefore more expensive. The first method is nearly always used for bridge and roof trusses unless the depth is so great that it would necessitate too small a scale.

At some plants the templet shop is arranged to permit laying out a structure full size. The templet maker locates the rivets which are shown but not exactly located on the drawing. Where this is practiced drawings are made in a somewhat different manner, as to what dimensions are given, than where all details including rivet spacing are shown.

The beginner should always have a sample of the kind of structure of which he is required to make a drawing, for a guide. There are many practical points which can only be picked up in this way. He should also make himself familiar with the machines in the shop and their capacities. It is sometimes as easy to design a masonry plate which will go into the planer as one that is too wide for it.

Before starting on the drawings for any particular structure, a draftsman should make himself perfectly familiar with all the data. Time spent in a general preliminary consideration and plan of action is generally well spent. If further information is required, it should be asked for *at once*. If a mistake or omission is discovered in the order bill, the attention of the

engineer in charge of the office, or of this particular contract, should be called to it *at once.*

Working to the order bill may make some trouble, but this is necessary. Should any doubtful points come up, some one should be consulted who is more familiar with this kind of work, or with the requirements of the parties for whom the work is to be built. *A man should never be ashamed to ask intelligent questions.*

86. Order of Procedure for a Pin Connected Bridge. No definite order of procedure can be outlined, which can be followed in all cases, but the following order for a pin connected truss bridge will serve as a guide to the beginner.

The stress sheet and specifications form a part of the contract and the draftsman must work from these.

1st. Write on a blueprint of the stress sheet the horizontal and vertical components of the stresses in the inclined members.

2nd. Determine the location of the centers of gravity of the compression members and decide on the location of the center lines. (70.)

3rd. Determine all the center lengths so as to give the required camber. (68.)

4th. Make a table of heights as follows:

Depth of tie over the stringers	=
Depth of the stringers	=
Bottom of stringer to bot. of fl. bm.	=
Bottom of floor bm. to pin cent.	=
Base of rail to pin cent.	= (Sum)
Pin cent. to masonry	=
Base of rail to masonry	= (Sum)
Lower pin cent. to base of rail	=
Required clearance	=
Lower pin cent. to clearance	= (Sum)
Depth of truss c. to c. pins	=
Depth of portal, vert. from p. c.	= (Dif.)

5th. If the bridge is on a skew, calculate the lengths and bevels necessary to draw the portal.

6th. Calculate the size of masonry plate required so as not to exceed the allowed pressure on the masonry and so as to provide enough room for the rollers.

7th. Assume sizes of pins, determine thicknesses of pin bearings on each member and calculate the pins. When the pins are all calculated decide upon two or three sizes for the truss, making some larger than necessary for the sake of simplicity. Fix on the location and thicknesses of all pin plates and the number of rivets required in each. The calculation of the pins will have determined the packing at each panel point. (67.)

8th. Calculate the pitch of rivets required in the flanges of the stringers and floor beams and the number of shop and field rivets for their end connections. (This information is frequently given on the stress sheet.) (8) (41.)

9th. Calculate the rivets required in the lateral systems, including portals, to take the longitudinal and transverse components of the stresses as required.

While performing the above preliminary work, a few sketches will be necessary, and it is important to decide upon the form of the connections for the lower lateral system, allowing clearances for eye bar heads, and to see that the steel work will fit the masonry, allowing sufficient clearance at the ends for expansion.

No rigid rule can be laid down for the best order in which the different parts should be drawn up, but for this class of structure the following will work out satisfactorily:

The scale for the center line diagram is usually $\frac{3}{8}$ inch, $\frac{1}{2}$ inch or $\frac{3}{4}$ inch per foot, and for the details, $\frac{3}{4}$ inch, 1 inch, $1\frac{1}{4}$ inch or $1\frac{1}{2}$ inch per foot. The 1 inch scale is used more than any other one for details.

1st. Draw the portal, especially if it is a skew bridge. A layout of the hip joint will be necessary.

2nd. Work out the hip joint with portal connection, lateral connection, pin plates, etc.

3rd. Work out the shoe joint with rollers, anchor bolts, masonry plates, shoes, end strut or beam and lateral connections, pin plates, etc.

4th. Work up the spacing of the lattice bars, batten plates and rivets in the end posts.

5th. Work up the lower chord joints, with floor beam connections, beginning at the middle of the truss and working toward the end.

6th. Finish the hip vertical.

7th. Draw the top chord joints, and fix spacing for lattice bars, batten plates and rivets in top chords.

8th. Finish the intermediate posts.

9th. Finish the top view of top chords.

10th. Draw top lateral system and top struts.

11th. Draw bottom lateral system and end struts.

12th. Draw stringers and beams.

13th. See that each drawing has a proper title and number, and that all general notes required are on the drawings.

14th. Go over each drawing to see that all information which may be wanted by the following persons, is given: The checker, the templet maker, the layer-out, the fitter-up, the inspector, the shipper, and the erector. See that each piece is properly marked and the number wanted is given, that the sizes of rivets and open holes are all given.

15th. Make a marking or erection diagram (single line) and a diagram showing how the bridge is to be located on the masonry.

16th. After the drawings are checked, look into all corrections carefully before doing any erasing. *Do not erase the checker's marks.* In case you do not understand the checker's changes or see any reason for them, ask him for information. The important thing is to have the drawing clear and correct.

Riveted truss bridges can be handled in much the same way as pin connected bridges. The scale for the truss drawing is usually somewhat smaller than for the details. Great care should be exercised in order that connections may be as free from eccentricity and as compact as possible. (20) It is important to so space rivets that the net section of any member will not be less than was contemplated in the design. (19) When a connection is too complicated to exactly proportion the rivets, assumptions should be made which will be on the safe side.

87. Order of Procedure for a Plate Girder Bridge. The method of procedure for a plate girder bridge may be outlined as follows: The scale of the drawing of the girder should be $\frac{3}{4}$ inch, 1 inch or $1\frac{1}{4}$ inch per foot. Two or more sheets may be

used for long girders. For a skew bridge the full length of one girder must be drawn. The girder should be drawn first, but it will be necessary to sketch the lateral and beam connections before it can be completed. The first thing to be considered is the location of the splices in the web. The hand books give the maximum lengths obtainable for plates of different widths and thicknesses. Web plates up to about 96 inches wide may be obtained longer than convenient for handling in the shop. Their length should be limited to from 20 to 25 feet, except for girders less than 30 feet long whose webs may be made without a splice.

The pitch of the rivets in the flanges should be determined and regular groups of spacing be decided on, as for example, $2\frac{1}{4}$ inch, $2\frac{1}{2}$ inch, 3 inch, $4\frac{1}{2}$ inch and 6 inch. Now the splices may be located. If it is a deck girder, they should be so located that there will be no odd spaces, if possible, in the groups decided on. Stiffeners are always placed on the splice plates. The intermediate stiffeners need not be spaced so exactly equal but that they may come on one of the rivets previously located, except where the pitch in the flanges is less than 3 inches, in which case a space of at least 3 inches will generally be required on each side of the stiffener. If the girder is for a through bridge, the splices will usually be located at the panel points, from which everything else must be located. Through girders often have their top flanges bent to a quadrant at the upper corners, and extend down the ends of the girder. This necessitates splices in the top flange near the bend so that long pieces will not have to be bent. All splices in a flange should break joints.

In general no countersinking is allowed in girders except in the shoe plates. When the rivets in the horizontal leg of a flange angle stagger with those in the vertical leg, some of the former will interfere with the outstanding legs of the stiffeners. To avoid this, special spacing may be introduced near the stiffener or the stiffeners notched as shown in Fig. 90. In unusual cases it may also be desirable to notch the other leg of the stiffener to clear a rivet.

The horizontal legs of the flange angles are usually as wide or wider than the vertical legs. When the vertical leg is 5 inches or over, two rows of rivets are used in it. The practice with regard to the horizontal leg differs. The simplest way is to have

also two lines of rivets in each horizontal leg, putting those of the inner row in one leg opposite those of the outer row in the other leg. This, however, gives more rivets than necessary through the flange plates. If only one row of rivets is used in each horizontal leg, they should stagger with those in the vertical legs. If two rows are used in each leg the spacing in the horizontal legs may be increased to one and one half or two times that in the vertical leg. For example, where the spacing in the vertical leg is $2\frac{1}{4}$ inches, 3 inches and $4\frac{1}{2}$ inches, that in the



FIG. 90.



FIG. 91.



FIG. 92.



FIG. 93.

horizontal legs might be $4\frac{1}{2}$ inches, $4\frac{1}{2}$ inches and 6 inches, or $4\frac{1}{2}$ inches, 6 inches and 6 inches. When the spacing in one leg is 3 inches, for instance, and that in the other is $4\frac{1}{2}$ inches, the rivets on the inner row of the $4\frac{1}{2}$ inch spacing will stagger with those in the other leg, while those in the outer row will come opposite. Three lines of rivets are sometimes used in 7 inch and 8 inch legs of angles.

The minimum pitch (13) of rivets depends upon the distance between rivet lines and the gage of the latter, and is influenced by clearance for the riveting tool. In Fig. 91 "g" depends upon

the thickness of the angle. For large angles, therefore, there are usually two standard gages. In crimped stiffeners the distance "*a*" Fig. 92 should not be less than 2 inches. Stiffeners should be placed with the backs of the angles toward the ends of the girder. Flange rivets should not be located closer to stiffeners than shown in Fig. 93. This allows room enough for the regular die of the riveting machine.

Even if fillers are not required under stiffeners, it is best to use them at points where beams or frames connect and at the splice plates. Connections for beams and frames should, if possible, be made in such a manner that they may be swung into position without striking the rivet heads in the flanges of the girders.

For girder bridges on a grade, the girders should, if possible, be made so that they will fit if turned end for end. The bevel should be in the masonry plates and not in the shoe plates.

88. Shop Bills. Shop bills are lists of material for use in the shop. They are made on sheets $8\frac{1}{2}\times11$ inches or $8\frac{1}{2}\times14$ inches. The forms used by different companies differ somewhat, but the essential features are as follows:

They should be numbered consecutively, and should show the number of the drawing to which they refer. Each finished piece should be billed separately, and the number to be shipped should appear in the first column. In the second column should be given the number of constituent parts required to make the number of members shown in the first column. The main parts of members should be given first, the details following, putting the lacing last. Shop rivets are not billed.

The size of each part, the name or location, or both, and its length, must be given. Both the finished length and the ordered length should be given in separate columns. In the "remarks" column it is usually indicated whether or not a piece is to come from the mill or from stock. Blacksmith work, machine work, and riveted work are usually put on separate bills. Blank forms are sometimes used for pins, bars, field rivets, etc. Be sure that nothing is omitted, as it might seriously delay erection.

A *check list* for various kinds of structures should be prepared, giving all possible items to ship, similar to the "Order of Estimating" given in Art. 6. By consulting these, omissions may be avoided.

It is usually required to send drawings to the shop or to have them printed for approval, as soon as they are finished. If they are sent for approval it may be better and more convenient not to make the bills until the prints are returned approved, as there may be some changes. Five or six sets of prints are required for the shop. Sending out drawings before all parts of the structure are drawn up is not the most logical thing to do, but is often necessary.

A simple form of shop bill is shown in Fig. 94. The fol-

FORM No. –

Sheet No. 25 Cont. No. 243

THE OHIO STATE BRIDGE COMPANY

Trusses Span No. 3 Date 9-3-04

Bridge No. 16 Q.R.&M. Ry. Drawing No. 14

Ship	No. Pcs.	Kind	SIZE	Wt. P. Ft.	DESCRIPTION	Finished Length	Ordered Length	REMARKS
4	Interm.		Top Chord	Sec.	CD - R&L			
	4	PL	25" × 3/8"		Cover Pl.	21'-9 15/16"	21'-9 1/2"	Carnegie
	8	Ls	3 1/2" × 3 1/2" × 3/8"	8.5	Top Ls	21'-9 15/16"	21'-9 1/2"	"
	8	Ls	" × " × 5/8"	13.7	Bot. Ls	21'-9 15/16"	21'-9 1/2"	"
	8	PL	16" × 3/8"		Webs	21'-9 15/16"	21'-9 1/2"	"
	8	PL	9" × 3/8"		Web splice	1'-0"	12'-0"	M.L. "
	4	PL	"		Cover "	2'-1"	12'-0"	M.L. "
	4	PL	15" × 3/8"		Batten Pls.	2'-0 3/4"	8'-4"	M.L. "
	88	PL	2 1/4" × 3/8"		Lattice 15 5/8" 15 5/8"			Stock
2	Interm.		Top Chord	Sec.	DD			
	2	PL	25" × 3/8"		Cover Pl.	24'-9 15/16"	24'-9 1/2"	Carnegie

FIG. 94.

lowing information should also be put on a bill sheet and sent with the shop bills:

Contract No.	Ship to
Description	Shop Paint
Location	Field Paint
Date to Ship	Lumber furnished by
Inspected by	Penalty
Erected by	

In general, the drawings should show everything complete,

but the drawings of the forge work, machine shop work, and miscellaneous details are often made on bill sheets.

89. Shipment. Field splices and connections are often determined by the limitations of transportation facilities. These should be determined at the outset. Some routes can take care of pieces of greater extreme dimensions than others. Tunnels often limit the width of the loading and overhead bridges, the height. Sharp curves have an important bearing on loading long pieces, especially girders. It should be remembered that a piece extending over two or more cars, swings away from the center line of the track on a curve, requiring more clearance than on a straight track, and that a car on a curve is inclined toward the inside of the curve. Ordinarily, pieces about 10 feet high can be transported on the railroads, but the width at the top is usually limited to about 6 feet. The greatest width of a steel car is 10 feet 2 inches. Pieces 10 feet or more in width can be transported if they are not too high or too long. The question of weight is not generally an important one, except that cars of proper capacity must be used so that no truck will be overloaded. It is allowable to put two thirds of the nominal capacity of a car on one truck.

For *export* shipment special instruction must be obtained on each job as to maximum lengths, weights, etc. Pieces for export work must, in some cases, be so small that they can be transported on pack animals. A thorough and simple system of marking is necessary. Instead of marks, colors are sometimes used.

The question of cost of freight is sometimes an important one, and may determine the maximum length of a piece. If the total weight of a contract is less than a car load, so far as cost of transportation is concerned, no piece should be longer than a car length.

There are two kinds of *freight rates*, "car load" and "less than car load" (C. L. and L. C. L.), the latter being the higher. The minimum car load is generally 30,000 lbs.; the minimum for two cars is 40,000 lbs.; and 20,000 lbs. is added for each additional car. Therefore if any piece extends from one car over part of another, freight must be paid on at least 40,000 lbs., no matter how much less the shipment weighs. In case of a girder extending over three cars, the minimum amount charged would be on 60,000 lbs.

90. Materials. The materials used by the structural engineer are wrought steel, wrought iron, cast steel, cast iron and timber. *Cast steel* and *cast iron* are used for the machinery of draw bridges. Except in special cases of columns for buildings, and pedestals, and for small details like washers, ornaments and separators, *cast iron has passed out of use entirely* in structural work. *Cast steel* is sometimes used for shoes of bridges.

Timber is used for the compression members in combination bridges and roof trusses, and for the floors of bridges.

Wrought iron is used for rods which must be welded,—rods with loop eyes, or forked heads. In the best classes of work welds are entirely avoided. Welds in steel are not considered reliable.

The qualities of the materials required are given in the specifications governing the work. We shall consider structural steel more in detail.

At present *three kinds of steel* are commonly specified, viz., "rivet steel," "soft steel" and "medium steel." Of these, rivet steel is the softest and medium steel the hardest, or the steel of greatest ultimate strength. "Hard steel," or steel having an ultimate strength greater than 70,000 lbs. per sq. in., is seldom used for bridges or buildings.

There is at present a movement toward the adoption of a single grade of steel for all structural purposes.[1] This would simplify the steel maker's work, and no doubt result in a more uniform and a cheaper product.

The quality of steel is determined by analysis and test. There is considerable uniformity in the requirements of various specifications. These may be enumerated as follows:

Chemical Requirements. Percentage of phosphorus, sulphur, manganese, silicon, carbon, copper and arsenic.

Physical Requirements. Process of manufacture, uniformity, finish, heat treatment, ultimate strength, elastic limit, elongation, reduction of area at point of fracture, appearance of fracture, bending, bending after quenching, punching, drifting of punched holes, variation of cross section and full sized tests.

Chemical analysis determines the amounts of the impurities in steel. All elements except iron and carbon may be called impurities. Since it is practically impossible to eliminate all

[1] See Bulletin No. 62 American Railway Engineering and Maintenance of Way Association.

the phosphorus and sulphur, a small percentage of manganese is considered advantageous. In order to meet the physical requirements the manufacturer must limit the amount of all impurities, and of the carbon. All specifications, however, limit the amount of phosphorus allowed, since this element renders the steel brittle or " cold short " while it, at the same time, hardens it. Some specifications also specify maximum allowable percentages of sulphur, manganese and silicon. The maximum allowable amount of phosphorus in steel depends upon its mode of manufacture. It is usually about 0.04% for basic open hearth steel and 0.08% for acid open hearth and Bessemer steels.

Carbon has the greatest influence upon the ultimate strength or hardness of steel. Phosphorus, manganese and sulphur make steel harder and also reduce its ductility.

Basic open hearth steel will, in general, have about the following ultimate strengths, depending upon the percentage of carbon:

55,000 lbs. per sq. in. with 0.10% carbon.
60,000 lbs. per sq. in. with 0.15% carbon.
65,000 lbs. per sq. in. with 0.20% carbon.
70,000 lbs. per sq. in. with 0.25% carbon.

The elastic limit will be about 0.6 of the ultimate tensile strength.

There is no rigid line separating the different grades of steel, but steel having less than 0.15% carbon is generally soft steel, and with more than 0.30% carbon, hard steel, the intermediate grade being medium steel. These grades are usually defined by their ultimate strength.

Process of Manufacture. Steel is made by the Bessemer or open hearth process. Open hearth steel is now used for all important bridge and building work. It is almost invariably required when a regular specification governs the work.

Bessemer steel is not so uniform in quality as open hearth steel and is, therefore, not so reliable a material. It is made in a converter, by blowing a blast of air through molten pig iron until the carbon and silicon are all burnt out. Ferro-manganese is then added to recarbonize the metal the required amount and to absorb the excess of oxygen, which would make the steel " rotten." From the converter the metal is poured into a ladle

and then into moulds. Here the metal is allowed to solidify, producing ingots. The ingots are reheated and then rolled into slabs, blooms and billets of various sizes, depending upon the final form into which they are to be rolled.

Open hearth (Siemens-Martin) steel is made in an open hearth furnace and is of two kinds, acid and basic. The use of the latter predominates.

Acid steel is made in a furnace having a lining of a refractory silicious material which has an acid reaction. Basic steel is made in a furnace having a lining of magnesite or dolomite, which has a basic reaction. The raw material in either case is pig iron, now usually charged in a molten state. If the pig iron contains larger percentages of phosphorus and sulphur than are allowed in the steel, these must be reduced. Since they have a great affinity for iron, some reagent must be introduced in the molten metal which has a greater affinity for them. For this purpose a basic material must be used, since they form acids when oxidized. The material employed is lime charged in the form of limestone. This cannot be used in an acid lined furnace because it would form a flux with the lining. In the acid process, therefore, the percentages of phosphorus and sulphur in the raw material must not much exceed what is allowed in the finished product. This process requires a better grade of pig iron than the basic process.

In the open hearth *basic process*, large quantities of oxide of iron in the form of iron ore or mill scale, are charged into the furnace, together with limestone and molten pig iron. The lime which is formed, combines with part of the phosphorus and sulphur, reducing the percentages of these to minute quantities, while the oxide of iron serves to burn out the carbon, manganese and silicon. The desired amounts of carbon and manganese are then added. As in the Bessemer process, the steel is made into ingots, billets and slabs, and is finally rolled into the desired shapes.

Upon the care with which all of these processes are carried out depends the uniformity and finish of the rolled steel, as well as its quality to some extent. Lack of uniformity may be due to unequal heat treatment, unequal working or to segregation in the ingot, producing a steel of variable composition. If a piece of steel is not uniformly treated and cooled there may be internal

stresses in it, hence it is required that pieces which are heated in working as eye bars, for example, must be annealed. The hotter a piece of steel is heated, the coarser grained it will be and the more rapidly it is cooled, the harder it will be. Rolling and hammering steel increases its density and strength, but working it at a blue heat may crush the grain, which is very injurious. Rough iron cracks are indications of " red shortness " or burning. Other surface defects are easily discovered on close inspection. Defects due to bad heat treatment, improper working, excess of impurities, etc., are discovered by chemical analysis and physical tests. Tests are made of material from each heat, melt or blow.

Specifications allow a range of 8000 to 10,000 lbs. per sq. in. in the ultimate tensile strength of any particular grade of steel, but they do not all agree as to the limits. Depending upon the specifications, soft steel may include steel having an ultimate strength as low as 52,000 lbs. per sq. in. and as high as 62,000 lbs. per sq. in., medium steel as low as 60,000 and as high as 70,000 lbs. per sq. in., and rivet steel from 48,000 to 58,000 lbs. per sq. in.

The ultimate strength, elastic limit, elongation and reduction of area are determined from test pieces cut from the finished material. It is usually required that the elastic limit must not be less than one half of the ultimate strength. As it is not difficult to obtain an elastic limit equal to 0.6 of the ultimate strength it would be well to specify, as is sometimes done, a minimum for the elastic limit. Thus, if the ultimate may vary from 60,000 to 68,000 lbs. per sq. in., the minimum elastic limit might be fixed at 32,000 lbs., for example, and then steel having a greater ultimate than 64,000 lbs., would have to have an elastic limit of at least one half the ultimate. In this case the unit stresses could be based upon an elastic limit of 32,000 lbs.

In commercial testing, the elastic limit is determined by the drop of the beam of the testing machine, that is, it is really the yield point.[1]

It is important that steel be ductile and not brittle. For determining ductility, the tension piece is measured after rupture to determine the stretch in an original length of eight inches, and the reduction of area at the point of fracture. The determination of the latter is not important and is usually omitted.

[1] See Heller's " Stresses in Structures," Art. 21.

In a general way, the elongation in eight inches is about 30% for good steel having an ultimate strength of 56,000 lbs., per sq. in., and 25% for 65,000 lb. steel. This is for standard test specimens having an area of cross section of not less than $\frac{1}{2}$ sq. in. The usual requirements are 25% for soft steel and 22% for medium. Pin material is only required to have an elongation of 16% or 17%, and eye bars, when tested *full size*, 10% in the body of the bar.

The percentage of reduction of area is about 1.8 to 1.9 times that of the elongation.

The *appearance of the surface of the fracture* is always noted in testing steel. If it shows defects such as blisters, cinders, spots, cracks or lack of uniformity of color, it is not a desirable product. The fracture of good material is described as "silky," and has a "uniform, fine grained, structure of blue steel gray color, entirely free from fiery 'luster' or a 'blackish' cast." If the fracture is granular and has a "fiery" luster it indicates over heating. If the fracture is dull or "sandy," the steel is impure, or worked cold, and should be rejected.

The *bending test* requires that the test piece shall bend cold without sign of fracture. For soft steel it must bend flat on itself, and for medium steel, to a curve whose diameter is from one to three times the thickness of the piece tested. Some specifications require this bending test to be made upon pieces which have been heated and quenched in water.

A *punching test* is sometimes specified. This requires that the walls between the punched holes shall not break down except when they are less than $\frac{1}{4}$ inch thick.

The *drifting test* requires that the ductility of the metal must be such that a punched hole will stand drifting until its diameter is increased from $33\frac{1}{3}$ to 100% without cracking the edges.

Pieces of large cross section are apt to be "piped," that is, they are not solid. This is due to bad working or unequal cooling, and occurs particularly in pins. It is usually specified that the larger sizes of pins (say over $4\frac{1}{2}$ inches) must be forged from blooms having a sectional area of about three times the area of the pin, in order that the material may be sufficiently worked to make it sound.

Full sized tests are usually confined to eye bars. Some

reductions in requirements of ultimate strength and elongation are made from those required for small test pieces, because pieces of large cross section do not test as high as those of small cross section.

91. Inspection. If an inspector is employed on a contract, his duties may relate to material, shop work and erection. On some classes of work the purchaser employs no inspector. The manufacturer has all work inspected as to dimensions, to avoid trouble in erection. In some cases reports of tests of material are furnished by the rolling mill, which conducts a testing department for this and other purposes.

An inspector is most frequently employed to make tests of the steel, at the mill, as it is rolled. The shop work is also inspected for the best classes of work, but in comparatively few cases is the field work inspected by a regular inspector. The large railway companies have inspectors in the mills, the shop, and the field.

The inspection of material includes tests, analyses, surface inspection, measuring sizes, etc., of steel, lumber, paint, etc. A shop inspector should see that no material is injuriously treated, that reaming of rivet holes is properly done, that all parts are made in accordance with the drawings, that rivets are good and tight, that members are straight, that no work is ragged or unfinished, that painting is done in accordance with the specifications, and should make reports of progress.

The field inspector should see that no part of the structure is injuriously treated, that no members are interchanged, that all field driven rivets are good, and that the painting is properly done.

Rare qualifications are required for a good inspector. He must serve his employer honestly and avoid friction with the contractor.

GENERAL SPECIFICATIONS

FOR

STEEL HIGHWAY BRIDGES

1911

OHIO STATE HIGHWAY DEPARTMENT

COLUMBUS, OHIO

SPECIFICATIONS FOR BRIDGE SUPERSTRUCTURES.

GENERAL

Classification.

1. All bridges under these specifications will be divided into four classes: (45 to 48)

Class A—Bridges for city traffic.

Class B—Bridges for suburban or interurban traffic with heavy electric cars.

Class C—Bridges for country roads with light electric cars or heavy highway traffic.

Class D—Bridges for country roads with ordinary highway traffic.

Type.

2. The following types of bridges are recommended:

For spans up to 6 *ft.*, concrete, stone or pipe culverts.

For spans from 6 *ft. to* 15 *ft.*, reinforced concrete slabs, reinforced concrete beams with slab floor, rolled steel beams cased in concrete with slab floor, or rolled steel beams with plank floor.

For spans 15 *ft., to* 25 *ft.*, reinforced concrete beams with slab floor, rolled steel beams cased in concrete with slab floor, or steel beams with plank floor.

For spans from 25 *ft. to* 40 *ft.*, steel plate girder bridges.

For spans from 40 *ft. to* 80 *ft.*, steel plate girders, or riveted truss bridges.

For spans from 80 *ft. to* 120 *ft.*, riveted truss bridges.

For spans over 120 *ft.*, riveted or pin-connected truss bridges.

Span.

3. In calculating the stresses, the length of span shall be understood to be the distance between centers of end pins for trusses, center to center of trusses for cross floor beams, centers of bearings for all longitudinal beams and girders, and the width of clear opening plus the depth of slab, for reinforced concrete slabs.

Clearances.

4. All through bridges carrying electric cars, shall have a clear headroom above top of rail, of at least 15 ft., for a width of 6 ft., over the center of the track. Where the track is straight there shall be a clear width of at least $6\frac{1}{2}$ feet on each side of the center line of track at a height of 1 ft., above the top of rail. Where the tracks are curved, the additional clearance shall be

computed by assuming the extreme length of car as 45 feet, width 8 ft. and distance between centers of trucks 20 ft.

5. For bridges without electric cars, the clear head room above the floor shall be at least 12½ ft. and preferably 15 ft.

Roadway.

6. The clear width of roadway shall in no case be less than 16 ft., and for bridges carrying electric cars there shall be a clear width of at least 12 ft. from the center line of track on one side of the track.

General Proportions.

7. The width center to center of girders or trusses shall in no case be less than one-twentieth of the effective span. The depths of trusses or girders shall preferably not be less than the following:

For rolled beams, one-twentieth (1-20) the span,
For plate girders, one-twelfth (1-12) the span,
For riveted trusses, one-tenth (1-10) the span,
For pin-connected trusses, one-eighth (1-8) the span,

In truss bridges the inclination of the diagonals with the vertical shall be preferably less than 45°.

Foot Walks.

8. Where foot walks are required, they will generally be placed outside of the trusses or girders and supported on over-hanging brackets.

Railings.

9. A handrailing 3½ ft. high shall be placed on each side of the bridge except where plate girders serve the same purpose. Where the handrailing is of rolled steel or cast iron it shall be of pleasing design and shall be rigidly attached to the superstructure.

Trestles.

10. Where trestles are used, each trestle bent shall, as a general rule, be composed of two supporting columns, and the bents united in pairs to form towers; each tower thus formed of four columns shall be thoroughly braced in both directions, and have struts between the feet of columns. (53) (108)

Trestle towers.

11. Each tower shall have sufficient base, longitudinally to be stable when standing alone without other support than its anchorage. (108)

12. Tower spans for high trestles shall not be less than 30 feet.

Approaches.

13. All floor timbers, rails, guards and handrailings shall extend over all piers and abutments and shall make suitable connection with the embankments at either end of the structure.

Approval of plans.

14. The contractor shall not, except at his own risk, order any material, or commence any work until after the shop drawings have been approved by the State Highway Commissioner or his Deputy. After approval, the contractor shall furnish the State Highway Department and the County Surveyor, without charge, with as many sets of the shop drawings as they may require.

15. The contractor shall check all leading dimensions and clearances as a whole and in detail, the fitting of all details, and become responsible for the exact position and elevation of all parts of the work; and the approval of the working drawings shall not relieve the contractor of this responsibilit

Anchor bolts.

16. The contractor for the metal work shall furnish the requisite anchor bolts to the sub-structure contractor with a masonry plan showing their location, in time that they may be built into the masonry.

Name plates.

17. One or more cast iron name plates of an approved design, giving the date of construction, the names of the County Commissioners, the County Surveyor, the State Highway Commissioner, the Contractor for the Superstructure and the Contractor for the Substructure, shall be securely bolted to the superstructure at the point or points specified.

FLOORING MATERIALS

Paved floors.

18. Pavements consisting of stone blocks, paving bricks, asphalt, etc., may rest on a reinforced concrete slab, or on a concrete bed resting on buckled plates as directed by the Highway Department.

Buckled plates.

19. When buckled plates are used they shall not be less than 5-16 inches thick and the concrete bed shall not be less than 3 inches thick for the roadway and 2 inches thick for the foot walks over the highest point. The buckled plates shall be placed with the buckle down and each buckle shall be provided with a drain hole. (128) (129)

Pavements.

20. When asphalt, brick or stone pavements are used, they shall be put down according to the specifications of the State Highway Department.

Scuppers.

21. Scuppers must be provided at frequent intervals along the curbs or wheel guards for drainage and for passing the sweepings and snow, clear from contact with any parts of the trusses or floor system.

Wood block.

22. Creosoted wood block pavements may be laid on a concrete base or on creosoted plank as directed by the Highway Department.

Sand cushion.

23. When a concrete bed is used, the wood blocks shall be laid on a one-inch sand cushion.

Sub-floor.

24. When a creosoted plank sub-floor is used under a wood block pavement, the planks shall be laid tight and coated with a layer of paving pitch, or coal tar known as Distillate No. 4, heated to 240° Fahr. Upon the hot tar shall be laid one layer of three-ply tarred roofing felt of a quality acceptable to the engineer. Another coating of hot tar shall be applied on top of the paper and the blocks laid in this coating while it is hot.

Laying.

25. The blocks shall be laid with the grain vertical in courses transversely of the roadway. They shall be laid to break joints at least three inches in consecutive courses.

Filler.

26. After the blocks are laid the joints shall be filled with coal tar, Distillate No. 6, heated to 320° Fahr. and thoroughly broomed into all joints while hot and then the whole pavement covered with a ¼ inch layer of clean coarse sand.

Timber.

27. The paving blocks shall be yellow pine 90% heart, sawed into rectangular blocks 3 inches thick, 6 to 10 inches long of the depth shown on the plans.

28. All other creosoted timber must be good long leaf yellow pine, free from large loose or rotten knots, must be sawed true and out of wind, and must be free from wind-shakes or other defects which would injure its quality.

Treatment.

29. When creosoted timber is specified, it must be sized and cut to the dimensions given on the plans before the creosoting is done.

30. The timber and paving blocks to be treated shall first be subjected to a steaming and vacuum drying process to remove the water and sap and to open the pores of the wood, after which they shall be impregnated with creosote oil as specified below.

Steaming and drying.

31. The timber and blocks shall be placed in the steaming cylinder and a 30-lb. steam pressure shall be applied and maintained in the cylinder for 4 hours, during which time the temperature must be maintained above 250° Fahr. After the steaming it shall be allowed to cool down for one hour.

Vacuum.

32. The material shall then be put under a vacuum of 24 inches or less and subjected to a temperature of 240° Fahr., until moisture and gases cease to come from the cylinder.

Application of oil.

33. At the end of the drying, the creosote oil shall be admitted to the cylinder while the timber is still under the vacuum, and a pressure of 100 lbs., per sq. in. shall be applied and maintained until the required amount of oil has been forced into the timber and blocks. The oil shall be at a temperature of 200° Fahr., when admitted to the cylinder and so maintained throughout the time of impregnation.

Oil.

34. The creosote oil shall be a dead oil of coal tar, commonly known as creosote, and shall have a specific gravity of not less than 1.02 or more than 1.10 at 68° Fahr. It shall at no time contain more than 2% of water, and if at any time water in excess of this amount is found in the oil, operations shall cease until the surplus water has been removed by distillation or otherwise.

Amount of oil.

35. The timber and blocks shall receive not less than 16 lbs. of oil per cu. ft.

Tests.

36. The quantity of oil forced into the timber shall be determined by weighing marked pieces selected as representing the average green timber before the charge is dried and finally reweighing them after the application of the oil. From these weights the average amount of oil used in the whole cylinder load shall be determined.

Plank floor.

37. For bridges with a plank floor the plank shall not be less than $2\frac{1}{2}$ inches thick, laid with $\frac{1}{4}$ inch openings and spiked to each supporting joist, if wood joists are used, or to 3 inch nailing strips securely bolted to the steel joists. When this is covered with an additional wearing floor (38) it must be laid diagonally with $\frac{1}{2}$-inch openings; all planks shall be laid with the heart side down. The floor plank must have a thickness in inches at least equal to the distance apart of the joists in feet. The floor planks must bear firmly upon all joists.

Wearing surface.

38. Where specified, an additional wearing floor $1\frac{1}{2}$ inches thick of white oak plank shall be placed over the above. (37)

Walks.

39. The foot-walk plank will be 2 inches thick and not over 6 inches wide, spaced with $\frac{1}{2}$-inch openings.

Guards.

40. There will be a wheel guard not less than 4 in. $\times$ 6 in. on each side of the roadway to prevent the hubs of wheels from striking any part of the bridge. It shall be blocked up from the floor to admit drainage and cir-

culation of air and shall be secured by $\frac{3}{4}$ in. hook bolts with washers under the nuts, to the steel joist, or if wood joists are used, by $\frac{3}{4}$ in. lag screws with washers, at intervals of not over 4 ft.

Wood joists.

41. When wood joists are used they will lap by each other so as to have full bearing on the floor beams, except the outside lines under the wheel guards, which must be butted over the floor beams. Their scantling will vary in accordance with the length of panels selected, but shall not be less than 3 inches or one-fourth of depth in width. When joists are spaced not over $2\frac{1}{2}$ feet centers, one joist shall be considered as carrying only two-thirds of the concentrated live load. (49)

Timber.

42. The timber, unless otherwise specified, shall be strictly first class spruce, white pine, southern yellow pine, or white oak bridge timber, sawed true and out of wind, full size, free from wind shakes, large or loose knots, decayed or sap wood, worm holes, or other defects impairing its strength or durability. It will be subject to the inspection and acceptance of the Engineer.

LOADS

43. All parts of the structure shall be proportioned for the maximum stresses produced by the dead load, temperature, wind, traction and by any one of the live loads given below as specified. (1)

Dead load.

44. The dead load shall comprise the actual weight of the completed structure. The dead load used in figuring stresses must not vary more than 5% from the actual estimated weight made from the completed design. In estimating the dead load the following unit weights shall be used:

Timber untreated	$4\frac{1}{2}$ lbs. per ft. B. M.
Timber creosoted -	5 lbs. per ft. B. M.
Concrete plain - -	140 lbs. per cu. ft.
Concrete reinforced	150 lbs. per cu. ft.
Asphalt - - -	155 lbs. per cu. ft.
Brick - - -	150 lbs. per cu. ft.
Macadam - - -	100 lbs. per cu. ft.

City bridges.

45. *Class A. City Bridges.* For the floor and its supports, on each street car track or on any part of the roadway, a concentrated load of 24 tons on two axles 10 ft. centers and 6 ft. center to center of wheels, with $\frac{2}{3}$ of the load on one axle (assumed to occupy an area 12 ft. $\times$ 20 ft) and upon the remaining portion of the floor including foot walks, 100 lbs. per sq. ft.

For the trusses for spans up to 100 ft., 1800 lbs. per lineal ft. of each car track (assumed to occupy 12 ft. in width) and 100 lbs. per sq. ft. on the remaining floor surface, with a minimum live load of 2200 lbs., per lineal

ft. of bridge; for spans of 200 ft. and over, 1200 lbs. for each lineal ft. of track and 80 lbs. per sq. ft. of floor, with a minimum live load of 1600 lbs. per lineal foot of bridge; proportionally for intermediate spans.

Suburban and interurban bridges.

46. *Class B. Suburban and Interurban Bridges.* For the floor, and its supports, on any part of the roadway a concentrated load of 15 tons on two axles 10 ft. centers and 6 ft. center to center of wheels, with $\frac{2}{3}$ of the load on one axle (assumed to occupy an area of 12 ft. $\times$ 20 ft.) and on each street car track a concentrated load of 24 tons on two axles 10 ft. centers with $\frac{2}{3}$ of the load on one axle, and upon the remaining portion of the floor including footwalks 100 lbs. per sq. ft.

For the trusses of spans up to 100 ft., 1800 lbs., per lineal ft. of each car track and 80 lbs. per sq. ft. of the remaining floor surface, with a minimum live load of 2000 lbs. per lin. ft. of bridge; for spans of 200 ft. and over, 1200 lbs. per lineal ft. of each car track and 60 lbs. per sq. ft. of the remaining floor surface with a minimum live load of 1500 lbs. per lineal foot of bridge; proportionally for intermediate spans.

Heavy country bridges.

47. *Class C. Heavy Country Bridges.* For the floor and its supports, on any part of the roadway, a concentrated load of 15 tons on two axles 10 ft. centers and 6 ft. center to center of wheels with $\frac{2}{3}$ of the load on one axle, and on each street car track a concentrated load of 24 tons on two axles 10 ft. centers, with $\frac{2}{3}$ of the load on one axle, and upon the foot walks 100 lbs. per sq. ft.

For the trusses of a span up to 100 ft. 1200 lbs. per lineal ft. of each car track and 80 lbs. per sq. ft. of the remaining floor surface with a minimum live load of 1600 lbs. per lineal foot of bridge; for spans of 200 ft. and over, 1000 lbs. per lineal ft. of each car track and 60 lbs. per sq. ft. of remaining floor surface, with a minimum live load of 1200 lbs. per lineal ft. of bridge; proportionally for intermediate spans.

Country bridges.

48. *Class D. Ordinary Country Bridges.* For the floor and its supports on any part of the roadway a concentrated load of 10 tons on two axles 10 ft. centers and 6 ft. center to center of wheels with $\frac{2}{3}$ of the load on one axle.

For the trusses of spans up to 100 ft. 80 lbs. per sq. ft. of floor surface with a minimum live load of 1200 lbs. per lineal ft. of bridge; for spans of 200 ft. and over, 60 lbs. per sq. ft. of floor surface, with a minimum live load of 1000 lbs. per lineal ft. of bridge; proportionally for intermediate spans.

Distribution.

49. Concentrated loads applied through paving or macadam may be assumed to be distributed at an angle of 30° with the vertical. Street car rails may be assumed to distribute their loads over three ties. The width of tires on the wheels in the above loadings may be assumed at as many inches as the load on two axles is in tons. Isolated loads on concrete slabs

may be assumed to be distributed over a width equal to twice the depth of the slab, in excess of the actual width of the load on top of the slab. (41)

Impact.

50. To compensate for the effect of impact and vibration the dynamic increment of the live load shall be added to the maximum computed live load stresses and shall be computed by the following formula:

$I = S\left(\frac{100}{300+L}\right)$ in which

I = the dynamic increment

S = the maximum computed static live load stress

L = the length of load necessary to produce the maximum static stress.

Swing bridges.

51. For swing bridges and other movable structures the dead load stresses during motion shall be increased 25% as a dynamic increment.

Wind loads.

52. To provide for wind and vibrations, the top lateral bracing in deck bridges, and the bottom lateral bracing in through bridges, shall be proportioned to resist a lateral force of 300 pounds for each lineal foot of the span; 150 pounds of this to be treated as a moving load. (111)

The bottom lateral bracing in deck bridges, and the top lateral bracing in through bridges shall be proportioned to resist a lateral force of 150 pounds for each lineal foot. (111)

For spans exceeding 300 feet, add in each of the above cases 10 pounds additional for each additional 30 feet.

53. In trestle towers the bracing and columns shall be proportioned to resist the following lateral forces, in addition to the stresses from dead and live loads:

On the trusses loaded or unloaded the lateral pressures specified above; and a lateral pressure of 100 pounds for each vertical foot of the trestle bents.

Temperature.

54. In steel structures variation in temperature to the extent of 150 degrees Fahr. shall be provided for.

Centrifugal force.

55. For electric railways on curves the additional effects due to the centrifugal force of cars single or coupled shall be considered as a live load. It will be assumed to act 5 feet above base of rail, and will be computed for a speed of $60—2\frac{1}{2}D$ miles per hour, where D = degree of curve.

Traction.

56. The stresses produced in the bracing of the trestle towers, in any members of the trusses, or in the attachments of the girders or trusses to

their bearings, by suddenly stopping the maximum electric car trains on any part of the work must be provided for; the coefficient of friction of the wheels on the rails being assumed as 0.20.

UNIT STRESSES AND PROPORTION OF PARTS

57. All parts of structures shall be so proportioned that the sum of the maximum stresses produced by the foregoing loads shall not exceed the following amounts in pounds per sq. in. except as modified in paragraphs 66 to 70:

Steel tension.

58. *Axial tension* on net section 16,000

Compression.

59. *Axial compression* on gross section of columns ..... $16{,}000\text{-}70\frac{L}{r}$

With a maximum of 14,000

Where L is the length of the member in inches and r is the least radius of gyration in inches.

Bending.

60. *Bending:* on extreme fibers of rolled shapes, built sections, girders and steel castings; net section 16,000

On extreme fibers of pins 24,000

On extreme fibers of timber, yellow pine or white oak 1,800

White pine or spruce 1,500

Shearing.

61. *Shearing:* shop driven rivets and pins 12,000

Field driven rivets and turned bolts 10,000

Plate girder webs; gross section 10,000

Bearing.

62. *Bearing:* shop driven rivets and pins 24,000

Field driven rivets and turned bolts 20,000

Expansion rollers; per lineal inch ..... $600d$

Where d is the diameter of the roller in inches.

On masonry 600

Concrete.

63. Unit stresses for concrete and reinforced concrete, see General Specifications for Concrete and Reinforced Concrete Structures of the State Highway Department.

Limiting lengths.

64. The unsupported lengths of main compression members shall not exceed 120 times their least radius of gyration, and those for wind and sway bracing 140 times their least radius of gyration.

65. The lengths of riveted tension members in horizontal or inclined positions shall not exceed 200 times their radius of gyration about the horizontal axis. The horizontal projection of the unsupported portion of the member is to be considered as the effective length.

Alternate stresses.

66. Members subject to alternate stresses of tension and compression shall be proportioned for the stresses giving the largest section. If the alternate stresses occur in succession during the passage of one series of loads, as in stiff counters, each stress shall be increased by 50% of the smaller. This increased stress shall be used in proportioning the connections.

Counters.

67. Wherever the live and dead load stresses are of opposite character, only two-thirds of the dead load stress shall be considered as effective in counteracting the live load stress.

68. For bridges carrying electric or motor cars counters shall be provided and proportioned so that a future increase of 25% in the specified live load shall not in any case increase the allowed unit stress more than 25 per cent.

Combined stresses.

69. Members subject to both axial and bending stresses shall be proportioned so that the combined fiber stresses will not exceed the allowed axial stress. (93) (112)

Wind stresses.

70. For stresses produced by longitudinal and lateral or wind forces combined with those from live and dead loads and centrifugal force, the unit stress may be increased 25 per cent over those given above; but the section shall not be less than required for live and dead loads and centrifugal force. (52) (53)

Net section at rivets.

71. In proportioning tension members the diameter of the rivet holes shall be taken 1-8 in. larger than the nominal diameter of the rivet.

72. In proportioning rivets the nominal diameter of the rivet shall be used.

Net section at pins.

73. Pin-connected riveted tension members shall have a net section through the pin-hole at least 25% in excess of the net section of the body of the member, and the net section back of the pin-hole, parallel with the axis of the member, shall not be less than the net section of the body of the member.

Rolled beams.

74. Rolled beams shall be proportioned by their moments of inertia.

Plate girders.

75. Plate girders shall be proportioned either by the moment of inertia of their net section; or by assuming that the flanges are concentrated at their centers of gravity; in which case one-eighth of the gross section of the web, if properly spliced, may be used as flange section. The thickness of web plates shall not be less than 1/240 of the unsupported distance between flange angles.

76. The gross section of the compression flanges of plate girders shall not be less than the gross section of the tension flanges, nor shall the stress per sq. in. in the compression flange of any beam or girder exceed $16{,}000 - 200\left(\frac{L}{b}\right)$, where L is the unsupported length and b the width of the flange.

Flange rivets.

77. The flanges of plate girders shall be connected to the web with a sufficient number of rivets to transfer the total shear at any point in a distance equal to the effective depth of the girder at that point, combined with any load that is applied directly to the flange.

DETAILS OF DESIGN

78. All parts shall be so designed that the stresses coming upon them can be accurately calculated.

Camber.

79. All truss bridges shall be cambered an amount equal to one-six hundredth (1/600) of the span, and plate girders one-twelve hundredth (1/1200) of the span unless otherwise specified.

Open sections.

80. Structures shall be so designed that all parts will be accessible for inspection, cleaning and painting.

Pockets.

81. Pockets or depressions which would hold water shall have drain holes, or be filled with water-proof material.

Symmetry.

82. Main members shall be so designed that the center of gravity will be as nearly as practicable in the center of the section, and the centers of gravity of intersecting main members of trusses shall meet at a common point.

Counters.

83. Rigid counters are preferred; and where subject to reversal of stress shall preferably have riveted connections to the chords. Adjustable counters shall have open turnbuckles.

Connections.

84. The strength of connections shall be sufficient to develop the full strength of the member, even though the computed stress is less, the kind of stress to which the member is subjected being considered.

Minimum thickness.

85. For main members and their connections no material shall be used of a less thickness than 5/16 of an inch; and for laterals and their connections, no material less than $\frac{1}{4}$ of an inch in thickness; except for lining or filling vacant spaces. No bars shall be used with a net area less than $\frac{3}{4}$ of one square inch. (93)

Riveting.

86. The pitch of rivets in all classes of work shall never exceed six inches, or sixteen times the thinnest outside plate, nor be less than three diameters of the rivet.

87. The minimum distance from the center of any rivet hole to a sheared edge shall be $1\frac{1}{2}$ in. for $\frac{7}{8}$ in. rivets and $1\frac{1}{4}$ in. for $\frac{3}{4}$ in. rivets, and to a rolled edge $1\frac{1}{4}$ in. and $1\frac{1}{8}$ in. respectively. The maximum distance from any edge shall be eight times the thickness of the plate, but shall not exceed 6 in.

88. The rivets used shall generally be $\frac{7}{8}$ and $\frac{3}{4}$ inch for the main members and the floor system.

Long rivets.

89. Rivets carrying calculated stress and whose grip exceeds four diameters shall be increased in number at least one per cent for each additional 1/16 in. of grip.

Indirect connection.

90. Rivets carrying stress where the parts connected are not in direct contact, shall be increased in number over the number theoretically required, 25% for each intervening plate.

Bolts.

91. When members are connected by bolts the holes must be reamed parallel and the bolts turned to a driving fit. All bolts must be of neat lengths, and shall have a washer under the heads and nuts where in contact with wood. Bolts must not be used in place of rivets, except by special permission. All nuts must be of hexagonal shape.

92. The pitch of rivets at the ends of built compression members shall not exceed four diameters of the rivets, for a length equal to one and one half times the maximum width of member.

Compression members.

93. In compression members the metal shall be concentrated as much as possible in the webs and flanges. The thickness of each web shall not be less than one-thirtieth (1/30) of the distance between its connections to the flanges. Cover plates shall have a thickness not less than one forty-

eighth (1/48) of the distance between rivet lines and they shall not be thicker than $\frac{3}{8}$ inch except when necessary to resist bending stresses or to comply with the above requirement. (85)

Tie plates.

94. The open sides of compression members shall be provided with lattice and shall have tie plates as near each end as practicable. Tie plates shall be provided at intermediate points where the lattice is interrupted. In main members the end tie plates shall have a length not less than the distance between the lines of rivets connecting them to the flanges, and intermediate ones a length not less than one-half this distance. Their thickness shall not be less than one-forty-eighth of the same distance.

Lattice.

95. The latticing of compression members shall be proportioned to transmit in a distance equal to one-fourth ($\frac{1}{4}$) the length of the column, the allowance for flexure provided in the column formula of paragraph 59 by the term $70\frac{L}{r}$, and also any shear due to transverse loading. The thickness shall not be less than one-fortieth (1/40) of the distance between rivets for single lattice or one sixtieth for double lattice with riveted intersections. The minimum widths of bars shall be $1\frac{3}{4}$ inches or one-sixth (1/6) the greater width of the members. Lattice bars with at least two rivets in each end shall be used for flanges 5 inches and over in width.

96. The inclination of lattice bars with the axis of the member shall not be less than 45 degrees, and when the distance between rivet lines in the flanges is more than 15 in., if single rivet bars are used, the lattice shall be double and riveted at the intersections.

97. Lattice bars shall be so spaced that the portion of the flange included between their connections shall be as strong as the member as a whole.

Faced joints.

98. Abutting joints in compression members when faced for bearing shall be spliced on four sides sufficiently to hold the connecting members accurately in place. All other joints in riveted work, whether in tension or compression, shall be fully spliced.

Pin plates.

99. Where necessary, pin-holes shall be reinforced by plates, some of which must be the full width of the member so the allowed pressure on the pins shall not be exceeded, and so the stresses shall be properly distributed over the full cross-section of the members. These reinforcing plates must contain enough rivets to transfer their proportion of the bearing pressure, and at least one plate on each side shall extend not less than six inches beyond the edge of the batten plates.

100. Where the ends of compression members are forked to connect to the pins, the aggregate compressive strength of these forked ends must equal the compressive strength of the body of the members.

Pins.

101. Pins shall be long enough to insure a full bearing on all the parts connected upon the turned body of the pin. They shall be secured by chambered nuts or be provided with washers if solid nuts are used. The screw ends shall be long enough to admit of burring the threads.

102. Members packed on pins shall be held against lateral movement.

Expansion.

103. Provision for expansion to the extent of $\frac{1}{8}$ inch for each 10 ft., shall be made for all steel structures. Efficient means shall be provided to prevent excessive motion at any one point.

End bearings.

104. All bridges over 100 feet span shall have hinged bolsters on both ends, and at one end nests of turned friction rollers or rockers running between planed surfaces. These rollers shall not be less than $3\frac{3}{8}$ inches in diameter for spans of 100 feet or less, and for greater spans this diameter shall be increased in proportion of 1 inch for each 100 feet additional. The rollers and bearings must be so arranged that they can be readily cleaned and so that they will not hold water.

105. Bridges less than 100 feet span shall be secured at one end to the masonry, and the other end shall be free to move longitudinally upon smooth surfaces. (160)

106. Where two spans rest upon the same masonry, a continuous plate, not less than $\frac{3}{8}$ inch thick, shall extend under the two adjacent bearings, or the two bearings must be rigidly tied together.

Wall plates.

107. Wall plates may be cast or built up; and shall be so designed as to distribute the load uniformly over the entire bearing. They shall be secured against displacement.

Anchors.

108. Anchor bolts for viaduct towers and similar structures shall be long enough to engage a mass of masonry the weight of which is at least one and one-half times the uplift. (53)

109. Bridges on an inclined grade without pin shoes shall have the sole plates beveled so that the masonry and expansion surfaces may be level.

Floor beams.

110. Floor beams shall preferably be square to the trusses or girders. They shall be riveted directly to the girders or trusses or may be placed on top of deck bridges.

Bracing.

111. Lateral, longitudinal and transverse bracing in all structures shall preferably be composed of rigid members.

112. All through bridges shall have latticed portals, of approved design, at each end of the span, connected rigidly to the end posts and top chords.

They shall be as deep as the specified head-room will allow and provision shall be made in the end posts for the bending stresses from wind pressure. (93) (95)

113. When the height of the trusses exceeds 20 ft. an approved system of overhead diagonal bracing shall be attached to each post and to the top lateral struts.

114. Knee braces shall be placed at each intermediate panel point, and connected to the vertical posts and top lateral struts, for trusses 20 feet and less in depth.

115. Pony trusses and through plate or lattice girders shall be stayed by knee braces or gusset plates attached to the top chords at the ends and at intermediate points, and attached below to the cross floor beams or to the transverse struts.

116. All deck girders shall have transverse braces at the ends. All deck bridges shall have transverse bracing at each panel point. This bracing shall be proportioned to resist the unequal loading of the trusses.

Diaphragms.

117. At all points where floor beams, portals or other bracing connect with the posts of chords, proper diaphragms must be inserted to distribute the loads and forces over the full section of these posts or chords.

118. All members of the web, lateral, longitudinal or sway systems must be securely fastened at their intersections to prevent sagging and rattling.

Flange plates.

119. Where flange plates are used, one cover plate of the top flange shall extend the whole length of the girder.

Stiffeners.

120. There shall be web stiffeners, generally in pairs, over bearings, at points of concentrated loading, and at other points where the thickness of the web is less than one-sixtieth (1/60) of the clear distance between the flange angles. The distance between the stiffeners shall not exceed the clear distance between flange angles or a maximum of six feet.

121. Stiffeners at the ends and at points of concentrated loading shall be proportioned by the formula of paragraph 59, the effective length being assumed as one-half the depth of the girders. End stiffeners and those under concentrated loads shall be on fillers and have their outstanding legs as wide as the flange angles will allow and shall fit tightly against them. Intermediate stiffeners may be offset or on fillers and their outstanding legs shall not be less than 1/40 the depth of the girders plus 2 inches.

122. The webs of plate girders must be spliced at all joints by plates on each side of the web. The splice must be proportioned to transmit the resultant of the shear and the portion of the bending moment taken by the web.

Flange plates.

123. In girders with flange plates, at least one-half of the flange section shall be angles or else the largest sized angles must be used. Flange plates must extend beyond their theoretical length two rows of rivets at each end

Lattice trusses.

124. In lattice girders and trusses the web members must be double. and connect symmetrically to the webs of the chords. The use of plates or flats alone, for tension members must be avoided where it is possible; in lattice trusses, the counters, suspenders and two panels of the lower chord, at each end, must be latticed; all other tension members must be connected by batten plates or latticed.

Eye-bars.

125. The eye-bars composing a member shall be so arranged that adjacent bars shall not have their surfaces in contact; they shall be as nearly parallel to the axis of the truss as possible, the maximum inclination of any bar being limited to one inch in 16 ft.

126. In special cases, where floor beam hangers may be permitted, they must be rigidly attached to the trusses, and be so arranged as to stay the floor beams firmly against rotation or end motion.

Pony trusses.

127. Pony trusses shall be riveted structures, with double webbed chords, and shall have all web members latticed or otherwise effectively stiffened.

Buckled plates.

128. Buckled plates must be firmly riveted to the supporting beams and be spliced at all free edges. Preferably they will be made in continuous sheets of panel lengths. They may be pressed or formed without heating. (19)

129. A buckled-plate floor, as specified, may be considered as the required lateral system of bracing at the floor level.

WORKMANSHIP

130. All parts forming a structure shall be built in accordance with approved drawings. The workmanship and finish shall be equal to the best practice in modern bridge works. Material arriving from the mills shall be protected from the weather and shall have clean surfaces before being worked in the shops.

Straightening.

131. Material shall be thoroughly straightened in the shop, by methods that will not injure it, before being laid off or worked in any way.

Finish.

132. Shearing and chipping shall be neatly and accurately done and all portions of the work exposed to view neatly finished.

Rivets.

133. The size of rivets called for on the plans shall be understood to mean the actual size of the cold rivet before heating.

Reaming.

134. Steel may be used in tension without reaming of punched holes up to $\frac{5}{8}$ inch in thickness and may be used in compression without reaming up to $\frac{3}{4}$ inch in thickness.

Punching.

135. Where reaming is not required the diameter of the punch shall not be more than 1/16 inch greater than the diameter of the rivet, nor the diameter of the die more than $\frac{1}{8}$ inch greater than the diameter of the punch.

136. Punching shall be accurately done. Drifting to enlarge unfair holes will not be allowed. If the holes must be enlarged to admit the rivet, they shall be reamed. Poor matching of holes will be cause for rejection.

137. Where sub-punching and reaming are required the punched holes shall be at least 1/16 inch smaller than the nominal diameter of the rivet and the holes shall then be reamed to a diameter not more than 1/16 inch greater than the nominal diameter of the rivet.

138. Where reaming is required it shall be done after the pieces forming one built member are assembled and firmly bolted together. No interchange of reamed parts will be permitted.

139. Reaming shall be done with twist drills and without using any lubricant.

140. The outside burrs on reamed holes shall be removed to the extent of making a 1/16 in. fillet.

Assembling.

141. Riveted members shall have all parts well pinned up and firmly drawn together with bolts, before riveting is commenced. Contact surfaces are to be painted. (163)

Lattice bars.

142. Lattice bars shall have neatly rounded ends, unless otherwise called for.

Stiffeners.

143. Stiffeners shall fit neatly between flanges of girders. Where tight fits are called for, the ends of the stiffeners shall be faced and shall be brought to a true contact bearing with the flange angles.

Fillers.

144. Web splice plates and fillers under stiffeners shall be cut to fit within $\frac{1}{8}$ in. of flange angles.

Web plates.

145. Web plates of girders which have no cover plates, shall be flush with the backs of angles or project above the same not more than $\frac{1}{8}$ in.

unless otherwise called for. When web plates are spliced, not more than $\frac{1}{4}$ in. clearance between ends of plates will be allowed.

Floor beams and stringers.

146. The main section of floor beams and stringers shall be milled to exact length after riveting and the connection angles accurately set flush and true to the milled ends.

Riveting.

147. Rivets shall be uniformly heated to a light cherry red heat in a gas or oil furnace so constructed that it can be adjusted to the proper temperature. They shall be driven by pressure tools wherever possible. Pneumatic hammers shall be used in preference to hand driving.

148. Rivets shall look neat and finished, with heads of approved shape, full and of equal size. They shall be central on shank and grip the assembled parts firmly. Recupping and calking will not be allowed. Loose, burned or otherwise defective rivets shall be cut out and replaced. In cutting out rivets great care shall be taken not to injure the adjacent metal. If necessary, they shall be drilled out.

149. The several pieces forming one built member shall be straight and fit closely together, and finished members shall be free from twists, bends or open joints.

Joints.

150. Abutting joints shall be cut or dressed true and straight and fitted close together, especially where open to view. In compression joints depending on contact bearing, the surfaces shall be truly faced, so as to have even bearings after they are riveted up complete and when perfectly aligned.

Eye-bars.

151. Eye-bars shall be straight and true to size, and shall be free from twists, folds in the neck or head, or any other defect. Heads shall be made by upsetting, rolling or forging. Welding will not be allowed. The forms of heads will be determined by the dies in use at the works where the eye-bars are made, if satisfactory to the engineer, but the manufacturer shall guarantee the bars to break in the body when tested to rupture. The thickness of head and neck shall not vary more than 1/16 in. from that specified.

152. Before boring, each eye-bar shall be properly annealed and carefully straightened. Pin-holes shall be in the center line of bars and in the center of heads. Bars of the same length shall be bored so accurately that, when placed together, pins 1/32 in. smaller in diameter than the pin-holes can be passed through the holes at both ends of the bars at the same time without forcing.

Pin-holes.

153. Pin-holes shall be bored true to gages, smooth and straight; at right angles to the axis of the member and parallel to each other, unless

otherwise called for. The boring shall be done after the member is riveted up.

154. The distance center to center of pin-holes shall be correct within 1/32 in., and the diameter of the holes not more than 1/50 in., larger than that of the pin, for pins up to 5 in., in diameter and 1/32 in., for larger pins.

Pins and rollers.

155. Pins and rollers shall be accurately turned to gages and shall be straight and smooth and entirely free from flaws.

Screw threads.

156. Screw threads shall make tight fits in the nuts and shall be U. S. standard, except above the diameter of $1\frac{3}{8}$ in., when they shall be made with six threads per inch.

Annealing.

157. Eye-bars, all forgings and any pieces which have been partially heated or bent cold must be wholly annealed. Crimped stiffeners need not be annealed.

158. Steel castings shall be free from large or injurious blowholes and shall be annealed.

Welds.

159. Welds in steel will not be allowed.

Bed plates.

160. Expansion bed plates shall be planed true and smooth. Cast wall plates shall be planed top and bottom. The finishing cut of the planing tool shall be fine and correspond with the direction of expansion.

Pilot nuts.

161. Pilot and driving nuts shall be furnished for each size of pin, in such numbers as may be ordered.

PAINTING

Cleaning.

162. Steel work, before leaving the shop, shall be thoroughly cleaned and given one good coating of pure linseed oil, or such paint as may be called for, well worked into all joints and open spaces.

Contact surfaces.

163. In riveted work, the surfaces coming in contact shall each be painted before being riveted together.

Inaccessible surfaces.

164. Pieces and parts which are not accessible for painting after erection, including tops of stringers, eye-bar heads, ends of posts and chords, etc., shall have an additional coat of paint before leaving the shop.

165. Painting shall be done only when the surface of the metal is perfectly dry. It shall not be done in wet or freezing weather, unless protected under cover.

Machined surfaces.

166. Machine-finished surfaces shall be coated with white lead and tallow before shipment or before being put out into the open air.

Buckled plates.

167. Buckled plates shall have a thick and thorough coating of red lead and linseed oil before shipment. All rivet heads and scarred places shall also be coated with this red lead as soon as practicable after erection.

Field Painting.

168. After the steel work is erected it shall be thoroughly cleaned of all dirt, rust, scale, or grease and given two additional coats of paint as specified below. The first field coat is to be pure red lead and pure raw linseed oil mixed in the proportion of 20 lbs. of lead to one gallon of oil. The second coat is to be a pure graphite, ground in pure raw linseed oil of color to be selected by the County Commissioners. The first coat must be thoroughly dry before the second coat is applied.

ERECTION

169. The contractor, unless it be otherwise specified, shall furnish all staging and false work, shall erect and adjust all the metal work, and put in place all floor timbers, guards, etc., complete.

Contractor's responsibility.

170. The contractor shall so conduct all his operations as not to interfere with the work of other contractors, or close any thoroughfare by land or water, except by written consent of the *County Commissioners or other proper authority.*

171. The contractor shall assume all risks of accident to men or material prior to the acceptance of the finished structure. The contractor must also remove all false work, piling and other obstructions, or unsightly material produced by his operations.

INSPECTION

172. The manufacturer shall furnish all facilities for inspecting and testing the weight and quality of workmanship at the shop where material is manufactured. He shall furnish a suitable testing machine for testing full-sized members, if required.

173. The purchaser shall be notified well in advance of the start of the work in the shop, in order that he may have an inspector on hand to inspect material and workmanship.

174. When an inspector is furnished by the purchaser, he shall have full access, at all times, to all parts of the shop where material under his inspection is being manufactured.

175. The inspector shall stamp each piece accepted with a private mark. Any piece not so marked may be rejected at any time and at any stage of the work. If the inspector, through an oversight or otherwise, has accepted material or work which is defective or contrary to the specifications, this material, no matter in what state of completion, may be rejected by the purchaser.

176. Complete copies of shipping invoices shall be furnished to the purchaser with each shipment. These shall show the scale weights of individual pieces.

Final tests.

177. Before the final acceptance the Engineer may make a thorough test by passing over each structure the specified loads or their equivalent, or by resting the maximum load upon the structure for twelve hours. After such tests the structures must return to their original positions without showing any permanent change in any of their parts.

MATERIAL

Steel.

178. All steel must be made by the open hearth process. The phosphorus must not exceed 0.08 of one per cent for steel made by the acid method, or 0.04 for steel by the basic method.

179. The steel must be uniform in character for each specified kind. The finished bars, plates and shapes must be free from injurious seams or flaws, cracks on the faces or corners, or other defects, and have a clean, smooth finish. No work shall be put upon any steel at or near the blue temperature or between that of boiling water and of ignition of hard-wood sawdust.

180. The tensile strength, elastic limit and ductility shall be determined by samples cut from the finished material after rolling. The samples to be at least 12 inches long, and to have a uniform sectional area not less than $\frac{1}{2}$ square inch.

181. Material which is to be used without annealing or further treatment is to be tested in the condition in which it comes from the rolls. When material is to be annealed or otherwise treated before use, the specimen representing such material is to be similarly treated before testing, for tensile strength. The elongation shall be measured on an original length of 8 inches. At least two test pieces shall be taken from each melt or blow of finished material, one for tension and one for bending.

182. All samples or full-sized pieces must show uniform fine grained fractures of a blue steel-gray color, entirely free from fiery luster or a blackish cast.

Structural steel.

183. Structural steel shall have an ultimate strength, when tested in samples of the dimensions above stated, of 60,000 to 70,000 pounds per square inch, an elastic limit of not less than one-half of the ultimate strength, and a minimum elongation of 20 per cent. in 8 inches. But for eye-bar

material, not over 20 per cent. of the material must run below 62,000 or above 68,000 pounds per square inch. Steel for pins may have a minimum elongation of 15 per cent.

184. Before or after heating to a low cherry red and cooling in water at 82 degrees Fahr., this steel must stand bending to a curve whose inner radius is one and a half times the thickness of the sample, without cracking.

Eye-bars.

185. Eye-bar material, $1\frac{1}{2}$ inches and less in thickness, shall on test pieces cut from finished material, fill the above requirements. For thickness greater than $1\frac{1}{2}$ inches, there will be allowed a reduction in the percentage of elongation of 1 per cent. for each $\frac{1}{4}$ of an inch increase of thickness, to a minimum of 18 per cent. No bars over 2 inches in thickness will be used, except by special permission.

186. Full-sized eye-bars shall show not less than 10 per cent. elongation in the body of the bar, and an ultimate strength not less than 56,000 pounds per square inch. Should a bar break in the head, but develop 10 per cent. elongation and the ultimate strength specified, it shall not be cause for rejection, provided that not more than $\frac{1}{3}$ of the total number of bars tested break in the head. (151)

187. Full-sized material for eye-bars shall bend cold 180° to a curve, whose inner radius is equal to the thickness of the material, without fracture on the outside of the bend.

Pins.

188. Pins over 7 inches in diameter shall be forged. Blooms for pins shall have at least three times the sectional area of the finished pins.

Rivet steel.

189. Rivet steel shall have an ultimate strength of 48,000 to 58,000 pounds per square inch, an elastic limit not less than one-half the ultimate strength and a minimum elongation of 23 per cent. in 8 inches.

190. The steel for rivets must, under the above bending test, stand closing solidly together without sign of fracture. When nicked and bent around a bar of its own diameter it shall break gradually and give a fine, uniform, silky fracture.

Variation in weight.

191. A variation of cross-section or weight in the finished members of $2\frac{1}{2}$ per cent. from the specified size may be cause for rejection.

192. Steel castings will be used for drawbridge wheels, track segments and gearing. They must be true to form and dimensions, of a workmanlike finish and free from injurious blowholes and defects. All castings must be annealed.

When tested in specimens of uniform sectional area of at least $\frac{1}{2}$ square inch for a distance of two inches, they must show an ultimate strength of not less than 67,000 pounds per sq. in., an elastic limit of one-half the ultimate strength, and an elongation in 2 inches of not less than 10 per cent.

The metal must be uniform in character, free from hard or soft spots, and be capable of being properly tool finished.

193. Except where cast steel or chilled iron is required, all castings must be of tough, gray iron, free from cold shuts or injurious blowholes, true to form and thickness, and of workmanlike finish. Sample pieces, 1 inch square cast from the same heat of metal in sand moulds, shall be capable of sustaining, on a clear span of twelve inches, a central load of 2,400 pounds, when tested in the rough bar. A blow from a hammer shall produce an indentation on a rectangular edge of the casting without flaking the metal.

INDEX

	Art.	Page
Adding Machines	5	9
Angles—maximum lengths	44	100
Bearing plates for plate girder	44	109
Bending of chords due to weight	50	123
Bolsters for plate girder	44	109
Books of reference	83	200
Bottom Lateral Bracing	62	152
Box girders	34	72
Building construction	26	48
Buildings with columns	32	61
Built tension members	49	117
Butt joints	14	22
Button head rivets	9	16
Calculation of joists	78	186
Calculation of pins	67	160
Camber	68	167
Chords—Design of	57	136
—Location of pins	70	171
Classes of structural steel work	1	1
Clearances	85	209
Columns	50	119
—Mill buildings with	32	61
—stresses in	32	62
Compression and bending combined	50	119
Compression members	50	119
—Allowance for rivet holes	15	24
—Design of	57	133
—Width of	57	135
Contracts and proposals	3	2
Corrugated iron or steel	24	45
Countersunk rivets	9	16
Countersunk rivet values	17	29
Dead load	53	125
—for plate girder bridge	44	91
—of truss bridges	48	117
Dead loads—Roof	27	50

	Art.	Page
Deck plate girder bridge design	44	90
estimate	44	110
stress sheet	44	112
Depth of truss	54	125
Depth of trusses	47	115
Design of chords	57	136
compression members	57	133
end posts	58	140
deck plate girder bridge	44	90
floor beam	60	146
mill building	29	53
pin-connected bridge	52	125
portal	59	144
riveted connections	17	28
roof purlins	30	54
roof truss	31	57
a stringer	43	84
tension members	56	129
Designing and estimating	4	3
Designing and estimating	Chap. I	1
Detail drawings	65	159
Details—Duplication of	85	207
floor beams	72	177
hip joint	70	171
pin-connected bridges	Chap. VI	159
a riveted tension member	69	168
Distribution of loads	77	186
Dolly	11	19
Drafting department	82	195
Draftsman's equipment	83	196
Drawing boards	82	196
instruments	83	197
pencils	83	198
room light	82	196
table	82	196
Drawings for roof trusses	33	64
Drawing of roof truss	..	70
Drift pins	10	18
Driving rivets	11	18
Eccentricity of pins in chord members	50	123
Economic depth of girders	38	76
girders	43	85
girders	44	95
trusses	47	115
Effective depth of plate girders	37	76
End floor beam	60	148
End posts—Design of	58	140

	Art.	Page
End posts—Lacing	71	176
Equivalent loads	48	116
Erection	81	194
Erection and manufacture	Chap. VIII	193
Estimate for deck plate girder bridge	44	110
for pin connected bridge	64	154
of weight of stringers	43	89
Estimates of cost	4	3
Estimates—Forms of	4	5
Estimating and designing	4	3
Estimating and designing	Chap. I	1
—Order of	6	9
—Order for highway bridges	6	11
—Order for railway bridges	6	10
—Order for steel buildings	6	12
Eye bars	49	117
False work	81	194
Field riveting	81	195
Field rivet values	17	29
Flange plates of plate girders	44	96
riveting in plate girders	41	80
riveting in plate girders	43	87
riveting in plate girders	44	98
sections	34	72
splices in plate girders	42	83
splices in plate girders	44	100
Flanges of girders	37	75
girders	43	86
girders	44	95
Floor beams—Details	72	177
—Details	72	180
—Design	60	146
Floor—Design of, for bridge	44	90
Flooring materials	74	183
creosoted wood block floor	74	184
macadam	74	184
plank floors with steel joists	74	183
Freight	89	218
Gallows frame	81	194
General plans	8	14
Girders	Chap. IV	72
—Economic depth	38	76
—Effective depth	37	76
—The flanges	37	75
—Flange riveting	40	80
—Flange splices	42	83
—Maximum lengths	34	72

	Art.	Page
Girders—Moment of resistance	35	73
—Shear distribution	36	74
—Stiffeners	39	78
—Stresses	35	73
—Stresses	43	86
—Stresses	44	92
—The web	36	73
—Web splices	40	79
Grip of rivets	9	16
Heating rivets	11	19
Highway bridges	Chap. VII	182
—artistic effects in	73	183
Calculation of joists	78	168
Distribution of load	77	186
Flooring materials	74	183
Impact	76	185
Kinds of bridges	73	182
—loads	75	184
—Types of steel highway bridges	79	191
Hip joint—Detail of	70	174
pin	67	171
Impact	76	185
Inertia—Moment of	57	138
Inspection	91	224
Intermediate posts—Lacing	71	177
Jack rafters	26	48
Joints—Butt	14	22
—Lap	14	22
Kinds of Highway Bridges	73	182
Lacing of compression members	50	122
compression members	71	173
Lap joints	14	22
Laterals—Bottom	62	152
Lateral bracing of plate girders	44	104
stringers	43	89
Lateral systems	51	124
Laterals—Top	61	151
Loads	48	116
Loads for highway bridges	75	184
Loads—Roof	27	50
Location of pins in top chord and end posts	70	171
Macadam floor	74	184
Manufacture and erection	Chap. VIII	193
Materials	90	219
Material orders	84	200
Mill Buildings	Chap. III	45
—Design of a	29	53

	Art.	Page
Moment in deck plate girder	44	92
Moment of inertia	57	138
Moment of resistance of plate girder	35	73
Net sections of tension members	19	35
Order of estimating	6	9
highway bridges	6	11
railway bridges	6	10
steel buildings	6	12
Order of procedure for a pin connected bridge	86	211
for plate girder bridge	87	213
Ordering material	84	200
Packing	66	160
Packing at various joints	67	166
Panel lengths	47	115
Pins	66	159
Pins—Calculation of	67	160
Pin-connected bridges	Chap. V	115
—Design of	52	125
details of	Chap. VI	159
—Estimate	64	158
—Order of procedure for	86	211
stresses	55	127
—Stress sheet	64	158
Pins—Location in top chord and end posts	70	171
Pin plates	18	31
Pin plates	18	30
Pitch of rivets defined	13	21
Pitch of roofs	24	46
Plank floor on steel joists	74	183
Plans—General	8	14
Plans—Show	8	15
Plate girder bridges	Chap. IV	72
Plate girder bridges—Order of procedure	87	213
Plate girder design	44	90
Plate girders—Economic depth	38	76
—Economic depth	43	85
—Economic depth	44	95
—Effective depth	37	76
—Effective depth	43	87
—Effective depth	44	95
—Flanges	37	75
—Flanges	43	86
—Flanges	44	95
—Flange plates	44	96
—Flange riveting	41	80
—Flange riveting	43	87
—Flange riveting	44	98

	Art.	Page
Plate girders—Flange splices	42	83
—Flange splices	44	100
—Highway design	..	190
—Lateral bracing	44	104
—Maximum moment	44	92
—Stiffeners	39	78
—Stiffeners	43	88
—Stiffeners	44	100
—Stresses	35	73
—Stresses	43	86
—Stresses	44	92
—Web	36	73
—Web	43	86
—Web	44	95
—Web splices	40	79
—Web splices	44	101
Plates—Sizes of	84	202
Pony trusses	47	116
—design for highway	..	189
Portal Bracing	59	144
Proposals and contracts	3	2
Purlins	30	53
—arrangement of, at ridge	30	56
Radius of gyration	57	135
Rafter design, for a roof truss	31	60
Reaming	10	17
Rivet holes	10	17
—Allowance for in compression members	15	24
in tension members	19	35
Rivet pitch in flanges of girders	41	81
Rivet spacing	85	208
Rivet values—Cooper's	72	178
Riveted joints—Alternating stresses	15	25
—Alternating stresses	16	28
—Assumption made in design of	15	24
—Design of	17	28
—Examples	18	30
—Friction in	15	25
—Kinds of	14	22
—Manner of failure	17	28
—Requirements for good	16	27
—Slip in	15	25
Riveted tension member details	69	168
Riveted truss bridges	86	213
—Design, highway bridge	..	192
Riveting	Chap. II	16
—Design of joints in a roof truss	33	64

	Art.	Page
Riveting of flanges of plate girders	41	80
of flanges of plate girders	43	87
of flanges of plate girders	44	98
machines	11	19
of pin plates	18	30
of pin plates	18	31
—Theory of	15	23
Rivets—American Bridge Co.'s standard	9	16
—Bending in	15	26
—Button heads	9	16
—Conventional signs for	21	43
—Cooper's rivet values	72	178
—Countersunk	9	16
—Dimensions of	9	16
—Driving	11	18
—Field values	17	29
—Grip	9	16
—Heating	11	19
—Initial tension in	15	25
—Length required	9	16
—Shape of heads	9	16
—Proper sizes	12	20
—Spacing of	13	20
—Values of countersunk	17	29
—Working stresses	17	28
Rollers	63	153
Roofs	22	45
—Building construction	26	48
—Construction	23	45
—Coverings	24	45
—Dead load	27	50
—Design of	31	57
loads	27	50
pitch for various coverings	24	46
Roof purlins	30	53
—design of	30	54
rafters	23	45
—sheathing	23	45
—sheeting	23	45
truss drawings	33	64
truss drawing	33	70
trusses—Types of	25	46
Scales	83	198
for roof truss drawing	33	67
for shop drawing	86	212
Shear—Distribution over cross-section of girder	36	73
Shear in girders	36	74

	Art.	Page
Shear in girders	43	86
Shear in girders	44	93
Shipment	89	218
Shoes for plate girder	44	109
Shoes and rollers	63	153
Shop bills	88	216
Shop drawings	85	203
drawings—Methods of working up	85	203
drawings—Notes on	85	207
drawings for roof truss	33	64
drawings for roof truss	33	70
drawings—Titles on	85	205
Shop operations	80	193
Shops—Kinds of	2	2
Show plans	8	15
Signs for rivets on drawings	21	43
Sizes of rivets	9	17
Sizes of rivets	12	20
Slide rules	5	8
—Duplex	5	8
—Engineer's	5	8
—Fuller's	5	8
—Manheim	5	8
—Rule for operation of	5	9
—Thacher's	5	8
—Three multiple	5	8
Snap for rivet heads	11	19
Snow loads	27	51
Solid floors	45	114
Spacing of rivets	13	20
Specifications	7	13
–for bridge superstructures	..	225
Splices in flanges of plate girders	44	100
—Flanges of girders	42	83
in webs of plate girders	40	79
in webs of plate girders	44	101
Steel—Acid	90	221
—Basic	90	221
—Bessemer	90	220
—Effect of carbon	90	220
—Open hearth	90	220
—Physical characteristics	90	219
—Process of manufacture	90	220
—Specifications for	90	220
—Tests of	90	222
Stiffeners	87	214
Stiffeners	39	78

	Art.	Page
Stiffeners	43	88
Stiffeners	44	100
Stiffeners—Crimped	39	79
Stress sheets	8	14
for deck plate girder bridge	44	112
for pin connected bridge	64	157
for a roof	32	62
Stresses in columns of mill buildings	32	62
in girders	35	73
in girders	43	84
in girders	44	92
in pin connected bridge	55	127
in roof trusses	28	52
in roof trusses	28	52
in trusses of bridge due to wind	55	127
Stringer—Design	43	84
—Estimate of weight	43	89
laterals	43	89
Structural steel—Classes of	1	1
Templets	80	193
Tension members	49	117
—Built	56	129
—Details of riveted	69	168
—Design of	56	129
—Net sections	19	35
Tension on rivet heads	15	25
Tests of steel	90	222
Theory of riveting	15	23
Through plate girders	45	113
Ties—Design of, for bridge	44	107
Tie rods	22	45
Time savers	5	8
Titles on shop drawings	85	205
Top chord—Lacing	71	173
Top lateral bracing	61	151
Tracing linen	85	203
Traveler	81	194
Trusses—Types of	47	115
Types of plate girder flanges	34	72
Types of roof trusses	25	46
Types of steel highway bridges	79	191
Types of trusses	47	115
Webs of girders	36	73
of girders	43	85
of girders	44	95
—Moment of resistance	36	75
—Moment of resistance	37	75

	Art.	Page
Webs splices in plate girders	40	79
splices in plate girders	44	101
Wheel guards	74	184
Width of compression members	57	135
Wind pressure	27	50



6000 x 9 = 45000#

Page 168

2 5 14 x 3/8

Sq. cut. = (14 - 2) 3/8 = 4.5 □" flat

Zig Zag cut = 2 1/8 + 4.16 + 5 1/4 + 4.16 + 2 1/8 = 5.19

4 L 6 x 3 1/2 x 1/2

Sq. cut. = (9 - 1) 1/2 = 4 □"

Zig Zag thru 2 holes = (1 1/2 + 6.32 + 1 1/2) - 2 = 7.32

3.66 □" (the last)

" " " 3 holes = (1 1/2 + 4.16 + 4.04 + 1 1/2) - 3 = 8.24

2 x 4 1/2 = 9.00

4 x 3.66 = 14.64

23.64